


P.O. Box 92
 810 E 7TH
 EUREKA, KS 67045
 (620) 583-5561



**Cementing & Acidizing
 of Kansas, LLC**



Cement or Acid Field Report
 Ticket No. 980
 Foreman KEVIN MCCOY
 Camp EUREKA

Cement & Acid Field Report

Date	Customer ID #	Lease & Well Number	Section	Township	Range	County	State
12/4/13	1003	BAKER # BD-3	4	24S	18E	ALLEN	KS
Customer COLT ENERGY, INC			Unit #		Driver		Unit #
Mailing Address P.O. Box 388			102		SHANNON F.		
City TOLA			111		RICK L.		
State KS	Zip Code 66749	Safety Meeting KM SF AL					Driver

Job Type Plug BACK Hole Depth 987' Slurry Vol. _____ Tubing 2 3/8 Euc
 Casing Depth _____ Hole Size _____ Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 4 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting: Rig up to 2 3/8 Tubing. BREAK Circulation w/ FRESH water. WASH down to Firm TD of 987' Spot 15 sks Class "A" Cement w/ 2% Gel, 1% CaCl2, 2* PhenoSeal/sk ON TD. Pull Tubing up 14'. Circulate Excess Cement out of hole. Job Complete. Rig down.


Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 106	1	Pump Charge	200.00	200.00
C 107	0	Mileage 4 WELL OF 4	0	N/C
C 108 A	.47 TONS	Ton Mileage	1/2 M/C	172.50
C 200	15 SKS	CLASS "A" Cement	15.00	225.00
C 206	30 *	Gel 2%	.20	6.00
C 205	15 *	CaCl2 1%	.60	9.00
C 208	30 *	Pheno Seal 2*/sk	1.25	37.50
			Sub Total	650.00
			Sales Tax	20.54
Authorization <u>[Signature]</u> Title _____			Total	670.54

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561

Elite

**Cementing & Acidizing
 of Kansas, LLC**



Cement or Acid Field Report
 Ticket No. **1031**
 Foreman KEVIN MCCOY
 Camp EUREKA

ARI # 15-001-30584 ✓

Date	Customer ID #	Lease & Well Number		Section	Township	Range	County	State
12/27/13	1003	BAKER RD-3		4	24S	18E	ALLEN	KS
Customer <u>Colt Energy</u>				Unit #		Driver		State
Mailing Address <u>P.O. Box 388</u>				102		SHANNON F.		KS
City <u>Iola</u>				111		RICK L.		
State <u>KS</u>		Zip Code <u>66749</u>						
Safety Meeting <u>KM SF R</u>								

Job Type Plug BACK (MISC Pump) Hole Depth 987' Slurry Vol. 4 BBL Tubing 2 3/8"
 Casing Depth 955' Hole Size _____ Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 4 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement 3 BBL Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting: Ran 2 3/8 Tubing to 984'. Break Circulation w/ Fresh water. Spot 15 sacks Class A Cement w/ 2% G&L @ 984'. Pull Tubing up to 942'. Back wash excess Cement out of hole. Job Complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 106	1 1/2	Pump Charge	200.00	300.00
C 107	0	Mileage 2 nd well of 2	0	N/C
C 200	15 Sks	CLASS "A" Cement	15.00	225.00
C 206	30 #	G&L 2%	.20 #	6.00
C 108 A	.70 TONS	TON Mileage	M/C	345.00
			Sub Total	876.00
			Sales Tax	17.09
			Total	893.09

Authorization *R. R. Adkins* Title _____
 THANK YOU
 AT 7.4%

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.