

Use:	HENNING	
Owner:	DIAMOND B MIAMI FLOOD Ltd.	
OPR #:	5876	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface: 20' of 7"	Cemented: 5 Sacks	Hole Size: 9 7/8"
Longstring: 698'2 7/8"8RD	Cemented: 110	Hole Size: 5 5/8

Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 913-795-2991



Well #: EH-11
Location: NW,NE,SE,NW,S23,T16,R21
County: MIAMI
FSL:3898
FEL: 2980
API#: 15-121-29539-00-00
Started: 7/22/13
Completed: 7/23/13

SN: NONE	Packer:	TD: 710'
Plugged:	Bottom Plug:	

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
2	2	TOP SOIL	1	496	BLACK SHALE
8	10	CLAY	20	516	SHALE
7	17	LIME	2	518	LIME
11	28	SHALE	9	527	SHALE
17	45	LIME	6	533	LIME
2	47	SHALE	28	561	SHALE
6	53	RED BED	2	563	COAL
3	56	SHALE	7	570	SHALE (LIMEY)
10	66	SAND (DRY)	5	575	LIME
9	75	SHALE	13	588	SHALE
15	90	LIME	4	592	LIME
26	116	SANDY SHALE (FLOWING WATER)	3	595	COAL
59	175	SHALE	12	607	SHALE(LIMEY)
20	195	LIME	5	612	LIME
7	202	SHALE	3	615	SHALE
13	215	SAND(DRY)	3	618	LIME
12	227	SHALE	3	621	SHALE
6	233	LIME	2	623	BLACK SHALE
1	234	BLACK SHALE	10	633	SHALE
15	249	SHALE	1	634	LIME
8	257	SAND(DRY)	4	638	SHALE
7	264	SHALE	1	639	SHALE(OIL SAND STRK)
6	270	LIME	2	641	OIL SAND (SOME SHALE)(POOR BLEED)
6	276	SHALE	3	644	OIL SAND (SOME SHALE)FAIR BLEED)
1	277	LIME	1	645	LIME
13	290	SHALE	2	647	OIL SAND (SHALEY)(GOOD BLEED)
10	300	LIME	3	650	OIL SAND (VERY SHALEY)(POOR BLEED)(WATER)
2	302	SHALE	3	653	OIL SAND(SOME SHALE)(FAIR BLEED)
14	316	LIME	3	656	SHALE(OIL SAND STRK.)
4	320	BLACK SHALE	2	658	OIL SAND(SOME SHALE)(FAIR BLEED)
4	324	SHALE	3	661	SHALE(OIL SAND STRK)
23	347	LIME	26	687	SHALE
4	351	BLACK SHALE	1	688	LIME
5	356	LIME	10	698	SHALE
3	359	SHALE	3	701	SHALE(OIL SAND STRK)
5	364	LIME	3	704	OIL SAND (FAIR BLEED)(SHALEY)
13	387	SHALE	3	707	SANDY SHALE(OIL SAND STRK)(FAIR BLEED)
19	406	SAND (WATER IRON)	TD	710	DARK SHALE
67	473	SHALE			SURFACE 7/22/13 LONGSTRING 695' 27/8" 8RD TD 710'
8	481	SANDY SHALE			SET TIME 5:00P.M. SET TIME 3:30P.M. 7/23/13
14	495	SHALE			CALLED 2:40 BROOKE CALLED 2:10P.M. BROOKE