


810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561

**Elite**

**Cementing & Acidizing  
 of Kansas, LLC**

APZ# 15-001-30832 ✓



**Cement or Acid Field Report**

Ticket No. **1101**

Foreman Kevin McCoy

Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
2/18/2014	1003	Conger # C11-i	14	25	19E	Allen	KS
Customer			Unit #	Driver	Unit #	Driver	
Colt Energy, Inc			102	SHANNON F.			
Mailing Address			111	RICK L.			
P.O. Box 388							
City	State	Zip Code					
Lola	KS	66749					

Job Type	Hole Depth	Slurry Vol.	Tubing
LONGSTAIR	970'	38	
Casing Depth	Hole Size	Slurry Wt.	Drill Pipe
950.45'	6.25"	13.7*	
Casing Size & Wt.	Cement Left in Casing	Water Gal/SK	Other
4.5" 10.5#	5'	9	
Displacement	Displacement PSI	Bump Plug to	BPM
15.2 BBL	500	1000 PSI	

Remarks: SAFETY Meeting: Rig up to 4 1/2 casing. Break Circulation w/ 5 BBL fresh water. Pump 6 SKS GEL FLUSH (300") w/ HULLS 5 BBL water SPACER. MIXED 115 SKS THICK SET CEMENT w/ 2" PhenoSeal /SK @ 13.7 #/GAL = 38 BBL SLURRY. wash out Pump & Lines. Shut down. Release Plug. Displace Plug to SEAT w/ 15.2 BBL fresh water. FINAL Pumping Pressure, 500 PSI. Bump Plug to 1000 PSI. Wait 2 mins. Release Pressure. Float Held. Shut casing in @ 0 PSI. Good Cement Return to SURFACE = 7 BBL SLURRY to Pit. Job Complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 102	1	Pump Charge	1050.00	1050.00
C 107	50	Mileage	3.95	197.50
C 201	115 SKS	THICK SET CEMENT	19.50	2242.50
C 208	230 #	PhenoSeal 2" /SK	1.25 #	287.50
C 206	300 #	Gel Flush	.20 #	60.00
C 214	40 #	Hulls	.45 #	18.00
C 108B	6.32 TONS	TOR MIKAGE 50 miles	1.35	426.60
C 403	1	4 1/2 Top Rubber Plug	45.00	45.00
			Sub Total	4327.10
			7.4% Sales Tax	196.32
Authorization <u>R.R. [Signature]</u> Title _____			Total	4523.42

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.