



# ALLIED OIL & GAS SERVICES, LLC 062172

Federal Tax I.D. # 20-8651475

REMIT TO P.O. BOX 93999  
SOUTHLAKE, TEXAS 76092

SERVICE POINT:  
Oakley KS

DATE <u>12-15-13</u>	SEC <u>20</u>	TWP <u>14</u>	RANGE <u>32</u>	CALLED OUT	ON LOCATION <u>9:00 a.m.</u>	JOB START <u>2:15 p.m.</u>	JOB FINISH <u>3:15 p.m.</u>
LEASE <u>Krebs L</u>	WELL # <u>1</u>	LOCATION <u>Oakley 22 S Winto</u>			COUNTY <u>Logan</u>	STATE <u>KS</u>	
OLD OR <u>NEW</u> (Circle one)							

CONTRACTOR <u>Am. Eagle</u>	OWNER <u>Same</u>
TYPE OF JOB <u>Production</u>	
HOLE SIZE <u>7 7/8</u>	T.D. <u>4523'</u>
CASING SIZE <u>5 1/2</u>	DEPTH <u>4513'</u>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL <u>Port Collar</u>	DEPTH <u>2207'</u>
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT <u>19.16'</u>
CEMENT LEFT IN CSG. <u>19.16'</u>	
PERFS.	
DISPLACEMENT <u>106.95 bbl water</u>	
EQUIPMENT	
PUMP TRUCK # <u>720</u>	CEMENTER <u>Paul Beaver</u>
BULK TRUCK # <u>600</u>	HELPER <u>Tyler Flipse</u>
BULK TRUCK #	DRIVER <u>Chris Helpingstine</u>
BULK TRUCK #	DRIVER

CEMENT			
AMOUNT ORDERED <u>230 sks ASC</u>			
<u>10% Salt 5# Gilsomite 2% gel</u>			
COMMON	@		
POZMIX	@		
GEL <u>4 sks</u>	@	<u>26.40</u>	<u>105.60</u>
CHLORIDE	@		
ASC <u>230 sks</u>	@	<u>20.90</u>	<u>4807.00</u>
Salt <u>24 sks</u>	@	<u>26.35</u>	<u>632.40</u>
Gilsomite <u>1150#</u>	@	<u>.98</u>	<u>1127.00</u>
Super flush <u>12 bbl</u>	@	<u>58.70</u>	<u>704.40</u>
KCL <u>2 gal</u>	@	<u>34.40</u>	<u>68.80</u>
HANDLING <u>294.35 ft<sup>3</sup></u>	@	<u>2.48</u>	<u>729.99</u>
MILEAGE <u>12.85 hrs x 25mi x 2.60</u>			<u>835.25</u>
TOTAL			<u>9010.44</u>

**REMARKS:**

Break circulation/drop ball, ball went through shoe @ 200#, circulate 1 hr.  
Mix 30 sks in R.H. mix 12 bbl super flush down casing, mix 200 sks down casing, wash up in pit, release plug + Displace w/ 20 bbl KCL water and 86.95 bbl fresh water plug did land @ 1500# w/ 800# lift pressure float did not  
Thank You! Paul + Tyler

**SERVICE**

DEPTH OF JOB	<u>4523'</u>
PUMP TRUCK CHARGE	<u>2765.75</u>
EXTRA FOOTAGE	@
MILEAGE MILV <u>25</u>	@ <u>7.70</u> <u>192.50</u>
MANIFOLD <u>Head</u>	@ <u>275.00</u>
MILV <u>25</u>	@ <u>4.40</u> <u>110.00</u>
TOTAL <u>3343.25</u>	

CHARGE TO: Black Tea  
STREET \_\_\_\_\_  
CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

**PLUG & FLOAT EQUIPMENT**

<u>Weatherford 5 1/8</u>		
Port Collar	@	<u>3042.00</u>
AFV Float shoe	@	<u>408.33</u>
Latchdown plug Assembly	@	<u>324.09</u>
Turbolizers <u>8</u>	@	<u>748.80</u>
Baskets <u>3</u>	@	<u>1182.87</u>
TOTAL		<u>5706.09</u>

To: Allied Oil & Gas Services, LLC.  
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

SALES TAX (If Any)	
TOTAL CHARGES	<u>18,059.78</u>
DISCOUNT <u>2,470.73</u>	IF PAID IN 30 DAYS
<u>\$15,589.04 Net.</u>	

PRINTED NAME \_\_\_\_\_  
SIGNATURE Paul Beaver