

810 E 7TH
PO Box 92
EUREKA, KS 67045
(620) 583-5561

Elite

**Cementing & Acidizing
of Kansas, LLC**



Cement or Acid Field Report
Ticket No. **1087**
Foreman Kevin McCoy
Camp EUREKA

API # 15-001-30833

Date	Customer ID #	Lease & Well Number		Section	Township	Range	County	State
2/14/14	1003	Conger # E9-1		14	25	19E	ALLEN	Ks
Customer			Safety Meeting KM SF RL	Unit #	Driver	Unit #	Driver	
Mailing Address				102	SHANNON F.			
City				111	RICK L.			
State								
City		State	Zip Code					
To/From		Ks	66749					

Job Type Longstring Hole Depth 960' Slurry Vol. 38 bbl Tubing _____
 Casing Depth 944.50 Hole Size 6 7/8" Slurry Wt. 13.7" Drill Pipe _____
 Casing Size & Wt. 4 1/2" 10.5" Cement Left in Casing 5' Water Gal/SK 9.0 Other _____
 Displacement 15.2 bbl Displacement PSI 450 Bump Plug to 1000 PSI BPM _____

Remarks: SAFETY Meeting: Rig up to 4 1/2 casing. BREAK Circulation w/ 5 bbl fresh water. Pump 6 SKS Gel Flush (300") w/ HULLS, 5 bbl water spacer. Mixed 115 SKS THICK SET Cement w/ 2" Pheno-SEAL/sk @ 13.7"/gal = 38 bbl slurry. wash out pump & lines. Shut down. Release Plug. Displace Plug to Seat w/ 15.2 bbl fresh water. FINAL Pumping Pressure 450 PSI. Bump Plug to 1000 PSI. WAIT 2 minutes. Release Pressure. FLOAT Held. Shut casing in @ 0 PSI. Good Cement Returns to Surface = 7 bbl slurry To Pt. Job Complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 102	1	Pump Charge	1050.00	1050.00
C 107	50	Mileage	3.95	197.50
C 201	115 SKS	THICK SET Cement	19.50	2242.50
C 208	230 "	PhenoSEAL 2"/SK	1.25 "	287.50
C 206	300 "	Gel Flush	.20 "	60.00
C 214	40 "	HULLS	.45 "	18.00
C 108B	6.32 Tons	Ton Mileage 50 miles	1.35	426.60
C 403	1	4 1/2 Top Rubber Plug	45.00	45.00
			Sub TOTAL	4327.10
			Sales Tax 7.4%	196.32
Authorization <u>R. R. Adlock</u> Title _____			Total	4523.42

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.