


810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



**Cementing & Acidizing
 of Kansas, LLC**



Cement or Acid Field Report

Ticket No. **1068**
 Foreman Kevin McCoy
 Camp EUREKA

API # 15-001-30837 ✓

Date	Customer ID #	Lease & Well Number		Section	Township	Range	County	State
1/30/14	1003	KNOX # V 9 - 1		14	25.5	19E	Allen	Ks
Customer Colt Energy, Inc.				Safety Meeting KM SF RL	Unit #	Driver	Unit #	Driver
Mailing Address P.O. Box 388					102	SHANNON F.		
City Toia					111	RICK L.		
State Ks		Zip Code 66749						

Job Type Longstring Hole Depth 961' Slurry Vol. 38 BBL Tubing _____
 Casing Depth 943' Hole Size _____ Slurry Wt. 13.7[#] Drill Pipe _____
 Casing Size & Wt. 4 1/2 10.5[#] Cement Left in Casing 5' Water Gal/SK 9.0 Other _____
 Displacement 15 BBL Displacement PSI 500 Bump Plug to 1000 PSI BPM _____

Remarks: Safety Meeting: Rig up to 4 1/2 casing. Break circulation w/ 20 BBL fresh water. Pump 300" (6 SKS) Gel flush w/ Hulls, 10 BBL water spacer. Mixed 115 SKS Thick Set Cement w/ 2" Phenoseal / SK @ 13.7[#]/GAL yield 1.85 = 38 BBL slurry. wash out pump & lines. Shut down. Release Plug. Displace Plug to seat w/ 15 BBL fresh water. Final Pumping Pressure 500 PSI. Bump Plug to 1000 PSI. Wait 2 mins. Release Pressure. Float Held. Shut casing in @ 0 PSI. Good Cement Returns to Surface = 6 BBL slurry to pit. Job Complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 102	1	Pump Charge	1050.00	1050.00
C 107	50	Mileage 1 ST well of 4	3.95	197.50
C 201	115 SKS	THICK SET Cement	19.50	2242.50
C 208	230 "	PhenoSeal 2"/SK	1.25 "	287.50
C 206	300 "	Gel Flush	.20 "	60.00
C 214	40 "	Hulls	.45 "	18.00
C 108 B	6.32 TONS	Ton Mileage 50 miles	1.35	426.60
C 403	1	4 1/2 Top Rubber Plug	45.00	45.00
THANK YOU			Sub Total	4327.10
7.4%			Sales Tax	176.32
Authorization <u>[Signature]</u>	Title _____	Total		4523.42

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.