

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561

**Elite**

**Cementing & Acidizing  
 of Kansas, LLC**

API # 15-001-30838



**Cement or Acid Field Report**

Ticket No. **1042**

Foreman Kevin McCoy

Camp EUREKA

Date	Customer ID #	Lease & Well Number	Section	Township	Range	County	State
1/15/14	1003	Knox # V10-1	23	25	19E	Allen	KS
Customer	Mailing Address	City	State	Zip Code	Safety Meeting	Unit #	Driver
Colt Energy, Inc	P.O. Box 388	Iola	KS	66749	Unit # 102 110	Shannon F. Rudy M.	

Job Type LONG STAIN Hole Depth 95.5 Slurry Vol. 38 BBL Tubing \_\_\_\_\_  
 Casing Depth 947.20 Hole Size 6 3/4" Slurry Wt. 13.7" Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 4 1/2, 10.5#/ft. Cement Left in Casing 5 Water Gal/SK 9.0 Other \_\_\_\_\_  
 Displacement 15 BBL Displacement PSI 500 Bump Plug to 1000 PSI BPM \_\_\_\_\_

Remarks: SAFETY Meeting: Rig up to 4 1/2 casing w/ wash head. Break circulation w/ fresh water. wash down 5'. Pump 6 SKS Gel flush w/ hulls. 10 BBL water spacer. shut down. Rig up Cement head. Pump 5 BBL dye water. mixed 115 SKS THICK SET Cement w/ 2" PhenoSeal/ft @ 13.7"/gal yield 1.85 = 38 BBL slurry. wash out pump & lines. shut down. Release plug. Displace plug to seat w/ 15 BBL fresh water. Final Pumping Pressure 500 PSI. Bump Plug to 1000 PSI. wait 2 mins. Release pressure. float held. shut casing in @ 0 PSI. Good cement returns to surface = 6 BBL slurry to pit. Job Complete. Rig down

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 102	1	Pump Charge	1050.00	1050.00
C 107	50	Mileage	3.95	197.50
C 201	115 SKS	THICK SET Cement	19.50	2242.50
C 208	230 #	PhenoSeal 2"/ft	1.25 #	287.50
C 206	300 #	Gel Flush	.20 #	60.00
C 214	40 #	Hulls	.45 #	18.00
C 108 B	6.32 Tons	Ton Mileage	1.35	426.60
C 403	1	4 1/2 Top Rubber Plug	45.00	45.00
<u>THANK YOU</u>			Sub Total	4327.10
<u>7.4%</u>			Sales Tax	196.32
Authorization <u>R. R. [Signature]</u>	Title _____	Total	4523.42	

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.