



CONSOLIDATED
Oil Well Services, LLC

263185

TICKET NUMBER 44347
LOCATION OAKLEY KS.
FOREMAN DAMON M. TRAINING
FUZZY

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

KANSAS

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10-12-13	6335	MACKEY 12-10 11-12	12	23	31 W	FINNEY
CUSTOMER <u>PETRO SANDTANDER</u>			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS			399	STEVEN		
CITY			528 F-127	COBY R		
STATE			529 F-129	TIM W.		
ZIP CODE						

JOB TYPE SURFACE HOLE SIZE 12 1/4 HOLE DEPTH 2045 CASING SIZE & WEIGHT 8 5/8 24#
 CASING DEPTH _____ DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT 12.5-14.7 SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT In CASING 41.09
 DISPLACEMENT 127.18 DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: SAFETY MEETING RIG UP ON TRINIDAD #216 Hookup and circulate. Mix 750 sks 65/35, 69ccal, 39cc, 1 1/4" flo seal Tail with 150 sks class A 39cc. Drop plug and displace 131 BBL. Cement did circulate approx 30 BBL to pit. Flood held

Thanks Damon

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
54015	1	PUMP CHARGE	1785.00	1785.00
5406	50	MILEAGE	5.25	262.50
5407A	39.68	TON MILEAGE DELIVERY	1.75	3472.00
11045	150 SKS	CLASS A CEMENT	18.55	2782.50
1102	2382*	CALCIUM CHLORIDE	.94	2239.08
1118B	4200*	BETONITE	.27	1134.00
1127A	750 SKS	65/35	16.00	12000.00
1107	182*	FLOSEAL	2.97	558.36
4411	1	8 5/8 RUBBER PLUG	141.75	141.75
4132	3	8 7/8 CENTRALIZERS	86.00	258.00
4204	1	8 5/8 GUIDE SHOE	524.00	524.00
4229	1	8 7/8 AFU INSERT	313.00	313.00
5117	1	MISCELLANEOUS	385.00	385.00
				25855.19
				258552.
				23269.07
			7.3%	SALES TAX 1310.75
				ESTIMATED TOTAL 24580.42

completed

Flavin 3737

AUTHORIZATION [Signature] TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



CONSOLIDATED
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

263255

TICKET NUMBER 44446
LOCATION OAKLEY KS.
FOREMAN DAMON M. TRAINING
Fuzzy

FIELD TICKET & TREATMENT REPORT

CEMENT

KANSAS

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10-16-13	6335	MACKAY 11-12	12	23	31 W	FINNEY
CUSTOMER		GARDEN CITY 6mi RD. E TO SCOTT RD INTO 7milers E Y25	TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS			399	TIM W		
CITY			460	JEREMYS		
STATE			RIDE ALONG	D.J.		
ZIP CODE						

JOB TYPE LONG STRING HOLE SIZE 7 7/8 HOLE DEPTH 4950 CASING SIZE & WEIGHT 5 1/2" #17 + 15.5"
 CASING DEPTH 4943.72 DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT 14.7 SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT IN CASING SHOE 20.9
 DISPLACEMENT 116.82 DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: SAFETY MEETING RIG UP ON TRINIDAD 216 RAW FLOAT EQUIPMENT
CENT. # 2, 4, 6, 8, 10, 12, 14, 16 RIG UP TO CIRCULATE FOR 1 HR.
ON BOTTOM. MIX MUD FLUSH THEN MIX 240 SKS OF OWC #5 KOLSEAL
1/4 OF 170 CFL-115 AND .14# DEFOMER SHUT DOWN WASHED UP RELEASED
THE PLUG PUMPED 116.82 BAR OF H2O PLUG LANDED 1900# RELEASED
PRESSURE IS DIED UP. WASHED UP AND RIGGED DOWN.

THANK YOU DAMON FUZZY

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
54210	1	PUMP CHARGE	3175.00	3175.00
5406	70	MILEAGE	5.25	367.50
5407A	11.28	TON MILEAGE DELIVERY	17.75	1381.80
1126	240 SKS	OWC	23.70	5688.00
1110A	1200 #	KOLSEAL	.56	672.00
1135A	56.4 #	FL-115	11.08	624.91
1146	33.6 #	CAF-38	10.20	342.72
4159	1	5 1/2 FLOAT SHOE (W)	433.75	433.75
4454	1	5 1/2 LATCH DOWN ASSY. (W)	318.25	318.25
4130	8	CENTRALIZERS (W)	61.00	488.00
11446	500 GAL	MUD FLUSH	1.00	500.00
				13991.93
			LESS 10% DISC	1399.19
			SUBTOTAL	12592.74
			7.3% SALES TAX	595.74
			ESTIMATED TOTAL	13188.48

completed

Revin 3737

AUTHORIZATION MJL

TITLE _____

DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.