



264881

TICKET NUMBER 44921
LOCATION Ottawa, KS
FOREMAN Casey Kennedy

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
12/13/13	7069	Reynolds # 25	SE 5	17	22	M
CUSTOMER Reusch Oil Well			TRUCK #		DRIVER	
MAILING ADDRESS PO Box 520			729		Cohen ✓ Safety Meeting	
CITY Ottawa			57		Garber ✓	
STATE KS			503		Dan Det ✓	
ZIP CODE 66067			675		Kei Det ✓	

JOB TYPE long string HOLE SIZE 5 7/8" HOLE DEPTH 740' CASING SIZE & WEIGHT 2 7/8" EUE
 CASING DEPTH 735' DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
 DISPLACEMENT 4.25 bbls DISPLACEMENT PSI _____ MIX PSI _____ RATE 4.5 bpm

REMARKS: had safety meeting, established circulation, mixed & pumped 100 # Premium Gel followed by 10 bbls fresh water, mixed & pumped 117 sls 50/50 Pozmix cement w/ 2% gel per sk, cement to surface, flushed pump clean, pumped 2 1/2" rubber plug to casing TD w/ 4.25 bbls fresh water, pressured to 800 psi, released pressure, shut in casing.

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE		1085.00
5406	20 mi	MILEAGE		84.00
5402	735'	casing footage		368.00
5407	minimum	ten mileage		180.00
5502C	2 hrs	80 Vac		
1124	117 sls	50/50 Pozmix cement		1345.50
1118B	297 #	Premium Gel		65.74
4402	1	2 1/2" rubber plug		29.50
			7.65%	SALES TAX
				ESTIMATED
				TOTAL
				110.19
				3267.53

Ravin 3737

AUTHORIZATION _____ TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form