


Dale Jackson Production Co.
Box 266, Mound City, Ks 66056



Cell # 620-363-2683

Office # 913-795-2991

Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 657' 27/8" 8 Round Pipe	Cemented: 80 Sacks	Hole Size: 5 5/8"

SN: 597 'FT	Packer:	TD: 670 ' FT.
-------------	---------	---------------

Plugged:	Bottom Plug:
Lease:	WENDT
Owner:	Bobcat Oilfield Services
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Well #: 12-14
Location: SW, NW, NE, SE- S27-T19S-R22E
County: LINN
FSL: 2145 'FT
FEL: 1155 'FT
API#: 15-107-24897 -00-00
Started: 3/28/2014
Completed: 3/31/2014

Well

Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	TOP SOIL	14	477	Shale
9	10	Lime & Shale	35	512	Lime (Shaley)
21	31	Shale	4	516	Shale
1	32	Black Shale	2	518	Lime
12	44	Shale	2	520	Shale
4	48	Lime	6	526	Black Shale
23	71	Shale	10	536	Shale (Limey)
1	72	Black Shale	1	537	Coal
23	95	Shale	5	542	Shale
10	105	Lime	9	551	Light Sandy Shale
10	115	Shale	18	569	Shale
37	152	Lime	1	570	Lime
2	154	Shale	15	585	Shale
3	157	Black Shale	1	586	Shale (Limey)
2	159	Shale	7	593	Shale
19	178	Lime	1.5	594.5	Sand (Slight Oder) (Some Shale)
3	181	Shale	1	595.5	Lime
2	183	Black Shale	2	597.5	Sandy Shale (Oil Sand Stk)
2	185	Lime	1.5	599	Lime
6	191	Shale (Limey)	5	604	Oil Sand (Shaley) (Good Bleed)
3	194	Lime	1	605	Sandy Shale (Oil Sand Stk)
14	208	Light Sandy Shale (Limey)	1	606	Sandy Shale (Slight Oder)
104	312	Shale	3	609	Sandy Shale
14	326	Light Sandy Shale	3	612	Shale
15	341	Shale	1	613	Coal
4	345	Black Shale	14	627	Shale
6	351	Shale	3	630	Black Shale
3	354	Lime	6	636	Shale (limey)
15	369	Shale	2	638	Sandy Shale
13	382	Lime	6	644	Sandy Shale (limey)
3	385	Shale	6	650	Sandy Shale
1	386	Light Sandy Shale	13	663	Black Shale
2	388	Sand (Dry) (Very Shaley)	7	670	Shale
1	389	Sandy Shale	TD	670	
20	409	Sand (Dry) (Some Shale)			SET SURFACE - 5:00 PM - 3/28/14
6	415	Sandy Shale			CALLED IN 3:34 PM - TALKED TO Michelle
16	431	Shale			LONGSTRING -657' FT 2 7/8" 8 ROUND PIPE
3	434	Coal			SET 3:30 PM - 3/31/14
4	438	Shale			CALLED IN 2:38 PM - TALKED TO Brooke
10	448	Lime			
10	458	Shale			
3	461	Lime			
2	463	Black Shale			



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 12-14
Location: SW,NW,NE,SE,S27,T19,R22E
County: LINN
FSL: 2145 S'FTY
FEL: 1155 E'FT.
API#: 15-107-24932-00-00
Started: 3/28/14
Completed: 3/31/14

Lease :	WENDT
Owner:	BOBCAT OILFIELD SERVICES INC
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	594	0:00	-----	Sand (Slight Oder) (Some Shale)	594.50
1	595	1:15	1.25	Lime	595.50
2	596	3:00	1.75	Sandy Shale (oil Sand Stk)	597.50
3	597	4:45	1.75		
4	598	6:30	1.75	Lime	599.00
5	599	7:45	1.75		
6	600	8:45	1	Oil Sand (Shaley) (Good Bleed)	
7	601	10:00	1.25		
8	602	11:15	1.25		
9	603	14:00	2.75		
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					



1/2 Mile North of Louisburg
 27295 Metcalf Rd.
 P.O. Box 729
 Louisburg, Kansas 66053
 913-837-2955 • 1-800-521-1764

MOSSMAN LUMBER COMPANY

True Value.

CUSTOMER NO.	JOB NO.	PURCHASE ORDER NO.	REFERENCE	TERMS	CLERK	DATE	TIME
251			ORDR # 78428	NET 10TH	RR	4/ 1/14	9:49

SOLD TO
 ROBERT OIL
 SUITE 103
 602 WEST ANITY
 LOUISBURG, KS 66053

SHIP TO
 11498 WEST 152 HWY

DEL. DATE: 3/28/14 TERM#551
 SLSPR: RR ROBERT RAND
 TAX : 001 LOUISBURG, KS
 DOC# 179096

 * INVOICE *

 ORDR 78428

QUANTITY		UM	SKU	DESCRIPTION	UNITS	PRICE/PER	EXTENSION
SHIPPED	ORDERED						
240		EA	FLYASH	80# SX FLY ASH CLASS C	240	5.45 /EA	1,308.00
280		EA	PORTLAND	94# PORTLAND CEMENT I/II	280	9.50 /EA	2,660.00
14		EA	PALLET	RETURNABLE PALLET	14	15.00 /EA	210.00 *
14		EA	WRAP	SHRINK WRAPPED PALLET	14	5.00 /EA	70.00
1		EA	FUEL	FUEL SURCHARGE	1	50.41 /EA	50.41

*Wendt
12-14*

** AMOUNT CHARGED TO STORE ACCOUNT ** 4,680.97
 TAXABLE 4298.41
 NON-TAXABLE 0.00
 SUBTOTAL 4298.41

X
 RECEIVED BY _____

TAX AMOUNT 382.56
 TOTAL AMOUNT 4680.97