

Lease:	WENDT	
Owner:	Bobcat Oilfield Services	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface:	Cemented:	Hole Size:
20' of 6"	5 Sacks	8 3/4"
Longstring:	Cemented:	Hole Size:
621' 2 7/8" 8 Round Pipe	80 Sacks	5 5/8"



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 4-14
Location: NW,NW,NE,SE 527-T19-R22E
County: LINN
FSU: 2475' FT S
REL: 1155' FT E
API#: 15-107-24889-00-00
Started: 4/18/2014
Completed: 4/21/2014

SN: 590'	Packer:	TD: 641'
Plugged:	Bottom Plug:	

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
2	2	TOP SOIL	3	432	Lime
11	13	Clay	16	445	Shale (Limey)
2	15	Lime	3	452	Lime
12	27	Shale	4	456	Black Shale
1	28	Black Shale	3	459	Shale (Limey)
10	38	Shale	9	468	Shale
5	43	Lime	38	506	Lime (Shaley)
25	68	Shale	4	510	Shale
1	69	Black Shale	3	513	Lime
21	90	Shale	5	518	Black Shale
8	98	Lime	3	521	Shale
10	108	Shale	2	523	Shale (Limey)
36	144	Lime	2	525	Shale
3	147	Shale	1	526	Coal
3	150	Black Shale	4	530	Shale
4	154	Shale	2	532	Shale (Limey)
18	172	Lime	11	543	Light Sandy Shale
	175	Shale	20	553	Shale
2	177	Black Shale	2	565	Lime
1	178	Lime	16	581	Shale
7	185	Shale (Limey)	5	586	Sandy Shale
5	190	Lime	4	590	Sand (Light Oder) (Shaley)
10	200	Light Sandy Shale (Limey)	1	591	Sandy Shale (Oil Sand Stk)
102	302	Shale	1.5	592.5	Oil Sand (Very Shaley) (Fair Bleed)
12	314	Light Sandy Shale	.5	593	Lime
23	337	Shale	3.5	596.5	Oil Sand (Some Shale) (Fair Bleed)
2	339	Black Shale	1	597.5	Oil Sand (Very Shaley) (Fair Bleed)
4	343	Shale	4.5	602	Sandy Shale (Oil Sand Stk)
4	347	Lime	2	604	Sandy Shale
14	361	Shale	2	606	Shale
13	374	Lime (Oder)	2	608	Coal
2	376	Shale	14	622	Shale
2	378	Sandy Shale	2	624	Lime
5	383	Sandy Shale (Oil Sand Stk) (Poor Bleed)	3	627	Black Shale
4	387	Sand (Slight Oder) (Some Shale)	7	634	Sandy Shale
3	390	Sand (Dry) (Some Shale)	7	641	Shale
5	395	Sand (Dry) (very Shaley)	TD	641	
1	396	Sand (Slight Oder) (Some Shale) (Limey)			SET SURFACE - 3:30 PM- 4/18/14
2	398	Sand (Dry) (Very Shaley)			CALLED IN 1:57 PM-TALKED TO BROOKE
11	409	Sandy Shale			LONGSTRING- 621' of 2 7/8" 8 ROUND PIPE
12	421	Shale			SET 4:30PM -4/21/14
4	425	Coal			CALLED IN 3:21 PM- TALKED TO MICHELLE
	430	Shale			



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 4-14
Location: NW, NW, NE, SE-S27-T19-R22E
County: LINN
FSL: 2475' S
FEL: 1155' E
API#: 15-107-24889
Started: 4/18/14
Completed: 4/21/14

Lease:	Wendt
Owner:	BOBCAT OILFIELD SERVICES INC
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	588	0:00	-----	Sand (Oder) (Dry)	590.00'
1	589	1:00	1		
2	590	2:00	1		
3	591	4:00	2	Sandy Shale (Oil Sand Stk)	591.00'
4	592	5:15	1.25	Oil Sand (Very Shaley) (Fair Bleed)	592.50'
5	593	6:45	1.5	Lime	593.00'
6	594	7:45	1	Oil Sand (Some Shale) (Fair Bleed)	596.50'
7	595	8:45	1		
	596	9:45	1		
9	597	12:00	2.25	Oil Sand (Very Shaley) (Fair Bleed)	597.50'
10	598	14:30	2.5	Sandy Shale (Oil Sand Stk)	
11	599	17:00	2.5		
12	600	19:30	2.5		
13	601	22:30	3		
14	602				
15	603				
16					
17					
18					
19					
20					



1/2 Mile North of Louisburg
 27295 Metcalf Rd.
 P.O. Box 729
 Louisburg, Kansas 66053
 913-837-2955 • 1-800-521-1764

MOSSMAN LUMBER COMPANY

True Value.

PL

CUSTOMER NO.	JOB NO.	PURCHASE ORDER NO.	REFERENCE	TERMS	CHECK	DATE	TIME
251			DROR # 78574	NET 10/11	PK	4/11/14	7:44

MOSSMAN
 LUMBER
 COMPANY
 27295 METCALF RD.
 LOUISBURG, MO 66053

1199 WEST 130 THIRY

DEL. DATE: 4/ 8/14 TERMS:SI
 SLSPR: RR ROBERT ROND
 TAX : 001 LOUISBURG, KS

DOCN 179128

 * INVOICE *

 DROR 78574

QUANTITY	UNITS	PRICE PER	EXTENSION
280	EA	5.45 /EA	1,526.00
245	EA	9.50 /EA	2,327.50
14	EA	15.00 /EA	210.00
14	EA	5.00 /EA	70.00
1	EA	50.41 /EA	50.41

*Wendy
 4-14*

TOTAL CHARGED TO STORE ACCOUNT **	4,556.28	TAXABLE	4183.91
		NON-TAXABLE	0.00
		SUBTOTAL	4183.91

5-28-2000 8:56PM FROM MOSSMAN LUMBER 9138375871

RECEIVED BY

TAX AMOUNT 372.37
 TOTAL AMOUNT 4556.28