



BASICSM
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

1700 S. Country Estates Rd.
P.O. Box 129
Liberal, Kansas 67905
Phone 620-624-2277

FIELD SERVICE TICKET
1717 02536 A

DATE _____ TICKET NO. _____

DATE OF JOB 3-26-12 DISTRICT 1717		NEW WELL <input checked="" type="checkbox"/> OLD WELL <input type="checkbox"/> PROD <input type="checkbox"/> INJ <input type="checkbox"/> WDW <input type="checkbox"/> CUSTOMER ORDER NO.:							
CUSTOMER Oxy USA		LEASE Hylbom A #1 WELL NO.							
ADDRESS		COUNTY Finney STATE KS							
CITY STATE		SERVICE CREW J. Chavez, Shawn Eddie							
AUTHORIZED BY Jay Bennett IRB		JOB TYPE: 242 5 1/2 Long String							
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	AM	TIME
19820	12	27462	12	14354	12	ARRIVED AT JOB	3-26-12	AM	-230
				14287 19578	1	START OPERATION	3-26-12	AM	-600
						FINISH OPERATION	3-26-12	AM	-930
						RELEASED	3-26-12	AM	-930
						MILES FROM STATION TO WELL	75		

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED:
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CL104	50-50 Poz AP LOCATION/DEPT. Libcap D02 <input type="checkbox"/> NON <input type="checkbox"/> LEASE/WELL/FAC Hylbom A-1	EA	220	8 25	1815 00
CC113	Gypsum MAXIMO / WSM #	EA	16	56	518 00
CC111	Salt TASK 01-02 ELEMENT	EA	16	38	513 76
CC105	C-15 PROJECT # 1146955 CAPEX / OPEX - Circle one	EA	111	9 38	1041 18
CC105	C-41 P SPO / BPA	EA	47	3 00	141 00
CC201	Gilsonite Circle Doc Type PRINTED NAME UNSUPPORTED	EA	1100	50	550 00
CF251	Guide Shoe SIGNATURE: Jeremy Kneese	EA	1		187 50
CF1451	Insert Float Valve I certify that these Services/Materials have been received	EA	1		161 25
CF103	Rubber Plug	EA	1		78 75
CF4105	Stop Collar	EA	1		63 00
CL155	Super Flush 11	SK	500	1 15	575 00
E101	Heavy Equipment Mileage	mi	150	5 25	787 50
CE240	Blending & Mixing Charge	SK	200	1 05	231 00
E113	Bulk Delivery Charge	ton	698.75	1 20	832 50
CE206	Depth Charge	4hrs	1		2160 00
CE504	Plug Contain Charge	job	1		187 50
E100	Pickup Mileage	mi	75	3 19	239 25
S003	Service Supervisor	EA	1		131 25
T105	Convent Data Acquisi Monitor	EA	1		412 50
SUB TOTAL					10625 94

CHEMICAL / ACID DATA:			

SERVICE & EQUIPMENT	%TAX ON \$	
MATERIALS	%TAX ON \$	
TOTAL		

SERVICE REPRESENTATIVE	THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY:
------------------------	---

(WELL OWNER OPERATOR CONTRACTOR OR AGENT)

FIELD SERVICE ORDER NO.



Cement Report

Customer <i>Oxy USA</i>		Lease No.		Date <i>3-26-12</i>					
Lease <i>Hylbom A</i>		Well # <i>1</i>		Service Receipt <i>2536</i>					
Casing <i>5 1/2 170</i>		Depth <i>5103</i>		County <i>Finney</i> State <i>115</i>					
Job Type <i>742 2m Strg</i>		Formation		Legal Description <i>30-23-34</i>					
Pipe Data			Perforating Data			Cement Data			
Casing size <i>5 1/2 170#</i>		Tubing Size		Shots/Ft			Lead		
Depth <i>5103</i>		Depth <i>55 44'</i>		From		To			
Volume <i>117.5615</i>		Volume		From		To			
Max Press <i>4200 PSI</i>		Max Press		From		To		Tail in <i>220 SK 50-50</i>	
Well Connection <i>5 1/2</i>		Annulus Vol.		From		To		<i>1.58 FT-SK POT</i>	
Plug Depth <i>5059'</i>		Packer Depth		From		To		<i>7.566 ft-SK 13.5#</i>	
Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log				
<i>230</i>					<i>Arrive On location</i>				
<i>235</i>					<i>Safety Meeting - Rig Up</i>				
<i>230</i>					<i>Rig Pump Casing</i>				
<i>600</i>					<i>Circulat w/ Rig</i>				
<i>655</i>					<i>Hook up to BCS</i>				
<i>700</i>	<i>4200</i>		<i>1.0</i>	<i>1.0</i>	<i>Pressure Test</i>				
<i>708</i>	<i>350</i>		<i>5</i>	<i>5.0</i>	<i>Pump Water Spacer</i>				
<i>712</i>	<i>325</i>		<i>12</i>	<i>5.0</i>	<i>Pump Super Flush</i>				
<i>718</i>	<i>300</i>		<i>5</i>	<i>5.0</i>	<i>Pump Water Spacer</i>				
<i>720</i>	<i>200</i>		<i>6.2</i>	<i>5.5</i>	<i>Pump Cmt @ 13.5#</i>				
<i>735</i>					<i>Wash up - Drop Plug</i>				
<i>740</i>	<i>300</i>		<i>107</i>	<i>4.0</i>	<i>Displace</i>				
<i>745</i>	<i>1000</i>		<i>107</i>	<i>6.0</i>	<i>Slam Down - Displace</i>				
<i>805</i>	<i>1500</i>		<i>10</i>	<i>2.0</i>	<i>Land Plug - Float Held</i>				
<i>810</i>	<i>4000</i>		<i>1.0</i>	<i>.25</i>	<i>TEST Casing - To 4200 PSI Per Co-MAN</i>				
<i>811</i>					<i>Pressured up to 4000 psi</i>				
					<i>Casing Failed, cement head jump</i>				
					<i>up, hit Blocks on Rig, Checked</i>				
					<i>Float again, did not Hold</i>				
					<i>Flaved back 161, shut in</i>				
					<i>Head</i>				
Service Units <i>19820</i>		<i>29462</i>		<i>14354-14287</i>					
Driver Names <i>J. Chast</i>		<i>Eddic</i>		<i>Shurr</i>					

Jim M. Knud
Customer Representative

Sony Benth
Station Manager

James Chover
Cementer
Taylor Printing, Inc.