

Cell # 620-363-2683

Dale Jackson Production Co/
Box 266, Mound City, Ks 66056

Office # 913-795-2991



Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 346' of 2 7/8" 8 round pipe	Cemented: 50	Hole Size: 5 5/8"
SN: 284.5'	Packer:	TD: 350'
Plugged:	Bottom Plug:	

**Well
Log**

Well #: 3-14
Location: NW,NE,SW,NW, S9-T20-R23E
County: LINN
FSL: 3795' S
FEL: 4481' E
API#:15-107-25013-00-00
Started: 5/15/14
Completed: 5/16/14

Lease:	Stainbrook
Owner:	Bobcat Oilfield Services Inc.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	Top Soil			
4	5	Clay			
33	38	Lime			
4	42	Shale			
4	46	Black Shale			
21	67	Lime			
2	69	Shale			
2	71	Black Shale			
3	74	Lime			
5	79	Shale			
5	84	Lime			
5	89	Black Shale			
7	96	Light Sandy Shale (Limey)			
38	134	Shale			
32	166	Sandy Shale			
67	233	Shale			
2	235	Coal			
8	243	Shale			
3	246	Lime			
26	272	Shale			
8	280	Lime			
4	284	Shale			
2	286	Sandy Shale (Limey)			
1	287	Sandy Shale (oil Sand Stks) (Poor Bleed)			
1	288	Oil Sand (Water & some Oil)			
3	291	Oil Sand (very little show)(Good Bleed)			
1.5	292.5	Sandy Shale (Oil Sand Stks) (Poor Bleed)			
1	293.5	Sandy Shale			
2.5	296	Sandy Shale (Oil Sand Stks)			
2.5	298.5	Oil Sand (Some Shale)(Good Bleed)			
6	304.5	Oil Sand (Very Shaley) (Fair Bleed)			
1	305.5	Sandy Shale (Oil Sand Stks)(Poor Bleed)			
1.5	307	Oil Sand (Shaley)(Fair Bleed)			
1.5	308.5	Oil Sand (Very Shaley) (Poor Bleed)			
1.5	310	Oil Sand (Some Shale)(Fair Bleed)			
1	311	Shale			
2	313	Sandy Shale (Oil Sand Stks) (Poor Bleed)			
14	327	Shale			
2	329	Coal			SET SURFACE - 12:30 PM - 5/15/14
5	334	Shale			CALLED IN 11:06 AM - TALKED TO BROOKE
6	340	Lime			LONGSTRING - 346' of 2 7/8" 8' ROUND PIPE
6	346	Shale (Limey)			SET TIME 12:00 PM - 5/16/14
TD	350	Shale			CALLED IN 11:53 AM - TALKED TO BROOKE



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 3-14
Location: NW,NE,SW,NW,S9-T20-R23E
County: Linn
FSL: 3795' S
FEL: 4481' E
API#:15-107-25013-00-00
Started: 5/15/2014
Completed: 5/15/2014

Lease :	Stainbrook
Owner:	Bobcat Oilfield Services Inc.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	287	0:00	-----	Oil Sand (Water & Some Oil)	288'
1	288	1:00	1		
2	289	2:00	1	Oil (Very little Shale) (Good Bleed)	291'
3	290	3:00	1		
4	291	4:00	1		
5	292	5:15	1.25	Sandy Shale (Oil Sand Stks)(Poor Bleed)	292.5'
6	293	6:15	1	Sandy Shale	293.5'
7	294	7:45	1.5	Sandy Shale (Oil Sand Stks)	296'
8	295	8:45	1		
9	296	10:15	1.5		
10	297	11:30	1.25	Oil Sand (Some Shale) (Good Bleed)	298.5'
11	298	12:45	1.25		
12	299	14:00	1.25	Oil Sand (Very Shaley) (Fair Bleed)	303'
13	300	15:00	1		
14	301	16:15	1.25		
15	302	17:30	1.25		
16	303	18:30	1		
17					
18					
19					
20					

P. 1




 1/2 Mile North of Louisburg
 27295 Metcalf Rd.
 P.O. Box 729
 Louisburg, Kansas 68053
 913-837-2955 • 1-800-521-1764

MOSSMAN LUMBER COMPANY

PAGE NO. 1

True Value.

ORDER NO.	DATE	QUANTITY	DESCRIPTION	UNIT	PRICE	TOTAL
79097	5/12/14	200	800 SX FLY ASH CLASS C	EA	5.45	1,090.00

ORDER NO. 79097
 DATE 5/12/14
 QUANTITY 200
 DESCRIPTION 800 SX FLY ASH CLASS C
 UNIT EA
 PRICE 5.45
 TOTAL 1,090.00

ORDER NO. 79097
 DATE 5/12/14
 QUANTITY 315
 DESCRIPTION 94# PORTLAND CEMENT 1/11
 UNIT EA
 PRICE 9.50
 TOTAL 2,992.50

DEL. DATE: 5/12/14 TERMS: 51
 SLSPR: RR ROBERT RANO
 TAX: 001 LOUISBURG, KS
 DOC# 179224
 # INVOICE #
 ORDER 79097

QUANTITY	ORDERED	UNIT	SKU	DESCRIPTION	UNITS	PRICE/EA	EXTENSION
200		EA	FLYASH	800 SX FLY ASH CLASS C	200	5.45 /EA	1,090.00
315		EA	PORTLAND	94# PORTLAND CEMENT 1/11	315	9.50 /EA	2,992.50
14		EA	PALLET	RETURNABLE PALLET	14	15.00 /EA	210.00 *
14		EA	WRAP	SHRINK WRAPPED PALLET	14	5.00 /EA	70.00
1		EA	FUEL	FUEL SURCHARGE	1	30.41 /EA	30.41

*Starnbrook
3-14*

** AMOUNT CHARGED TO STORE ACCOUNT ** 4,805.66
 TAXABLE 4412.91
 NON-TAXABLE 0.00
 SUBTOTAL 4412.91

FROM MOSSMAN LUMBER 9138375871

7-01-2000 3:22AM

X
 RECEIVED BY _____

TAX AMOUNT 72.75
 TOTAL PAID 4805.66