

Cell # 620-363-2683

Dale Jackson Production Co.
Box 266, Mound City, Ks 66056



Office # 913-795-2991

Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 340' of 2 7/8" 8 round pipe	Cemented: 50	Hole Size: 5 5/8"
SN: 277'	Packer:	TD: 350'
Plugged:	Bottom Plug:	

Well Log

Well #: 4-14
Location: NE,NE,SW,NW, S9-T20-R23E
County: LINN
FSL: 3795' S
FEL: 4151' E
API#:15-107-24970-00-00
Started: 5/08/14 21
Completed: 5/08/14 22

Lease:	Stainbrook
Owner:	Bobcat Oilfield Services Inc.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
2	2	Top Soil	2	325	Coal
3	5	Clay	6	331	Shale
29	34	Lime	7	338	Lime
3	37	Shale	4	342	Shale (Limey)
3	40	Black Shale	TD	350	Shale
1	41	Shale			
21	62	Lime			
3	65	Shale			
1	66	Black Shale			
3	69	Lime			
5	74	Shale			
6	80	Lime			
5	85	Shale			
8	93	Light Shale (Limey)			
38	131	Shale			
30	161	Sandy Shale			
70	231	Shale			
1	232	Coal			
2	234	Shale			
5	239	Lime			
28	267	Shale			
7	274	Lime			
2	276	Shale			
1	277	Sandy Shale (Limey)			
1	278	Sandy Shale (Oil Sand Stks)(Poor Bleed)			
3.5	281.5	Oil Sand (Shaley)(Some Water)(Slight Oil show)			
3.5	285	Oil Sand (Very Shaley)(Poor Bleed)			
5	290	Sandy Shale (Oil Sand Stks) (Water)			
1	291	Oil Sand (Shaley)(Fair Bleed)			
2	293	Sandy Shale (Oil Sand Stks)(Poor Bleed)			
2	295	Oil Sand (Shaley)(Fair Bleed)			
1	296	Sandy Shale (Oil Sand Stks)(Poor Bleed)			
3.5	299.5	Oil Sand (Some Shale)(Fair Bleed)			
1.5	301	Oil Sand (Very little shale)(Poor Bleed)			
1.5	302.5	Oil Sand (Some Shale)(Good Bleed)			
3.5	306	Oil Sand (Very Shaley)(Fair Bleed)			
2.5	308.5	Sandy Shale (Oil Sand Stks)(Poor Bleed)			
1.5	310	Oil Sand (Very little Shale)(Good Bleed)			
2	312	Sandy Shale (Oil Sand Stks)(Fair Bleed)			SET SURFACE - 1:00 PM - 5/21/14
1	313	Oil Sand (Very Shaley)(Fair Bleed)			CALLED IN 11:24 AM - TALKED TO BROOKE
.5	313.5	Shale			LONGSTRING - 340' of 2 7/8" 8' ROUND PIPE
1	314.5	Oil Sand (Very little Shale)(Good Bleed)			SET TIME 1:00 PM - 5/22/14
8.5	323	Shale			CALLED IN 11:54 AM - TALKED TO BROOKE



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 4-14
Location: NE, NE, SW, NW, S9-T20-R23E
County: Linn
FSL: 3795' S
FEL: 4151' E
API#: 15-107-24959-00-00
Started: 5/21/2014
Completed: 5/22/2014

Lease :	Stainbrook
Owner:	Bobcat Oilfield Services Inc
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	278	0:00	-----		
1	279	1:00	1		
2	280	2:00	1		
3	281	3:00	1		
4	282	4:00	1	Oil Sand (Shaley)(Some water)(Slight oil show)	281.5'
5	283	5:00	1	Oil Sand (Very Shaley)(Poor Bleed)	285'
6	284	6:00	1		
7	285	7:15	1.25		
8	286	8:30	1.25	Sandy Shale (Oil Sand Stks)(Water)	290'
9	287	9:45	1.25		
10	288	11:00	1.25		
11	289	12:15	1.25		
12	290	13:15	1		
13	291	14:30	1.25	Oil Sand (Shaley)(Fair Bleed)	291'
14	292	15:45	1.25	Sandy Shale (Oil Sand Stks)(Poor Bleed)	293'
15	293	17:00	1.25		
16	294	18:15	1.25	Oil Sand (Shaley)(Fair Bleed)	295'
17	295	19:30	1.25		
18	296	22:00	1.50	Sandy Shale (Oil Sand Stks)(Poor Bleed)	296'
19	297	23:30	1.50	Oil Sand	298'
20	298				



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 4-14
Location: NE,NE,SW,NW,S9-T20-R23E
County: Linn
FSL: 3795' S
FEL: 4151; E
API#: 15-107-24959-00-00
Started: 5/21/2014
Completed: 5/22/2014

Lease :	Stainbrook
Owner:	Bobcat Oilfield Services Inc
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #2

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	297	0:00	-----	Oil Sand (Some Shale)(Fair Bleed)	299.5'
1	298	1:00	1		
2	299	2:00	1		
3	300	3:00	1	Oil Sand (Poor Bleed)(Very little Shale)	301'
4	301	4:15	1.25	Oil Sand (Some Shale) (Good Bleed)	302.5'
5	302	5:15	1		
6	303	6:30	1.25	Oil Sand (Very Shaley)(Fair Bleed)	306'
7	304	7:45	1.25		
8	305	8:45	1		
9	306	10:00	1.25	Sandy Shale (Oil Sand Stks)(Poor Bleed)	308.5'
10	307	11:30	1.50		
11	308	13:00	1.50		
12	309	14:15	1.25	Oil Sand (Very little Shale)(Good Bleed)	310'
13	310	15:30	1.25	Sandy Shale (Oil Sand Stks)(Fair Bleed)	312'
14	311	17:00	1.50		
15	312	18:30	1.50	Oil Sand (Very Shaley)(Fair Bleed)	313'
16	313	20:00	1.50	Shale	313.5'
17	314	21:30	1.50	Oil Sand (Very Little Shale)(Good Bleed)	314.5'
18	315	23:15	1.75	Shale	317'
19	316	25:30	2.25		
20	317	27:45	2.25		



1/2 Mile North of Louisburg
27295 Metcalf Rd.
P.O. Box 720
Louisburg, Kansas 66053
913-837-2955 • 1-800-521-1764

MOSSMAN LUMBER COMPANY

PAGE NO. 1

True Value.

CUSTOMER NO.	POD NO.	PURCHASE ORDER NO.	REFERENCE	TERMS	CLERK	DATE	TIME
251			ORDR 79097	NET 10/11	RD	5/14/14	2:00

RIGHT OIL
BUILT 03
50 WEST BERRY
LOUISBURG, KS 66053

1140 WEST 150 W/MAIN

DEL. DATE: 5/12/14 TERMS51
SLSPR: RR ROBERT RAND
TAX : 001 LOUISBURG, KS

DOC# 179224

INVOICE #

ORDR 79097

QUANTITY	ORDERED	UNIT	SKU	DESCRIPTION	UNITS	PRICE	EXTENSION
200		EA	FLYASH	800 SX FLY ASH CLASS C	200	5.45 /EA	1,090.00
315		EA	PORTLAND	94# PORTLAND CEMENT 1/11	315	9.50 /EA	2,992.50
14		EA	PALLET	RETURNABLE PALLET	14	15.00 /EA	210.00 *
14		EA	WRAP	SHRINK WRAPPED PALLET	14	5.00 /EA	70.00
1		EA	FUEL	FUEL SURCHARGE	1	50.41 /EA	50.41

*Stainbrook
4-14*

*** AMOUNT CHARGED TO STORE ACCOUNT *** 4,805.66
TAXABLE 4412.91
NON-TAXABLE 0.00
SUBTOTAL 4412.91

RECEIVED BY

TAX AMOUNT 392.75
TOTAL AMOUNT 4805.66

FROM MOSSMAN LUMBER 9138375871

7-01-2000 3:22AM

