

Dale Jackson Production Co.  
Box 266, Mound City, Ks 66056



Cell # 620-363-2683

Office # 913-795-2991

Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 345' of 2 7/8" 8 round pipe	Cemented: 50	Hole Size: 5 5/8"

SN: 281'	Packer:
Plugged:	Bottom Plug:

TD: 350'

## Well Log

Well #: 17-14
Location: NW,SW,SW,NW, S9-T20-R23E
County: LINN
FSL: 3135' S
FEL: 5115' E
API#: 15-107-24969-00-00
Started: 5/08/14 9
Completed: 5/12/14

Lease:	Stainbrook
Owner:	Bobcat Oilfield Services Inc.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
5	5	Top Soil			
2	7	Clay			
25	32	Lime			
3	35	Shale			
2	37	Black Shale			
2	39	Shale			
22	61	Lime			
3	64	Shale			
1	65	Black Shale			
2	67	Lime			
6	73	Shale			
5	78	Lime			
1	79	Black Shale			
2	81	Shale			
11	92	Light Sandy Shale			
33	125	Shale			
31	156	Sandy Shale			
71	227	Shale			
1	228	Coal			
10	238	Shale			
4	242	Lime			
29	271	Shale			
7	278	Lime			
3	281	Shale			
1	282	Sandy Shale (Oil Sand Stks)(Poor Bleed) (Limey)			
1	283	Oil Sand (Very Shaley) (Fair Bleed) (Limey)			
3.5	286.5	Sandy Shale (Oil Sand Stks) (Fair Bleed)			
5.5	292	Oil Sand (Very Shaley) (Fair Bleed)			
2	294	Sandy Shale (Oil Sand Stks)			
1	295	Oil Sand (Some Shale) (Good Bleed)			
1.5	296.5	Sandy Shale (Oil Sand Stks)			
3.5	300	Oil Sand (Some Shale)(Good Bleed)(Very little water)			
1	301	Sandy Shale(Oil Sand Stks)			
2	303	Oil Sand (Some Shale) (Good Bleed)			
2.5	305.5	Oil Sand(Very Shaley)(Poor Bleed)			
1	306.5	Sandy Shale			
1.5	308	Oil Sand(Some Shale)(Fair Bleed)			
5.5	313.5	Oil Sand (Very Shaley)(Poor Bleed)			
13.5	327	Shale			SET SURFACE - 1:30 PM - 5/29/14
1	328	Coal			CALLED IN 11:53 AM - TALKED TO JOHN
8	336	Shale			LONGSTRING - 345' of 2 7/8" 8' ROUND PIPE
6	342	Lime			SET TIME 12:30 PM - 5/12/14
3	345	Shale (Limey)			CALLED IN 11:33 AM - TALKED TO BROOKE



Dale Jackson Production Co.  
 Box 266, Mound City, Ks 66056  
 Cell # 620-363-2683  
 Office # 913-795-2991

Well #: 17-14
Location: NW,SW,SW,NW,S9-T20-R23E
County: Linn
FSL: 3135' S
FEL: 5115' E
API#: 15-107-24969-00-00
Started: 5/09/2014
Completed: 5/12/2014

Lease :	Stainbrook
Owner:	Bobcat Oilfield Services Inc
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

# Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	283	0:00	-----	Sandy Shale (Oil Sand Stks)(Fair Bleed)	286.50'
1	284	1:15	1.25		
2	285	2:30	1.25		
3	286	3:45	1.25		
4	287	5:00	1.25	Oil Sand(Very Shaley)(Fair Bleed)	292.00'
5	288	6:15	1.25		
6	289	7:15	1		
7	290	8:15	1		
8	291	9:15	1		
9	292	10:30	1.25		
10	293	11:30	1	Sandy Shale(Oil Sand Stks)	294.00'
11	294	12:45	1.25		
12	295	13:45	1	Oil Sand (Some Shale)(Good Bleed)	295.00'
13	296	15:00	1.25	Sandy Shale (Oil Sand Stks)	296.50'
14	297	16:15	1.25	Oil Sand(Some Shale)(Good Bleed)(Very little water)	300'
15	298	17:15	1		
16	299	18:15	1		
17	300	19:30	1.25		
18	301	20:45	1.25	Sandy Shale (Oil Sand Stks)	301'
19	302	21:45	1	Oil Sand (Some Shale)(Good Bleed)	303'
20	303	23:00	1.25		





Dale Jackson Production Co.  
 Box 266, Mound City, Ks 66056  
 Cell # 620-363-2683  
 Office # 913-795-2991

Well #: 17-14
Location: NW, SW, SW, NW, S9-T20-R23E
County: Linn
FSL: 3135' S
FEL: 5115' E
API#: 15-107-24969-00-00
Started: 5/09/2014
Completed: 5/12/2014

Lease :	Stainbrook
Owner:	Bobcat Oilfield Services Inc
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

## Core Run #2

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	303	0:00	-----	Oil Sand (Very Shaley) (Poor Bleed)	305.50'
1	304	1:00	1		
2	305	2:45	1.75		
3	306	4:15	1.50	Sandy Shale	306.50'
4	307	5:30	1.25	Oil Sand (Some Shale) (Fair Bleed)	308'
5	308	7:15	1.75		
6	309	8:45	1.50	Oil Sand (Very Shaley) (Poor Bleed)	
7	310	10:30	1.75		313.50'
8	311	11:45	1.25		
9	312	13:00	1.25		
10	313	14:45	1.75		
11	314	16:30	1.75	Shale	
12	315	18:30	2		320'
13	316	20:30	2		
14	317	22:30	2		
15	318	23:45	1.25		
16	319	25:30	1.75		
17	320	27:30	2		
18					
19					
20					





1/2 Mile North of Louisburg  
27295 Melcott Rd.  
P.O. Box 729  
Louisburg, Kansas 66053  
913-837-2955 • 1-800-521-1764

# MOSSMAN LUMBER COMPANY

PAGE NO 1

COPY

*True Value.*

CUSTOMER NO.	PO NO.	PURCHASE ORDER NO.	REFERENCE	TERMS	CLERK	DATE	TIME
251			ORDER 7800	NET 10%		4/25/14	11:41

MOSSMAN  
LUMBER  
193  
LOUISBURG, KS 66053

1130 WEST 122 STREET

DEL. DATE: 4/22/14 TERMS: 51

SLSPR: RR ROBERT ROND  
TAX: 001 LOUISBURG, KS

DOCA 179167  
\*\*\*\*\*  
\* INVOICE \*  
\*\*\*\*\*  
ORDR 78800

QUANTITY	UNIT	SKU	DESCRIPTION	UNIT PRICE	EXTENSION
280	EA	FLYASH	80# 5X FLY ASH CLASS C	5.45 /EA	1,526.00
245	EA	PORTLAND	94# PORTLAND CEMENT 1/11	9.50 /EA	2,327.50
14	EA	PALLET	RETURNABLE PALLET	15.00 /EA	210.00 *
14	EA	WRAP	SHRINK WRAPPED PALLET	5.00 /EA	70.00
1	EA	FUEL	FUEL SURCHARGE	50.41 /EA	50.41

*Stainbrook  
17-14*

*M*

\*\* AMOUNT CHARGED TO STORE ACCOUNT \*\*

4,556.28  
TAXABLE 4183.91  
NON-TAXABLE 0.00  
SUBTOTAL 4183.91

TAX AMOUNT 372.37  
TOTAL AMOUNT 4556.28

RECEIVED BY