


Cell # 620-363-2683

Dale Jackson Production Co.
Box 266, Mound City, Ks 66056



Office # 913-795-2991

Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 337' of 2 7/8" 8 round pipe	Cemented: 50	Hole Size: 5 5/8"
SN: 276'	Packer:	TD: 341'
Plugged:	Bottom Plug:	

Well Log

Well #: 22-14
Location: NE,SW,SE,NW, S9-T20-R23E
County: LINN
FSL: 3135' S
FEL: 3491' E
API#:15-107-24974-00-00
Started: 6/03/14
Completed: 6/04/14

Lease:	Stainbrook
Owner:	Bobcat Oilfield Services Inc.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
2	2	Top Soil	5	323	Coal
2	4	Clay	4	327	Shale
24	28	Lime	5	332	Lime
3	31	Shale	5	337	Shale (Limey)
2	33	Black Shale	TD	341	Shale
2	35	Shale			
20	55	Lime			
4	59	Shale			
1	60	Black Shale			
3	63	Lime			
5	68	Shale			
6	74	Lime			
1	75	Coal			
3	78	Shale			
11	89	Light Shale (Limey)			
42	131	Shale			
9	140	Sandy Shale			
5	145	Shale			
12	157	Sandy Shale			
40	197	Shale			
4	201	Light Sandy Shale			
18	219	Shale			
3	221	Coal			
10	231	Shale			
5	236	Lime			
27	263	Shale			
7	270	Lime			
2	272	Shale			
4	276	Light Shale (Limey)			
1	277	Light Sandy Shale (Oil Sand Stks)(Limey)			
8	285	Oil Sand (Shaley)(Fair Bleed)			
2	287	Sandy Shale (Oil Sand Stks)(Poor Bleed)			
.5	287.5	Oil Sand (Limey)(Fair Bleed)			
2	289.5	Sandy Shale (Oil Sand Stks)(Poor Bleed)			
3	292.5	Oil Sand (Shaley)(Fair Bleed)			
6.5	299	Sandy Shale (Oil Sand Stks)(Poor Bleed)			
2	301	Oil Sand (Very Shaley)(Fair Bleed)			
1	302	Sandy Shale (Oil Sand Stks)(Poor Bleed)			
1	303	Oil Sand (Shaley)(Fair Bleed)			SET SURFACE - 1:30 PM - 6/03/14
2	305	Shale (Oil Sand Stks)(Fair Bleed)			CALLED IN 12:03 PM - TALKED TO DWAYNE
1	306	Oil Sand (Very Shaley)(Fair Bleed)			LONGSTRING - 337' of 2 7/8" 8' ROUND PIPE
1	307	Shale (Oil Sand Stks)(Poor Bleed)			SET TIME 12:30 PM - 6/04/14
11	318	Shale			CALLED IN 11:41 AM - TALKED TO BROOKE



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 22-14
Location: NE,SW,SE,NW, S9-T20-R23E
County: Linn
FSL: 3135' S
FEL: 3491' E
API#: 15-107-24974-00-00
Started: 6/03/2014
Completed: 6/04/2014

Lease :	Stainbrook
Owner:	Bobcat Oilfield Services Inc
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	277	0:00	-----	Oil Sand (Shaley)(Fair Bleed)	285'
1	278	0:45	.75		
2	279	2:00	1.25		
3	280	2:45	.75		
4	281	4:00	1.25		
5	282	5:00	1		
6	283	6:00	1		
7	284	7:00	1		
8	285	8:00	1		
				Sandy Shale(Oil Sand Stks)(Poor Bleed)	287'
9	286	9:00	1		
10	287	10:30	1.25		
				Oil Sand (Limey)(Fair Bleed)	287.5'
11	288	12:15	1.75	Sandy Shale(Oil Sand Stks)(Poor Bleed)	289.5'
12	289	13:15	1		
13	290	14:30	1.25	Oil Sabnd (Shaley)(Fair Bleed)	292.5'
14	291	15:30	1		
15	292	16:30	1		
16	293	17:30	1		
				Sandy Shale (Oil Sand Stks)(Poor Bleed)	297'
17	294	18:45	1.25		
18	295	20:15	1.5		
19	296	21:30	1.25		
20	297	22:30	1		

copy

1/2 Mile North of Louisburg
27295 Metcalf Rd.
P.O. Box 729
Louisburg, Kansas 66053
913-837-2955 • 1-800-521-1764

MOSSMAN LUMBER COMPANY

PAGE NO 1

True Value.

CUSTOMER NO.	JOB NO.	PURCHASE ORDER NO.	REFERENCE	TERMS	CHECK	DATE	TIME
251			ORDER 79278	NET 100%	RD	5/27/14	07:45

DEPT: 011
RTR: 103
612 WEST 91ST
LOUISBURG, KS 66053

1120 WEST 132ND HWY
LOUISBURG, KS 66053

DEL. DATE: 5/27/14 TERMS: 11
SLSPR: RR ROBERT RANO
TAX : 001 LOUISBURG, KS
DOC# L79273

* INVOICE *

ORDER 79278

QUANTITY	UNIT	DESCRIPTION	PRICE/UNIT	EXTENSION
240	EA	80# SX FLY ASH CLASS C	5.45 /EA	1,308.00
280	EA	94# PORTLAND CEMENT 1/11	9.50 /EA	2,660.00
14	EA	RETURNABLE PALLET	15.00 /EA	210.00 *
14	EA	SHRINK WRAPPED PALLET	5.00 /EA	70.00
1	EA	FUEL SURCHARGE	50.41 /EA	50.41

OK *[Signature]*

Stainbrook
22-14

* AMOUNT CHARGED TO STORE ACCOUNT **		4,680.97
TAXES		4298.41
NON-PAYABLE		0.00
SUBTOTAL		4298.41
TAX ADJUST		182.36
TOTAL DUE		4480.97

RECEIVED BY

P. 1
FROM MOSSMAN LUMBER 9138375871
7-15-2000 10:01PM