

Cell # 620-363-2683

Dale Jackson Production Co.  
Box 266, Mound City, Ks 66056



Office # 913-795-2991

|   |                      |                      |
|---|----------------------|----------------------|
| Surface:<br>20' of 6"                         | Cemented:<br>5 Sacks | Hole Size:<br>8 3/4" |
| Longstring:<br>338' of 2 7/8"<br>8 round pipe | Cemented:<br>50      | Hole Size:<br>5 5/8" |

|          |              |
|----------|--------------|
| SN: 274' | Packer:      |
| Plugged: | Bottom Plug: |

TD: 341'

### Well Log

|                                    |
|------------------------------------|
| Well #: 24-14                      |
| Location: NE,SE,SE,NW, S9-T20-R23E |
| County: LINN                       |
| FSL: 3135' S                       |
| FEL:2805' E                        |
| API#:15-107-24976-00-00            |
| Started: 5/27/14                   |
| Completed: 5/28/14                 |

|             |                               |
|-------------|-------------------------------|
| Lease:      | Stainbrook                    |
| Owner:      | Bobcat Oilfield Services Inc. |
| OPR #:      | 3895                          |
| Contractor: | DALE JACKSON PRODUCTION CO.   |
| OPR #:      | 4339                          |

| TKN | BTM Depth | Formation                               | TKN  | BTM Depth | Formation                                 |
|-----|-----------|---|------|-----------|---|
| 1   | 1         | Topsoil                                 | 10.5 | 314       | Shale                                     |
| 2   | 3         | Clay                                    | 3    | 317       | Coal                                      |
| 24  | 27        | Lime                                    | 5    | 322       | Shale                                     |
| 2   | 29        | Shale                                   | 6    | 328       | Lime                                      |
| 3   | 32        | Black Shake                             | 6    | 334       | Shale (Limey)                             |
| 1   | 33        | Shale                                   | TD   | 341       | Shale                                     |
| 21  | 54        | Lime                                    |      |           |   |
| 3   | 57        | Shale                                   |      |           |   |
| 2   | 59        | Black Shale                             |      |           |   |
| 3   | 62        | Lime                                    |      |           |   |
| 6   | 68        | Shale                                   |      |           |   |
| 5   | 73        | Lime                                    |      |           |   |
| 1   | 74        | Black Shale                             |      |           |   |
| 2   | 76        | Shale                                   |      |           |   |
| 15  | 91        | Light Sandy Shale (Limey)               |      |           |   |
| 40  | 131       | Shale                                   |      |           |   |
| 20  | 151       | Sandy Shale                             |      |           |   |
| 40  | 191       | Shale                                   |      |           |   |
| 9   | 200       | Light Sandy Shale (Limey)               |      |           |   |
| 17  | 217       | Shale                                   |      |           |   |
| 1   | 218       | Coal                                    |      |           |   |
| 8   | 226       | Shale                                   |      |           |   |
| 4   | 230       | Lime                                    |      |           |   |
| 33  | 263       | Shale                                   |      |           |   |
| 4   | 267       | Lime                                    |      |           |   |
| 2   | 269       | Shale                                   |      |           |   |
| 4   | 273       | Sandy Shale (Limey)                     |      |           |   |
| 1   | 274       | Sandy Shale (Limey)(Slight Oder)        |      |           |   |
| 1   | 275       | Sandy Shale (Oil Sand Stks)(Fair Bleed) |      |           |   |
| 2.5 | 277.5     | Oil Sand (Some Shale) (Good Bleed)      |      |           |   |
| 1   | 278.5     | Sandy Shale (Oil Sand Stks)(Poor Bleed) |      |           |   |
| 1   | 279.5     | Oil Sand (Very Shaley)(Fair Bleed)      |      |           |   |
| 2.5 | 282       | Sandy Shale (Oil Sand Stks)(Poor Bleed) |      |           |   |
| 2   | 284       | Oil Sand (Very Shaley)(Fair Bleed)      |      |           |   |
| 1   | 285       | Oil Sand (Some Shale)(Good Bleed)       |      |           |   |
| 3.5 | 288.5     | Oil Sand (Shaley)(Fair Bleed)           |      |           |   |
| 2.5 | 291       | Oil Sand (Some Shale)(Good Bleed)       |      |           |   |
| 5   | 296       | Oil Sand (Very Shaley)(Fair Bleed)      |      |           |   |
| 1   | 297       | Oil Sand (Some Shale)(Fair Bleed)       |      |           | SET SURFACE - 1:00 PM - 5/27/14           |
| 1   | 298       | Oil Sand (Some Shale)(Good Bleed)       |      |           | CALLED IN 1:45 PM - TALKED TO BROOKE      |
| 2   | 300       | Sandy Shale (Oil Sand Stks)(Poor Bleed) |      |           | LONGSTRING - 338' of 2 7/8" 8' ROUND PIPE |
| 1   | 301       | Oil Sand (Very Shaley)(Fair Bleed)      |      |           | SET TIME 2:00 PM - 5/28/14                |
| 2.5 | 303.5     | Sandy Shale (Oil Sand Stks)(Poor Bleed) |      |           | CALLED IN 1:10 PM - TALKED TO BROOKE      |



Dale Jackson Production Co.  
 Box 266, Mound City, Ks 66056  
 Cell # 620-363-2683  
 Office # 913-795-2991

|                                    |
|------------------------------------|
| Well #: 24-14                      |
| Location: NE,SE,SE,NW, S9-T20-R23E |
| County: Linn                       |
| FSL: 3135' S                       |
| FEL: 2805' E                       |
| API#: 15-107-24976-00-00           |
| Started: 5/27/2014                 |
| Completed: 5/28/2014               |

|             |                              |
|-------------|------------------------------|
| Lease :     | Stainbrook                   |
| Owner:      | Bobcat Oilfield Services Inc |
| OPR #:      | 3895                         |
| Contractor: | DALE JACKSON PRODUCTION CO.  |
| OPR #:      | 4339                         |

# Core Run #1

| FT | Depth    | Clock | Time  | Formation/Remarks                       | Depth  |
|----|----------|-------|-------|---|--------|
| 0  | 276      | 0:00  | ----- |   | 277.5' |
| 1  | 277      | 0:45  | .75   | Oil Sand (Some Shale)(Good Bleed)       |        |
| 2  | 278      | 1:45  | 1     | Sandy Shale (Oil Sand Stks)(Poor Bleed) | 278.5' |
| 3  | 279      | 2:45  | 1     | Oil Sand (Very Shaley)(Fair Bleed)      | 279.5' |
|    | Lockedup | 3:45  |       |   |        |
| 4  | 280      | 4:00  | 1.25  | Sandy Shale (Oil Sand Stks)(Poor Bleed) | 282'   |
| 5  | 281      | 5:00  | 1     |   |        |
| 6  | 282      | 6:00  | 1     |   |        |
|    |          |       |       | Oil Sand (Very Shaley (Fair Bleed)      |        |
| 7  | 283      | 7:00  | 1     |   |        |
|    | Lockedup |       |       |   |        |
| 8  | 284      |       |       |   |        |
| 9  | 285      |       |       |   |        |
| 10 | 286      |       |       |   |        |
| 11 | 287      |       |       |   |        |
| 12 | 288      |       |       |   |        |
| 13 |          |       |       |   |        |
| 14 |          |       |       |   |        |
| 15 |          |       |       |   |        |
| 16 |          |       |       |   |        |
| 17 |          |       |       |   |        |
| 18 |          |       |       |   |        |
| 19 |          |       |       |   |        |
| 20 |          |       |       |   |        |



COPY



1/2 Mile North of Louisburg  
27295 Metcalf Rd.  
P.O. Box 729  
Louisburg, Kansas 66053  
913-837-2955 • 1-800-521-1764

# MOSSMAN LUMBER COMPANY

PAGE NO 1

## True Value.

| CUSTOMER NO. | JOB NO. | PURCHASE ORDER NO. | REFERENCE   | TERMS    | CLERK | DATE    | TIME  |
|--------------|---------|--------------------|-------------|----------|-------|---------|-------|
| 251          |         |                    | ORDER 79278 | NET 10TH | RR    | 5/20/14 | 07:45 |

MOSSMAN LUMBER  
ROUTE 103  
600 WEST HWY  
LOUISBURG, KS 66053

STAINBROOK  
11400 WEST 152 HWY  
LOUISBURG, MO 64888

DEL. DATE: 5/27/14 TERMS: 1

DOC# L79273

\*\*\*\*\*

\* INVOICE \*

\*\*\*\*\*

SLSR: RR ROBERT RAND

TAX : 001 LOUISBURG, KS

ORDER 79278

| QUANTITY | ORDERED | UOM | SKU      | DESCRIPTION              | UNITS | PRICE PER | EXTENSION |
|----------|---------|-----|----------|--------------------------|-------|-----------|-----------|
| 240      |         | EA  | FLYASH   | 80# SX FLY ASH CLASS C   | 240   | 5.45 /EA  | 1,308.00  |
| 280      |         | EA  | PORTLAND | 94# PORTLAND CEMENT 1/II | 280   | 9.50 /EA  | 2,660.00  |
| 14       |         | EA  | PALLET   | RETURNABLE PALLET        | 14    | 15.00 /EA | 210.00 *  |
| 14       |         | EA  | WRAP     | SHRINK WRAPPED PALLET    | 14    | 5.00 /EA  | 70.00     |
| 1        |         | EA  | FUEL     | FUEL SURCHARGE           | 1     | 50.41 /EA | 50.41     |

OK 12/2

Stainbrook  
24-14

\*\* AMOUNT CHARGED TO STORE ACCOUNT \*\* 4,620.97

TRADE 4298.41  
 NON-PAYABLE 0.00  
 SUBTOTAL 4298.41

RECEIVED BY

TAX TOTAL 102.56  
 TOTAL 4400.97

P. 1

FROM MOSSMAN LUMBER 9138375871

7-16-2000 10:01PM