

Cell # 620-363-2683

Dale Jackson Production Co.  
Box 266, Mound City, Ks 66056



Office # 913-795-2991

Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 349' of 2 7/8" 8 round pipe	Cemented: 50	Hole Size: 5 5/8"
SN:	Packer:	TD: 350'
Plugged:	Bottom Plug:	

**Well Log**

Well #: 9W-14
Location: W2,NW,SW,NW, S9-T20-R23E
County: LINN
FSL: 3630' S
FEL: 4976' E
AP#: 15-107-24985-00-00
Started: 5/05/14
Completed: 5/06/14

Lease:	Stainbrook
Owner:	Bobcat Oilfield Services Inc.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
2	2	Top Soil	7	333	Shale
6	8	Clay	8	341	Lime
25	33	Lime	5	346	Shale (Limy)
1	34	Shale	4	350	Shale
2	36	Black Shale	TD	350	
3	39	Shale			
21	60	Lime			
2	62	Shale			
2	64	Black Shale			
3	67	Lime			
5	72	Shale			
6	78	Lime			
48	126	Shale			
31	157	Sandy Shale			
31	188	Shale			
1	189	Coal			
42	231	Shale			
1	232	Coal			
6	238	Shale			
3	241	Lime			
25	266	Shale			
9	275	Lime			
5	280	Shale			
1	281	Sandy Shale (Oil Sand Stks) (Poor Bleed) (Limy)			
1	282	Sandy Shale			
.5	282.5	Sandy Shale (Oil Sand Stks) (Poor Bleed)			
4	286.5	Oil Sand (Very little Shale) (Fair Bleed)			
1.5	288	Sandy Shale (Oil Sand Stks) (Poor Bleed)			
1	289	Sandy Shale			
5.5	294.5	Oil Sand (Very Shaley) Fair Bleed)			
1.5	296	Sandy Shale (Oil Sand Stks) (Poor Bleed)			
4	300	Oil Sand (Some Shale) (Fair Bleed)			
3	303	Oil Sand (Very Shaley) (Poor Bleed)			
1	304	Sandy Shale			
.5	304.5	Oil Sand (Some Shale) (Fair Bleed)			
.5	305	Sandy Shale			
.5	305.5	Oil Sand (Some Shale) (Fair Bleed)			
1	306.5	Shale			
2	308.5	Oil Sand (Some Shale) (Fair Bleed)			SET SURFACE - 3:00 PM - 5/05/14
3	311.5	Sandy Shale (Oil Sand Stks) (Poor Bleed)			CALLED IN 1:48 PM - TALKED TO BROOKE
1.5	313	White Sand (No Oil Show)			LONGSTRING - 349' of 2 7/8" 8' ROUND PIPE
11	324	Shale			SET TIME 12:30 PM - 5/06/14
2	326	Coal			CALLED IN 11:26 AM - TALKED TO BROOKE



Dale Jackson Production Co.  
 Box 266, Mound City, Ks 66056  
 Cell # 620-363-2683  
 Office # 913-795-2991

Well #: 9W-14
Location: W2,NW,SW,NW,S9-T20-R23E
County: LINN
FSL: 3630' S
FEL: 4976' E
API#: 15-107-24985-00-00
Started: 5/05/14
Completed: 5/06/14

Lease :	Stainbrook
Owner:	BOBCAT OILFIELD SERVICES INC
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

# Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	281	0:00	-----	Sandy Shale	282'
1	282	1:15	1.25	Sandy Shale (oil Sand Stks) (Poor Bleed)	282.5'
2	283	2:30	1.25	Oil Sand (Very little Shale) (Fair Bleed)	286.5'
3	284	3:30	1		
4	285	4:30	1		
5	286	5:30	1		
6	287	6:45	1.25	Sandy Shale (Oil Sand Stks) (Poor Bleed)	288'
7	288	8:00	1.25	Sandy Shale	289'
8	289	9:15	1.25	Oil Sand (Very Shaley) (Fair Bleed)	294.5
9	200	10:30	1.25		
10	291	11:30	1		
11	292	12:45	1.25		
12	293	14:00	1.25		
13	294	15:15	1.25		
14	295	16:30	1.25	Sandy Shale (Oil Sand Stks) (Poor Bleed)	296'
15	296	18:00	1.50	Oil Sand (Some Shale) (Fair Bleed)	300'
16	297	19:15	1.25		
17	298	20:45	1.50		
18	299	22:00	1.25		
19	300	23:15	1.25	Oil Sand (Very Shaley) (Poor Bleed)	301'
20	301	24:30	1.25		



Dale Jackson Production Co.  
 Box 266, Mound City, Ks 66056  
 Cell # 620-363-2683  
 Office # 913-795-2991

Well #: 9W-14
Location: W2, NW, SW, NW, S9-T20-R23E
County: LINN
FSL: 3630' S
FEL: 4976' E
API#: 15-107-24985-00-00
Started: 5/05/14
Completed: 5/06/14

Lease :	Stainbrook
Owner:	BOBCAT OILFEILD SERVICES
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

## Core Run #2

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	301	0:00	-----	Oil Sand (Very Shaley) (poor Bleed)	303'
1	302	1:30	1.50		
2	303	2:45	1.25		
3	304	4:15	1.50	Sandy Shale	304'
				Oil Sand (Some Shale) (Fair Bleed)	304.5'
4	305	5:45	1.50	Sandy Shale	305'
				Oil Sand (Some Shale) (Fair Bleed)	305.5'
5	306	7:00	1.25	Shale	306.5'
6	307	8:30	1.50	Oil Sand (Some Shale) (Fair Bleed)	308.5'
7	308	9:45	1.25		
8	309	11:00	1.25	Sandy Shale (Oil Sand Stks) (Poor Bleed)	
9	310	12:30	1.50		311.5'
10	311	14:15	1.75		
11	312	16:00	1.75	White Sand (No Oil Show)	
12	313	17:30	1.50		321'
				Shale	
13	314	18:45	1.25		
14	315	20:30	1.75		
15	316	22:15	1.75		
16	317	23:30	1.25		
17	318	25:30	2		
18	319	27:45	2.25		
19	320				
20	321				

RECEIVED BY

QUANTITY	DESCRIPTION	UNIT	PRICE	AMOUNT
280	80# SX FLY ASH CLASS F	280	5.45 /EA	1,326.00
245	94# PORTLAND CEMENT 1/11	245	9.50 /EA	2,327.50
14	RETURNABLE Pallet	14	15.00 /EA	210.00
14	SHRINK WRAPPED Pallet	14	5.00 /EA	70.00
1	FUEL SURCHARGE	1	50.41 /EA	50.41
				4183.91
				4,536.28

Stampbook 9/14/14

TAX AMOUNT 372.37  
 TAX RATE 8.2%  
 SUBTOTAL 4183.91  
 NET AMOUNT 4,536.28

DEL. DATE: 4/22/14  
 SLSPR: RR ROBERT ROAD  
 RR ROBERT ROAD  
 001 LOUISBURG, MS  
 ORDER 78800

QUANTITY	DESCRIPTION	UNIT	PRICE	AMOUNT
----------	-------------	------	-------	--------

True Value

**MUSSMAN LUMBER COMPANY**  
 1/2 Mile North of Louisville  
 27255 Madson Rd.  
 P.O. Box 729  
 Louisville, Kansas 66053  
 913-937-2955 • 1-800-521-1764

COPY