

Cell # 620-363-2683

Dale Jackson Production Co.  
Box 266, Mound City, Ks 66056



Office # 913-795-2991

|  |                             |                             |
|--|-----------------------------|-----------------------------|
| <b>Surface:</b><br>20' of 6"                         | <b>Cemented:</b><br>5 Sacks | <b>Hole Size:</b><br>8 3/4" |
| <b>Longstring:</b><br>347' of 2 7/8"<br>8 round pipe | <b>Cemented:</b><br>50      | <b>Hole Size:</b><br>5 5/8" |
| <b>SN:</b>   | <b>Packer:</b>              | <b>TD: 350'</b>             |
| <b>Plugged:</b>                                      | <b>Bottom Plug:</b>         |                             |

**Well Log**

|   |
|---|
| <b>Well #:</b> 10W-14                     |
| <b>Location:</b> NE,SW,SW,NW, S9-T20-R23E |
| <b>County:</b> LINN                       |
| <b>FSL:</b> 3646' S                       |
| <b>FEL:</b> 4646' E                       |
| <b>API#:</b> 15-107-25018-00-00           |
| <b>Started:</b> 5/14/14                   |
| <b>Completed:</b> 5/15/14                 |

|                    |                               |
|--------------------|-------------------------------|
| <b>Lease:</b>      | Stainbrook                    |
| <b>Owner:</b>      | Bobcat Oilfield Services Inc. |
| <b>OPR #:</b>      | 3895                          |
| <b>Contractor:</b> | DALE JACKSON PRODUCTION CO.   |
| <b>OPR #:</b>      | 4339                          |

| TKN | BTM Depth | Formation                                | TKN  | BTM Depth | Formation                                 |
|-----|-----------|--|------|-----------|---|
| 2   | 2         | Top Soil                                 | 1.5  | 314.5     | Oil Sand(Very Shaley) (Poor Bleed)        |
| 3   | 5         | Clay                                     | 12.5 | 327       | Shale                                     |
| 31  | 36        | Lime                                     | 2    | 329       | Coal                                      |
| 4   | 40        | Shale                                    | 4    | 333       | Shale                                     |
| 4   | 44        | Black Shale                              | 5    | 338       | Lime                                      |
| 21  | 65        | Lime                                     | 7    | 345       | Shale (Limey)                             |
| 3   | 68        | Shale                                    | TD   | 350       | Shale                                     |
| 1   | 69        | Black Shale                              |      |           |   |
| 2   | 71        | Lime                                     |      |           |   |
| 5   | 76        | Shale                                    |      |           |   |
| 6   | 82        | Lime                                     |      |           |   |
| 1   | 83        | Black Shale                              |      |           |   |
| 3   | 86        | Shale                                    |      |           |   |
| 8   | 94        | Light Shale (Limey)                      |      |           |   |
| 37  | 131       | Shale                                    |      |           |   |
| 12  | 143       | Sandy Shale (Dry Sand Stks)              |      |           |   |
| 13  | 156       | Sandy Shale                              |      |           |   |
| 50  | 206       | Shale                                    |      |           |   |
| 8   | 214       | Light Sandy Shale (Limey)                |      |           |   |
| 18  | 232       | Shale                                    |      |           |   |
| 1   | 233       | Coal                                     |      |           |   |
| 5   | 238       | Shale                                    |      |           |   |
| 3   | 241       | Lime                                     |      |           |   |
| 28  | 269       | Shale                                    |      |           |   |
| 8   | 277       | Lime                                     |      |           |   |
| 2   | 279       | Shale                                    |      |           |   |
| 3   | 282       | Sandy Shale (Limey)                      |      |           |   |
| 3   | 285       | Sandy Shale (Oil Sand Stks)(Limey)       |      |           |   |
| 2   | 287       | Oil Sand(Water)(Very Slight oil show)    |      |           |   |
| 1.5 | 288.5     | Oil Sand (Fair Bleed)                    |      |           |   |
| 2.5 | 291       | Sandy Shale (Oil Sand Stks) (Poor Bleed) |      |           |   |
| 2.5 | 293.5     | Oil Sand(Very Shaley)(Poor Bleed)        |      |           |   |
| 1   | 294.5     | Sandy Shale(Oil Sand Stks) (Poor Bleed)  |      |           |   |
| 3   | 297.5     | Oil Sand (Some Shale)(Fair Bleed)        |      |           |   |
| .5  | 298       | Sandy Shale                              |      |           |   |
| 5   | 303       | Oil Sand (Shaley)(Fair Bleed)            |      |           |   |
| .5  | 303.5     | Oil Sand(Fair Bleed)                     |      |           |   |
| 3.5 | 307       | Oil Sand (Very Shaley)(Poor Bleed)       |      |           |   |
| .5  | 307.5     | Oil Sand (Some Shale)(Fair Bleed)        |      |           | SET SURFACE - 2:00 PM - 5/14/14           |
| 1   | 308.5     | Shale                                    |      |           | CALLED IN 12:28 PM - TALKED TO LEVI       |
| 2   | 310.5     | Oil Sand (Shaley)(Good Bleed)            |      |           | LONGSTRING - 347' of 2 7/8" 8' ROUND PIPE |
| 1   | 311.5     | Shale                                    |      |           | SET TIME 2:00 PM - 5/15/14                |
| 1.5 | 313       | Oil Sand(Very Shaley)(Fair Bleed)        |      |           | CALLED IN 11:06 AM - TALKED TO BROOKE     |



Dale Jackson Production Co.  
 Box 266, Mound City, Ks 66056  
 Cell # 620-363-2683  
 Office # 913-795-2991

|                                   |
|-----------------------------------|
| Well #: 10W-14                    |
| Location: E2,NW,SW,NW,S9-T20-R23E |
| County: Linn                      |
| FSL: 3630' S                      |
| FEL: 4646' E                      |
| API#: 15-107-25018-00-00          |
| Started: 5/14/2014                |
| Completed: 5/15/2014              |

|             |                              |
|-------------|------------------------------|
| Lease :     | Stainbrook                   |
| Owner:      | Bobcat Oilfield Services Inc |
| OPR #:      | 3895                         |
| Contractor: | DALE JACKSON PRODUCTION CO.  |
| OPR #:      | 4339                         |

## Core Run #1

| FT | Depth | Clock | Time  | Formation/Remarks                                    | Depth   |
|----|-------|-------|-------|--|---------|
| 0  | 283   | 0:00  | ----- | Sandy Shale (Oil Sand Stks) (Poor Bleed) (Some Lime) | 285'    |
| 1  | 284   | 1:45  | 1.75  |  |         |
| 2  | 285   | 3:00  | 1.25  |  |         |
|    |       |       |       | Oil Sand (Water) (Very Slight Oil show)              | 287'    |
| 3  | 286   | 4:00  | 1     |  |         |
| 4  | 287   | 5:00  | 1     |  |         |
|    |       |       |       | Oil Sand (Fair Bleed)                                | 288.50' |
| 5  | 288   | 6:00  | 1     |  |         |
| 6  | 289   | 7:00  | 1     | Sandy Shale (Oil Sand Stks) (Poor Bleed)             | 291'    |
| 7  | 290   | 8:30  | 1.50  |  |         |
| 8  | 291   | 9:45  | 1.25  |  |         |
|    |       |       |       | Oil Sand (Very Shaley) (Poor Bleed)                  | 293.50' |
| 9  | 292   | 11:00 | 1.25  |  |         |
| 10 | 293   | 12:00 | 1     |  |         |
| 11 | 294   | 13:15 | 1.25  | Sandy Shale (Oil Sand Stks) (Poor Bleed)             | 294.50' |
| 12 | 295   | 14:30 | 1.25  | Oil Sand (Some Shale) (Fair Bleed)                   | 297.50' |
| 13 | 296   | 15:45 | 1.25  |  |         |
| 14 | 297   | 17:00 | 1.25  |  |         |
| 15 | 298   | 18:45 | 1.75  | Sandy Shale  | 298'    |
|    |       |       |       | Oil Sand (Shaley) (Fair Bleed)                       | 303'    |
| 16 | 299   | 20:00 | 1.25  |  |         |
| 17 | 300   | 21:30 | 1.50  |  |         |
| 18 | 301   | 23:15 | 1.75  |  |         |
| 19 | 302   | 24:45 | 1.50  |  |         |
| 20 | 303   | 26:00 | 1.25  |  |         |
|    |       |       |       | Oil Sand (Fair Bleed)                                |         |



Dale Jackson Production Co.  
 Box 266, Mound City, Ks 66056  
 Cell # 620-363-2683  
 Office # 913-795-2991

|                                   |
|-----------------------------------|
| Well #: 10W-14                    |
| Location: E2,NW,SW,NW,S9-T20-R23E |
| County: Linn                      |
| FSL: 3630'S                       |
| FEL: 4646' E                      |
| API#: 15-107-25018-00-00          |
| Started: 5/14/2014                |
| Completed: 5/15/2014              |

|             |                             |
|-------------|-----------------------------|
| Lease :     | Stainbrook                  |
| Owner:      | Bobcat Oilfield Services In |
| OPR #:      | 3895                        |
| Contractor: | DALE JACKSON PRODUCTION CO. |
| OPR #:      | 4339                        |

## Core Run #2

| FT | Depth | Clock | Time  | Formation/Remarks                  | Depth   |
|----|-------|-------|-------|------------------------------------|---------|
| 0  | 303   | 0:00  | ----- |                                    | 303.50' |
| 1  | 304   | 1:00  | 1     | Oil Sand (Very Shaley)(Poor Bleed) | 307'    |
| 2  | 305   | 3:00  | 2     |                                    |         |
| 3  | 306   | 5:15  | 2.25  |                                    |         |
| 4  | 307   | 6:45  | 1.50  |                                    |         |
|    |       |       |       | Oil Sand (Some Shale)(Fair Bleed)  | 307.50' |
| 5  | 308   | 8:30  | 1.75  | Shale                              | 308.50' |
| 6  | 309   | 10:45 | 2.25  | Oil Sand (Shaley) (Good Bleed)     | 310.50' |
| 7  | 310   | 12:30 | 1.75  |                                    |         |
| 8  | 311   | 14:00 | 1.50  | Shale                              | 311.50' |
| 9  | 312   | 15:30 | 1.50  | Oil Sand (Very Shaley)(Fair Bleed) | 313'    |
| 10 | 313   | 16:45 | 1.25  |                                    |         |
|    |       |       |       | Oil Sand (Very Shaley)(Poor Bleed) | 314.5'  |
| 11 | 314   | 18:30 | 1.75  |                                    | 318'    |
| 12 | 315   | 20:30 | 2     | Shale                              |         |
| 13 | 316   | 22:00 | 1.50  |                                    |         |
| 14 | 317   | 24:30 | 2.50  |                                    |         |
| 15 | 318   | 27:30 | 3     |                                    |         |
| 16 | 319   |       |       |                                    |         |
| 17 |       |       |       |                                    |         |
| 18 |       |       |       |                                    |         |
| 19 |       |       |       |                                    |         |
| 20 |       |       |       |                                    |         |

RECEIVED BY

X


| QUANTITY | UNIT | DESCRIPTION              | PRICE     | TOTAL    |
|----------|------|--------------------------|-----------|----------|
| 200      | EA   | 800 SX FLY ASH CLASS C   | 5.45 /EA  | 1,090.00 |
| 315      | EA   | 944 PORTLAND CEMENT 1/11 | 9.50 /EA  | 2,992.50 |
| 14       | EA   | RETURABLE PALLET         | 15.00 /EA | 210.00 * |
| 14       | EA   | SHRINK WRAPPED PALLET    | 5.00 /EA  | 70.00    |
| 1        | EA   | FUEL SURCHARGE           | 50.41 /EA | 50.41    |

Stainbreak  
low-14

| QUANTITY | UNIT | DESCRIPTION | PRICE | TOTAL    |
|----------|------|-------------|-------|----------|
| 412.91   | EA   | NON-TAXABLE | 0.00  | 0.00     |
| 412.91   | EA   | TAXABLE     | 4.90  | 2,023.66 |

ORDER 79097

DEL. DATE: 5/12/14  
 SLS PR: RR ROBERT ROAD  
 TAX : 001 LOUISBURG, KS  
 DOC# 179224  
 \* INVOICE \*



True Value

**MOSSMAN LUMBER COMPANY**  
 1/2 Mile North of Louisburg  
 27295 Mel-AH Rd.  
 P.O. Box 720  
 Louisburg, Kansas 66053  
 913-537-2955 • 1-800-621-1764