

Cell # 620-363-2683

Dale Jackson Production Co.
Box 266, Mound City, Ks 66056



Office # 913-795-2991

Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 349' of 2 7/8" 8 round pipe	Cemented: 50	Hole Size: 5 5/8"
SN:	Packer:	TD: 351'
Plugged:	Bottom Plug:	

Well Log

Well #: 29W-14
Location: W2,SW,SE,NW, S9-T20-R23E
County: LINN
FSL: 2970' S
FEL: 3716' E
API#: 15-107-24999-00-00
Started: 7/09/14
Completed: 7/10/14

Lease:	Stainbrook
Owner:	Bobcat Oilfield Services Inc.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	Top Soil	1.5	302	Shale (Oil Sand Stks)(Poor Bleed)
1	2	Clay	1	303	Oil Sand (Some Shale)(Good Bleed)
29	31	Lime	1	304	Shale (Oil Sand Stks)(Poor Bleed)
3	34	Shale	3	307	Oil Sand (Fair Bleed)
2	36	Black Shale	3	311	Oil Sand (Shaley)(Good Bleed)
1	37	Shale	9	320	Shale
21	58	Lime	3	323	Coal
3	61	Shale	7	330	Shale
3	64	Black Shale	8	338	Lime
2	66	Lime	3	341	Shale (Limey)
5	71	Shale	8	349	Shale
5	76	Lime	TD	351	Lime
1	77	Black Shale			
2	79	Shale			
8	87	Light Shale (Limey)			
42	129	Shale			
32	161	Sandy Shale			
36	197	Shale			
9	206	Light Sandy Shale			
14	220	Shale			
3	223	Coal			
8	231	Shale			
3	234	Lime			
27	261	Shale			
8	269	Lime			
1	270	Shale (Limey)			
1	271	Shale (Limey)(Oder)			
1	272	Light Shale (Limey)(Oder)			
3	275	Light Shale (Limey)			
1	276	Light Shale (Oil Sand Stks)(Poor Bleed) (Limey)			
1	277	Oil Sand(Shaley)(Some lime)(Fair Bleed)			
1.5	278.5	Oil Sand (Water & Some Oil)			
1.5	280	Oil Sand(Good Bleed)(Some Shale)			
1	281	Lime			
3.5	284.5	Oil Sand (Very Shaley)(Fair Bleed)			
1.5	286	Sandy Shale(Oil Sand Stks)(Poor Bleed)			
1.5	287.5	Oil Sand (Some Shale)(Good Bleed)			
2.5	290	Sandy Shale (Oil Sand Stks)(Poor Bleed)			
1.5	291.5	Oil Sand (Very Shaley)(Fair Bleed)			SET SURFACE – 1:00 PM – 7/09/14
1	292.5	Shale (Oil Sand Stks)(Poor Bleed)			CALLED IN 11:22 AM – TALKED TO BROOKE
2.5	295	Oil Sand (Very Shaley)(Poor Bleed)			LONGSTRING – 349' of 2 7/8" 8' ROUND PIPE
3	298	Sandy Shale(Oil Sand Stks)(Fair Bleed)			SET TIME 1:30 PM – 7/10/14
2.5	300.5	Oil Sand (Shaley)(Fair Bleed)			CALLED IN 12:36 PM – TALKED TO BROOKE



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 29W-14
Location: W2,SW,SE,NW,S9-T20-R23E
County: Linn
FSL: 2970' S
FEL: 3716' E
API#: 15-107-24999-00-00
Started: 7/09/2014
Completed: 7/10/2014

Lease :	Stainbrook
Owner:	Bobcat Oilfield Services Inc
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	277	0:00	-----	Oil Sand (Water & some Oil)	278.5
1	278	0:45	.75		
2	279	1:30	.75	Oil Sand (Good Bleed)(Some Shale)	280
3	280	2:30	1		
				Lime	281
4	281	4:00	1.5	Oil Sand (Very Shaley)(Fair Bleed)	284.5
5	282	5:00	1		
6	283	6:00	1		
7	284	7:00	1		
8	285	8:00	1	Sandy Shale (Oil Sand Stks)(Poor Bleed)	286
9	286	8:45	.75	Oil Sand (Some Shale)(Poor Bleed)	287.5
10	287	9:45	1		
11	288	10:45	1	Sandy Shale (Oil Sand Stks)(Poor Bleed)	290
12	289	11:45	1		
13	290	13:00	1.25		
				Oil Sand (Very Shaley)(Fair Bleed)	291.5
14	291	14:15	1.25	Shale (Oil Sand Stks)(Poor Bleed)	292.5
15	292	15:30	1.25		
16	293	16:45	1.25	Oil Sand (Very Shaley)(Poor Bleed)	
17	294	18:00	1.25		
18	295	19:15	1.25		
	Lockedup				
19	296				
20	297				



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 29W-14
Location: W2, SW, SE, NW, S9-T20-R23E
County: Linn
FSL: 2970' S
FEL: 3716' E
API#: 15-107-24999-00-00
Started: 7/09/2014
Completed: 7/10/2014

Lease :	Stainbrook
Owner:	Bobcat Oilfield Services Inc
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #2

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	295	0:00	-----	Sandy Shale (Oil Sand Stks) (Fair Bleed)	298
1	296	1:00	1		
2	297	2:30	1.5		
3	298	4:30	2	Oil Sand (Shaley)(Fair Bleed)	300.5
4	299	5:45	1.25		
5	300	7:00	1.25	Shale (Oil Sand Stks)(Poor Bleed)	302
6	301	8:15	1.25		
7	302	10:15	2	Oil Sand (Some Shale)(Good Bleed)	303
8	303	12:00	1.75		
9	304	13:45	1.75	Shale (Oil Sand Stks)(Poor Bleed)	304
10	305	15:30	1.75		
11	306	17:00	1.5	Oil Sand (Fair Bleed)	
12	307	19:00	2		
13	308				
14					
15					
16					
17					
18					
19					
20					

RECEIVED BY

QUANTITY	UNIT	DESCRIPTION	PRICE	TOTAL
240	EA	94# PORTLAND CEMENT 1/11	9.50	2,280.00
14	EA	RETURABLE PALLET	15.00	210.00
14	EA	SHRINK WRAPPED PALLET	5.00	70.00
1	EA	FUEL SURCHARGE	50.41	50.41
-1	EA	94# PORTLAND CEMENT 1/11 CREDIT RETURN	-9.50	-9.50
		DMWSE FROM TICKET 17934		
		Stampbook		

ORDER NO. 179389
 ORDER DATE: 6/30/14
 DEL. DATE: 6/30/14
 TAX: 001 LOUISBURG, KS
 ORDER 79803

QUANTITY	UNIT	DESCRIPTION	PRICE	TOTAL
240	EA	94# PORTLAND CEMENT 1/11	9.50	2,280.00
14	EA	RETURABLE PALLET	15.00	210.00
14	EA	SHRINK WRAPPED PALLET	5.00	70.00
1	EA	FUEL SURCHARGE	50.41	50.41
-1	EA	94# PORTLAND CEMENT 1/11 CREDIT RETURN	-9.50	-9.50
		DMWSE FROM TICKET 17934		
		Stampbook		

4288.91

117062

True Value

PAGE NO 1

MOSSMAN LUMBER COMPANY
 1/2 Mile North of Louisburg
 27295 Mitchell Rd.
 P.O. Box 729
 Louisburg, Kansas 66054
 913-637-2955 • 1-800-621-1764