



QUALITY OILWELL CEMENTING, INC.
 PO Box 32 - 740 West Wichita Ave, Russell KS 67665
 Phone: 785-324-1041 fax: 785-483-1087
 Email: cementing@ruraltel.net

Date: 4/22/2012
 Invoice # 5495

P.O.#:

Due Date: 5/22/2012

Division: Russell

Invoice

Contact:
 Samuel Gary Jr & Associates Inc
Address/Job Location:
 Samuel Gary Jr & Associates Inc
 1815 11th Street
 Great Bend, KS 67530

Reference:
 NILHAS TRUST 1-30

Description of Work:
 PROD LONG STRING

Services / Items Included:	Quantity	Price	Taxable	Item	Quantity	Price	Taxable
Labor		\$ 963.85	No	Auto Fill Float Shoe, 5 1/2"	1	\$323.00	Yes
Common-Class A	225	\$ 2,897.50	Yes	Pump Truck Mileage-Job to Nearest Camp	31	\$326.57	No
Cement Port Collar, 5 1/2"	1	\$ 2,638.89	Yes	Salt (Fine)	19	\$279.98	Yes
Gilsonite	1057	\$ 1,673.58	Yes	Latch Down Plug & Baffle, 5 1/2"	1	\$236.44	Yes
CFL 117	176	\$ 1,144.39	Yes	Bulk Truck Mileage-Job to Nearest Bulk Plant	31	\$191.10	No
5 1/2" Basket	4	\$ 971.11	Yes	KCL	2	\$63.04	Yes
5 1/2" Turbolizer	10	\$ 612.22	Yes				
Bulk Truck Mat-Material Service Charge	254	\$ 536.22	No				
CD-110	117	\$ 494.00	Yes				
Mud Clear	500	\$ 390.56	Yes				
Defoamer A or CAF-38	50	\$ 369.44	Yes				

Invoice Terms:

Net 30

SubTotal: \$ 14,111.89

Discount Available ONLY if Invoice is Paid & Received within listed terms of invoice: \$ (2,116.78)

SubTotal for Taxable Items: \$ 10,280.03

SubTotal for Non-Taxable Items: \$ 1,715.08

Total: \$ 11,995.11

Tax: \$ 699.04

6.80% Trego County Sales Tax

Amount Due: \$ 12,694.15

Applied Payments:

Balance Due: \$ 12,694.15

Thank You For Your Business!

Past Due Invoices are subject to a service charge (annual rate of 24%)

This does not include any applicable taxes unless it is listed.

©2008-2013 Straker Investments, LLC. All rights reserved.

RECEIVED

APR 27 2012

**SAMUEL GARY JR.
& ASSOCIATES, INC.**

REG COMP W/O FOR CR

Account	8200-238
Well/Prospect	
Deck	
AFE	
Approval	
Description	

QUALITY OILWELL CEMENTING, INC.

Federal Tax I.D.# 20-2886107

Phone 785-483-2025
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 5495

Date	Sec.	Twp.	Range	County	State	On Location	Finish
4-19-12	30	11	21	Trego	Ks		9:30 AM
Lease Nilhas trust	Well No. 1-30	Location I-70 + Riga Rd Exit, N to H Rd, 2w to 360 Ave					
Contractor Discoverey #4	Owner 1 3/4 N, w/into 1 mile			To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.			
Type Job Production	Hole Size 7 7/8"			T.D. 4090'	Charge To Sam Gary Jr. + Associates		
Csg. 5 1/2" 15 1/2# New	Depth 4074.24'			Street			
Tbg. Size	Depth			City			
Tool	Depth			State			
Cement Left in Csg. 4220'	Shoe Joint 4220'			The above was done to satisfaction and supervision of owner agent or contractor.			
Meas Line	Displace 96 BLS			Cement Amount Ordered 25 5x @ - Pro C-160% Salt 5% Gilsonite 1/2# FIC seal, 3% CB-110, .8% CFL-117			
EQUIPMENT				.25% CAF -38, 20 BL KCL 500 gal Mud Clear 48			
Pumptrk 9	No. Cementer	Helper Matt		Common 225			
Bulktrk 14	No. Driver	Wick		Poz. Mix			
Bulktrk pu.	No. Driver	Rick		Gel. CD-110 117#			
JOB SERVICES & REMARKS				Calcium			
Remarks:				Hulls			
Rat Hole 30 5x				Salt 19			
Mouse Hole 15 5x				Flowseal 56 #			
Centralizers 1, 3, 5, 7, 9, 11, 13, 15, 56, 58				Kol-Seal 1057 #			
Baskets 3, 9, 15, 56				Mud CLR 48 500 gal			
D/V or Port Collar				CFL-117 or CD110 CAF 38 50#			
Pipe on bottom, break Circulation				Sand 176 #			
pump 500 gal Mud Clear 48				Handling 254			
plug Rat hole w/ 30 5x				Mileage			
plug mouse hde w/ 15 5x				FLOAT EQUIPMENT			
Cement 5 1/2" casing w/ 180 5x				Guide Shoe			
shut down, wash pump + lines				Centralizer 10 turbos			
Released plug, Displaced with				Baskets 4			
96 BLS of water.				AFU Inserts			
Lift pressure 900 #				Float Shoe 1			
land plug to 1400 #				Latch Down 1			
Released + held.				1- Post Collar			
				1- Rotating head Assy			
				Pumptrk Charge proal / ong string			
				Mileage 31			
				Tax			
				Discount			
				Total Charge			
Signature 							