

Dale Jackson Production Co.
Box 266, Mound City, Ks 66056



Cell # 620-363-2683

Office # 913-795-2991

Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 348' of 2 7/8" 8 round pipe	Cemented: 50 sacks	Hole Size: 5 5/8"
SN:	Packer:	TD: 351'
Plugged:	Bottom Plug:	

Well

Well #: 16W-14
Location: N2,S2,N2, S9-T20-R23E
County: Linn
FSL: 3630' S
FEL: 2640' E
API#: 15-107-24987-00-00
Started: 7/18/14
Completed: 7/21/14

Log

Lease:	Stainbrook
Owner:	Bobcat Oilfield Services Inc
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
2	2	Top Soil	4	337	Shale (Limey)
1	3	Clay	9	346	Shale
28	31	Lime	4	350	Lime
4	35	Shale	TD	351	Black Shale
2	37	Black Shale			
1	38	Shale			
22	60	Lime			
3	63	Shale			
2	65	Black Shale			
3	68	Lime			
4	72	Shale			
6	78	Lime			
1	79	Black Shale			
4	83	Shale			
11	94	Light Shale (Limey)			
42	136	Shale			
19	155	Sandy Shale			
41	196	Shale			
5	201	Light Shale (Limey)			
1	202	Light Shale (Oil Sand Stks)			
4	206	Light Shale			
15	221	Shale			
2	223	Coal			
8	231	Shale			
2	233	Lime			
30	263	Shale			
8	271	Lime			
1	272	Shale			
1	273	Oil Sand (Shaley)(Good Bleed)			
1.5	274.5	Oil Sand (Some Shale)(Good Bleed)			
6	280.5	Oil Sand (Good Bleed)			
2	282.5	Oil Sand (Limey)(Good Bleed)			
3	285.5	Oil Sand (Very Shaley)(Good Bleed)			
2	287.5	Sandy Shale(Oil Sand Stks)(Poor Bleed)			
11.5	299	Oil Sand (Very Shaley)(Good Bleed)			
2	301	Oil Sand (Some Shale)(Good Bleed)			
5.5	306.5	Shale(Oil Sand Stks)(Poor Bleed)			
2.2	309	Oil Sand (Very Shaley)(Fair Bleed)			
2	311	Oil Sand (Shaley)(Good Bleed)			SET SURFACE - 12:30 PM - 7/18/14
7	318	Shale			CALLED IN 11:29 AM - TALKED TO MICHELLE
4	322	Coal			LONGSTRING - 348' of 2 7/8" 8' ROUND PIPE
4	326	Shale			SET TIME 1:00 PM - 7/21/14
7	333	Lime			CALLED IN 11:21 AM - TALKED TO BROOKE



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 16W-14
Location: N2,S2,N2, S9-T20-R23E
County: Linn
FSL: 3630' S
FEL: 2640' E
API#: 15-107-24987-00-00
Started: 7/18/14
Completed: 7/21/14

Lease :	Stainbrook
Owner:	Bobcat Oilfield Services Inc
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	273	0:00	-----	Oil Sand (Some Shale)(Good Bleed)	274.5
1	274	1:00	1		
2	275	1:45	.75	Oil Sand (Good Bleed)	280.5
3	276	2:30	.75		
4	277	3:30	1		
5	278	4:15	.75		
6	279	5:00	.75		
7	280	5:45	.75		
8	281	7:00	1.25	Oil Sand (Limey)(Good Bleed)	282.5
9	282	8:30	1.5		
10	283	9:45	1.25	Oil Sand (Very Shaley)(Good Bleed)	285.5
11	284	10:45	1		
12	285	12:00	1.25		
13	286	13:00	1	Sandy Shale (Oil Sand Stks)(Poor Bleed)	287.5
14	287	14:15	1.25		
15	288	15:30	1.25	Oil Sand (Very Shaley)(Good Bleed)	
16	289	16:30	1		
17	290	17:15	.75		
18	291	18:15	1		
19	292	19:15	1		
20	293	20:15	1		



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 16W-14
Location: N2,S2,N2, S9-T20-R23E
County: Linn
FSL: 3630' S
FEL: 2640' E
API#: 15-107-24987-0-00
Started: 7/18/14
Completed: 7/21/14

Lease :	Stainbrook
Owner:	Bobcat Oilfield Services Inc
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #2

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	293	0:00	-----	Oil Sand (Very Shaley)(Good Bleed)	299
1	294	1:00	1		
2	295	2:30	1.5		
3	296	4:00	1.5		
4	297	5:15	1.25		
5	298	6:30	1.25		
6	299	7:30	1	Oil Sand (Some Shale)(Good Bleed)	301
7	300	8:30	1		
8	301	9:30	1	Shale (Oil Sand Stks)(Poor Bleed)	306.5
9	302	10:45	1.25		
10	303	12:45	2		
11	304	14:00	1.25		
12	305	15:30	1.5		
13	306	17:15	1.75		
14	307	18:45	1.5	Oil Sand (Very Shaley)(Fair Bleed)	309
15	307	20:00	1.25		
16	309	21:30	1.5	Oil Sand (Shaley)(Good Bleed)	311
17	310	22:45	1.25		
18	311	24:00	1.25		
19	312	26:15	2.25	Shale	
20	313	29:00	2.75		

1805.66

[Handwritten signature]

QUANTITY	DESCRIPTION	UNIT	PRICE	TOTAL
200	800 SX FLY KSH CLASS C	EA	1.90	1,900.00
315	94# PORTLAND CEMENT 1/11	EA	9.50	2,992.50
14	RETURNABLE PALLET	EA	15.00	210.00
14	SHRINK WRAPPED PALLET	EA	5.00	70.00
1	FUEL SURCHARGE	EA	50.41	50.41
SUBTOTAL				4412.91
TAX				392.75
TOTAL AMOUNT				4805.66

Shanbrook
16W-14

CUSTOMER NO. _____
 ORDER NO. _____
 DATE: 7/14/14
 ORDER: 79960
 DEL. DATE: 7/14/14
 S.L.P.R.: RR ROBERT ROAD
 RR FOLTSBURG, KS
 TAX: _____
 DOC# 179437
 ***** INVOICE *****
 ORDER 79960

DATE	CLERK	TERMS	NET TOTAL	ORDER NO.	ORDER DATE
7/14/14				79960	7/14/14

True Value

MOSSMAN LUMBER COMPANY
 1/2 Mile North of Louisville
 27295 Mahaff Rd
 P.O. Box 129
 Louisville, Kansas 66053
 913-837-2955 • 1-800-521-1764

