

Dale Jackson Production Co/  
Box 266, Mound City, Ks 66056



Cell # 620-363-2683

Office # 913-795-2991

Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 348' of 2 7/8" 8 round pipe	Cemented: 50 sacks	Hole Size: 5 5/8"
SN:	Packer:	TD: 351'
Plugged:	Bottom Plug:	

Well #: 32W-14
Location: S2,S2,N2, S9-T20-R23E
County: Linn
FSL: 2970' S
FEL: 2640' E
API#: 15-107-25002-00-00
Started: 7/22/14
Completed: 7/23/14

Well

Log

Lease:	Stainbrook
Owner:	Bobcat Oilfield Services Inc
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
2	2	Top Soil	10	334	Lime
1	3	Clay	10	344	Shale
25	28	Lime	4	348	Lime
4	32	Shale	TD	351	Black Shale
3	35	Black Shale			
1	36	Shale			
20	56	Lime			
2	58	Shale			
2	60	Black Shale			
3	63	Lime			
5	68	Shale			
5	73	Lime			
1	74	Black Shale			
4	78	Shale			
2	80	Lime			
11	91	Light Shale (Limey)			
41	132	Shale			
18	150	Sandy Shale			
37	187	Shale			
1	188	Coal			
4	192	Shale			
9	201	Light Shale (Limey)			
16	217	Shale			
1	218	Coal			
8	226	Shale			
4	230	Lime			
28	258	Shale			
9	267	Lime			
1	268	Shale			
1	269	Light Shale			
2	271	Light Shale(Oil Sand Stks)(Poor Bleed) (Limey)			
5	276	Oil Sand (Very Shaley)(Fair Bleed)			
5	281	Oil Sand (Good Bleed)			
2	283	Oil Sand (Some Shale & Lime)(Fair Bleed)			
6	289	Sandy Shale(Oil Sand Stks)(Poor Bleed)			
3	292	Oil Sand (Some Shale)(Good Bleed)			
2.5	294.5	Oil Sand (Shaley)(Fair Bleed)			
2	296.5	Shale (Oil Sand Stks)(Poor Bleed)			
1	297.5	Oil Sand (Very Shaley)(Fair Bleed)			SET SURFACE - 1:00 PM - 7/22/14
6	303.5	Shale (Oil Sand Stks)(Poor Bleed)			CALLED IN 11:45 AM - TALKED TO BROOKE
13.5	317	Shale			LONGSTRING - 348' of 2 7/8" 8' ROUND PIPE
3	320	Coal			SET TIME 1:30 PM - 7/23/14
4	324	Shale			CALLED IN 12:43 PM - TALKED TO BROOKE



Dale Jackson Production Co.  
 Box 266, Mound City, Ks 66056  
 Cell # 620-363-2683  
 Office # 913-795-2991

Well #: 32W-14
Location: S2,S2,N2,S9-T20-R23E
County: Linn
FSL: 2970' S
FEL: 2640' E
API#: 15-107-25002-00-00
Started: 7/22/14
Completed: 7/23/14

Lease :	Stainbrook
Owner:	Bobcat Oilfield Services Inc
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

# Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	272	0:00	-----	Oil Sand (Very Shaley)(Fair Bleed)	276
1	273	0:45	.75		
2	274	1:45	1		
3	275	3:00	1.25		
4	276	4:00	1		
5	277	5:00	1	Oil Sand (Good Bleed)	281
	Lockedup	Start at	277.5		
6	278	0:30	.5		
7	279	1:15	.75		
8	280	2:15	1		
9	281	3:00	.75	Oil Sand (Some Shale & Lime)(Fair Bleed)	283
10	282	4:00	1		
11	283	5:00	1		
12	284	6:30	1.5	Sandy Shale (Oil Sand Stks)(Poor Bleed)	289
13	285	8:00	1.5		
14	286	9:00	1		
15	287	10:30	1.5		
16	288	11:45	1.25		
17	289	13:00	1.25		
18	290	14:15	1.25		
19	291	15:15	1		
20	292	16:15	1	Oil Sand (Some Shale)(Good Bleed)	





Dale Jackson Production Co.  
 Box 266, Mound City, Ks 66056  
 Cell # 620-363-2683  
 Office # 913-795-2991

Well #: 32W-14
Location: S2,S2,N2, S9-T20-R23E
County: Linn
FSL: 2970' S
FEL: 2640' E
API#: 15-107-25002-00-00
Started: 7/22/14
Completed: 7/23/14

Lease :	Stainbrook
Owner:	Bobcat Oilfield Services Inc
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

## Core Run #2

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	292	0:00	-----	Oil Sand (Shaley)(Fair Bleed)	294.5
1	293	1:15	1.25		
2	294	2:30	1.25		
3	295	4:00	1.5	Shale (Oil Sand Stks)(Poor Bleed)	296.5
4	296	5:45	1.75		
5	297	7:00	1.25	Oil Sand (Very Shaley)(Fair Bleed)	297.5
6	298	8:00	1		
7	299	9:30	1.5	Shale (Oil Sand Stks)(Poor Bleed)	303.5
8	300	10:45	1.25		
9	301	12:15	1.5		
10	302	13:45	1.5		
11	303	16:00	2.25		
12	304	17:15	1.25	Shale	
13	305	19:30	2.25		
14	306	22:00	2.5		
15	307	24:30	2.5		
16	308				
17					
18					
19					
20					





1/2 Mile North of Louisburg  
27295 Matcoff Rd.  
P.O. Box 729  
Louisburg, Kansas 66053  
913-837-2955 • 1-800-521-1764

# MOSSMAN LUMBER COMPANY

*True Value*

CUSTOMER NO.	JOB NO.	PURCHASE ORDER NO.	REFERENCE	TERMS	CLEAR	DATE	TIME
200			ORDR # 79360	NET 10TH	RR	7/14/14	13:39

REPAY TO:  
SUITE 100  
100 WEST BENTLEY  
LOUISBURG, MO 66053

11490 WEST 150 HIGHWAY  
LOUISBURG, MO 66053

DEL. DATE: 7/14/14 TENNESSEE

SLSPR: RR ROBERT ROAD  
TAX: 001 LOUISBURG, KS

DOC# 179637

\*\*\*\*\*

\* INVOICE \*

\*\*\*\*\*

ORDR 79360

QUANTITY SHIPPED	QUANTITY ORDERED	UNIT	DESCRIPTION	UNITS	PRICE PER UNIT	EXTENSION
200		EA	80# 5X FLY ASH CLASS C	200	5.45 /EA	1,090.00
315		EA	94# PORTLAND CEMENT 1/II	315	9.50 /EA	2,992.50
14		EA	RETURNABLE PALLET	14	15.00 /EA	210.00
14		EA	SHRINK WRAPPED PALLET	14	5.00 /EA	70.00
1		EA	FUEL SURCHARGE	1	50.41 /EA	50.41
				4,805.56		

*Stainbrook  
326W-14*

*EC*

AMOUNT CHARGED TO STORE ACCOUNT # 4,805.56  
 TAXABLE 4412.91  
 NON-TAXABLE 0.00  
 SUBTOTAL 4412.91

TAX AMOUNT 392.75  
 TOTAL AMOUNT 4805.66

*4805.66*

RECEIVED BY

X