

Cell # 620-363-2683

Dale Jackson Production Co.
Box 266, Mound City, Ks 66056

Office # 913-795-2991



Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 339' of 2 7/8" 8 round pipe	Cemented: 50 sacks	Hole Size: 5 5/8"
SN:	Packer:	TD: 341'
Plugged:	Bottom Plug:	

Well #: 31W-14
Location: SE,SE,NW, S9-T20-R23E
County: Linn
FSL: 2970' S
FEL: 2970' E
API#: 15-107-25001-00-00
Started: 7/23/2014
Completed: 7/24/2014

Well

Log

Lease:	Stainbrook
Owner:	Bobcat Oilfield Services Inc
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	Top Soil			
1	2	Concrete			
25	27	Lime			
3	30	Shale			
2	32	Black Shale			
2	34	Shale			
19	53	Lime			
3	56	Shale			
2	58	Black Shale			
3	61	Lime			
5	66	Shale			
6	72	Lime			
1	73	Black Shale			
3	76	Shale			
11	87	Light Shale (Limey)			
43	130	Shale			
15	145	Sandy Shale			
50	195	Shale			
6	201	Light Shale (Limey)			
17	218	Shale			
3	221	Coal			
7	228	Shale			
4	232	Lime			
28	260	Shale			
9	269	Lime			
1	270	Shale (Limey)			
6	276	Light Shale (Limey)			
2	278	Light Shale(Oil Sand Stks)(Poor Bleed)			
1	279	Oil Sand (Shaley)(Good Bleed)			
4.5	283.5	Oil Sand (Good Bleed)			
1	284.5	Lime (Poor Bleed)			
7	291.5	Oil Sand (Very Shaley)(Fair Bled)			
2.5	294	Shale (Oil Sand Stks)(Poor Bleed)			
2.5	296.5	Oil Sand (Shaley)(Good Bleed)			
8	304.5	Shale (Oil Sand Stks)(Poor Bleed)			
.5	305	White Sand			
12	317	Shale			
3	320	Coal			
3	323	Shale			SET SURFACE - 2:00 PM - 7/23/14
11	334	Lime			CALLED IN 12:43 PM - TALKED TO BROOKE
TD	341	Shale			LONGSTRING - 339' of 2 7/8" 8' ROUND PIPE
					SET TIME 1:00 PM - 7/24/14
					CALLED IN 11:18 AM - TALKED TO BROOKE



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 31W-14
Location: SE,SE,NW, S9-T20-R23E
County: Linn
FSL: 2970' S
FEL: 2970' E
API#: 15-107-25001-00-00
Started: 7/23/14
Completed: 7/24/14

Lease :	Stainbrook
Owner:	Bobcat Oilfield Services Inc
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	281	0:00	-----	Oil Sand (Good Bleed)	283.5
1	282	0:45	.75		
2	283	1:45	1		
3	284	2:45	1	Lime (Poor Bleed)	284.5
4	285	3:45	1		
5	286	4:30	.75	Oil Sand (Very Shaley)(Fair Bleed)	291.5
6	287	5:45	1.25		
7	288	6:45	1		
8	289	8:00	1.25		
9	290	9:00	1		
10	291	10:30	1.5		
11	292	12:00	1.5	Shale (Oil Sand Stks)(Poor Bleed)	294
12	293	13:15	1.25		
13	294	14:30	1.25		
14	295	15:30	1	Oil Sand (Shaley)(Good Bleed)	296.5
15	296	16:45	1.25		
16	297	18:00	1.25	Shale (Oil Sand Stks)(Poor Bleed)	
17	298	19:15	1.25		
18	299	20:30	1.25		
19	300	22:00	1.5		
20	301	23:30	1.5		



MOSSMAN LUMBER COMPANY

1/2 Mile North of Louisburg
27295 Matcoff Rd.
P.O. Box 729
Louisburg, Kansas 66053
913-637-2955 • 1-800-521-1764

True Value

CUSTOMER NO.	JOB NO.	PURCHASE ORDER NO.	REFERENCE	TERMS	CLERK	DATE	TIME
			ORDER # 79960	NET 10%	RR	7/14/14	11:39

DELIVER TO:
BLUES INN
C/O WEST UNITY
LOUISBURG, KS 66053

11490 WEST 150 HIGHWAY

DEL. DATE: 7/14/14 TERRASSI
SLSR: RR ROBERT RAOH
TAX : 001 LOUISBURG, KS

DOC# 179437

INVOICE #

ORDER 79960

QUANTITY SHIPPED	QUANTITY ORDERED	UNIT	DESCRIPTION	UNITS	PRICE PER	EXTENSION
200		EA	80# 5X FLY ASH CLASS C	200	3.45 /EA	1,090.00
315		EA	94# PORTLAND CEMENT 1/11	315	9.50 /EA	2,992.50
14		EA	RETURNABLE PALLET	14	15.00 /EA	210.00
14		EA	SHRINK WRAPPED PALLET	14	5.00 /EA	70.00
1		EA	FUEL SURCHARGE	1	50.41 /EA	50.41
				4,805.56	TAXABLE	4412.91
					NON-TAXABLE	0.00
					SUBTOTAL	4412.91

*Stainbrook
31W74*

EC

11805.66

9-04-2000 0:56AM FROM MOSSMAN LUMBER 9138375871

X RECEIVED BY

TAX INVOICE 792.75
TOTAL AMOUNT 4805.66