

Cell # 620-363-2683

Dale Jackson Production Co.
Box 266, Mound City, Ks 66056

Office # 913-795-2991



Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 335' of 2 7/8" 8 round pipe	Cemented: 50 sacks	Hole Size: 5 5/8"

SN: 272'	Packer:	TD: 341'
Plugged:	Bottom Plug:	

Lease:	Stainbrook
Owner:	Bobcat Oilfield Services Inc
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Well #: 31-14
Location: SW,SE,SE,NW, S9-T20-R23E
County: Linn
FSL: 2805' S
FEL: 3161' E
API#: 15-107-24983-00-00
Started: 7/29/2014
Completed: 7/30/2014

Log Well

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
2	2	Top Soil			
1	3	Clay			
18	21	Lime			
5	26	Shale			
3	29	Black Shale			
1	30	Shale			
21	51	Lime			
2	53	Shale			
1	54	Black Shale			
3	57	Lime			
5	62	Shale			
7	69	Lime			
1	70	Black Shale			
3	73	Shale			
8	81	Light Shale (Limey)			
47	128	Shale			
26	154	Sandy Shale			
60	214	Shale			
2	216	Coal			
7	223	Shale			
3	226	Lime			
29	255	Shale			
8	263	Lime			
3	266	Shale (Limey)			
7	273	Light Shale(Oil Sand Stks)(Poor Bleed)			
6.5	279.5	Oil Sand (Good Bleed)			
4.5	284	Sandy Shale(Oil Sand Stks)(Poor Bleed)			
3	287	Oil Sand (Shaley)(Good Bleed)			
2	289	Shale (Oil Sand Stks)(Poor Bleed)			
3.5	292.5	Oil Sand (Shaley)(Good Bleed)			
8.5	301	Shale (Oil Sand Stks)(Poor Bleed)			
1	302	Oil Sand (Some Shale)(Good Bleed)			
1	303	Shale (Oil Sand Stks)(Poor Bleed)			
10	313	Shale			
2	315	Coal			
7	322	Shale			
5	527	Lime			
4	331	Shale(Limey)			
8	339	Shale			SET SURFACE -- 2:00 PM -- 7/29/14
TD	341	Lime			CALLED IN 11:41 AM -- TALKED TO BROOKE
					LONGSTRING -- 335' of 2 7/8" 8' ROUND PIPE
					SET TIME 12:30 PM -- 7/30/14
					CALLED IN 11:27 AM - TALKED TO BROOKE



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 31-14
Location: SW,SE,SE,NW,S9-T20-R23E
County: Linn
FSL: 2805' S
FEL: 3161' E
API#: 15-107-24983-00-00
Started: 7/29/2014
Completed: 7/30/2014

Lease :	Stainbrook
Owner:	Bobcat Oilfield Services Inc
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	276	0:00	-----	Oil Sand (Good Bleed)	279.5
1	277	0:45	.75		
2	278	1:30	.75		
3	279	2:15	.75		
4	280	3:00	.75	Sandy Shale (Oil Sand Stks)(Poor Bleed)	284
5	281	4:00	1		
6	282	4:45	.75		
7	283	6:00	1.25		
8	284	7:00	1		
9	285	7:45	.75	Oil Sand (Shaley)(Good Bleed)	287
10	286	8:45	1		
11	287	9:45	1		
12	288	11:00	1.25	Shale (Oil Sand Stks)(Poor Bleed)	289
13	289	12:00	1		
14	290	13:00	1	Oil Sand (Shaley)(Good Bleed)	292.5
15	291	14:15	1.25		
16	292	15:30	1.25		
17	293	16:45	1.25	Shale (Oil Sand Stks)(Poor Bleed)	
18	294	18:00	1.25		
19	295	19:00	1		
20	296	20:15	1.25		

1805.66

[Handwritten signature]

RECEIVED BY

X

QUANTITY	DESCRIPTION	UNIT	PRICE	TOTAL
200	80# SX FLY ASH CLASS C	UNITS	1.45	290.00
315	94# PORTLAND CEMENT 1/11	UNITS	9.50	2,992.50
14	RETURNABLE PALLET	UNITS	15.00	210.00
14	SHRINK WRAPPED PALLET	UNITS	5.00	70.00
1	FUEL SURCHARGE	UNITS	50.41	50.41
NON-TAXABLE				0.00
TAX				442.91
TOTAL				4,805.56

Starbrook
31-14

ORDER NO. 179437
 DEL. DATE: 7/14/14
 RR ROBERT ROAD
 001 LOUISBURG, KS
 ORDER 79960
 INVOICE *
 TAX: \$1,598.00

True Value

MOSSMAN LUMBER COMPANY
 1/2 Mile North of Louisburg
 P.O. Box 729
 27255 Milled Rd.
 Louisburg, Kansas 66053
 913-837-2955 • 1-800-521-1764

