

Cell # 620-363-2683

Dale Jackson Production Co.
Box 266, Mound City, Ks 66056

Office # 913-795-2991



Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Longstring: 324' of 2 7/8" 8 round pipe	Cemented: 50 sacks	Hole Size: 5 5/8"
SN:	Packer:	TD: 331'
Plugged:	Bottom Plug:	
Lease:	Stainbrook	
Owner:	Bobcat Oilfield Services Inc	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	

Well #: 30W-14
Location: E2,SW,SE,NW,S9-T20-R23E
County: Linn
FSL: 2970' S
FEL: 3326' E
API#: 15-107-25000-00-00
Started: 7/30/2014
Completed: 7/31/2014

Log Well

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	Top Soil	TD	331	Lime
2	3	Clay			
22	25	Lime			
4	29	Shale			
2	31	Black Shale			
1	32	Shale			
22	54	Lime			
2	56	Shale			
2	58	Black Shale			
2	60	Lime			
6	66	Shale			
6	72	Lime			
1	73	Black Shale			
3	76	Shale			
10	86	Light Shale (Limey)			
46	132	Shale			
24	156	Sandy Shale			
36	192	Shale			
9	201	Light Sandy Shale (Limey)			
16	217	Shale			
1	218	Coal			
10	228	Shale			
4	232	Lime			
25	257	Shale			
9	266	Lime			
2	268	Shale (Limey)			
4	272	Light Shale(Some Lime)			
2	274	Oil Sand (Shaley)(Good Bleed)			
7.5	281.5	Oil Sand (Good Bleed)			
1.5	283	Shale (Oil Sand Stks)(Fair Bleed)			
2.5	285.5	Oil Sand (Very Shaley)(Fair Bleed)			
3	288.5	Oil Sand (Some Shale)(Good Bleed)			
5.5	294	Oil Sand (Shaley)(Good Bleed)			
1	295	Shale (Oil Sand Stks)(Fair Bleed)			
4.5	299.5	Oil Sand (Very Shaley)(Fair Bleed)			
2.5	302	Shale			
1	303	Oil Sand (Some Shale)(Fair Bleed)			
.5	303.5	Shale			
1	304.5	Oil Sand (Limey)(Fair Bleed)			SET SURFACE - 1:00 PM - 7/30/14
.5	305	Oil Sand (Limey)(Fair Bleed)(Coal Stks)			CALLED IN 11:27 AM - TALKED TO BROOKE
11	316	Shale			LONGSTRING - 324' of 2 7/8" 8' ROUND PIPE
2	318	Coal			SET TIME 12:30 PM - 7/31/14
5	323	Shale			CALLED IN 11:16 AM - TALKED TO BROOKE



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 30W-14
Location: E2,SW,SE,NW,S9-T20-R23E
County: Linn
FSL: 2970' S
FEL: 3376' E
API#: 15-107-25000-00-00
Started: 7/30/2014
Completed: 7/31/2014

Lease :	Stainbrook
Owner:	Bobcat Oilfield Services Inc
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	276	0:00	-----	Oil Sand (Good Bleed)	281.5
1	277	0:45	.75		
2	278	1:30	.75		
3	279	2:15	.75		
4	280	3:15	1		
5	281	4:00	.75		
6	282	5:00	1	Shale (oil Sand Stks)(Fair Bleed)	283
7	283	6:00	1		
8	284	7:00	1	Oil Sand (Very Shaley)(Fair Bleed)	285.5
9	285	8:00	1		
10	286	9:00	1	Oil Sand (Some Shale)(Good Bleed)	288.5
11	287	9:45	.75		
12	288	10:45	1		
13	289	11:45	1	Oil Sand (Shaley)(Good Bleed)	294
14	290	12:45	1		
15	291	14:00	1.25		
16	292	14:45	.75		
17	293	15:45	1		
18	294	16:45	1		
19	295	18:15	1.2	Shale (Oil Sand Stks)(Poor Bleed)	295
20	296	20:15	2	Oil Sand (Very Shaley)(Fair Bleed)	



Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683
 Office # 913-795-2991

Well #: 30W-14
Location: E2,SW,SE,NW,S9-T20-R23E
County: Linn
FSL: 2970' S
FEL: 3376' E
API#: 15-107-25000-00-00
Started: 7/30/2014
Completed: 7/31/2014

Lease :	Stainbrook
Owner:	Bobcat Oilfield Services Inc
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #2

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	296	0:00	-----	Oil Sand (Very Shaley)(Fair Bleed)	299.5
1	297	1:00	1		
2	298	2:00	1		
3	299	3:30	1.5		
4	300	4:45	1.25	Shale	302
5	301	6:45	2		
6	302	8:15	1.5		
				Oil Sand (Some Shale)(Fair Bleed)	303
7	303	10:00	1.75	Shale	303.5
8	304	11:45	1.75	Oil Sand (Limey)(Fair Bleed)	304.5
9	305	13:15	1.5	Oil Sand (Limey)(Fair Bleed)(Coal Stks)	305
				Shale	
10	306	15:15	2		
11	307	17:45	2.5		
12	308				
13					
14					
15					
16					
17					
18					
19					
20					



1/2 Mile North of Louisa
27295 Metcalf Rd.
P.O. Box 729
Louisburg, Kansas 66053
913-637-2955 • 1-800-521-1764

MOSSMAN LUMBER COMPANY

True Value.

CUSTOMER NO.	JOB NO.	PURCHASE ORDER NO.	REFERENCE	TERMS	CLERK	DATE	TIME
			79960	NET 10TH		7/14/14	13:39

REPEAT ON
SHEET 103
FOR NEXT ENTRY
LEADERS

11498 (RED) 152 (HARD)

DEL. DATE: 7/14/14 TERMS: 10/10
SLSR: RR ROBERT ROAD
TAX: 001 LOUISBURG, KS

DOC# 179637

INVOICE #

ORDR 79960

QUANTITY SHIPPED	QUANTITY ORDERED	UNIT	DESCRIPTION	UNITS	PRICE/EA	EXTENSION
200		EA	80# 5X FLY ASH CLASS C	200	3.45 /EA	1,030.00
315		EA	94# PORTLAND CEMENT 1/11	315	9.50 /EA	2,992.50
14		EA	RETURNABLE PALLET	14	15.00 /EA	210.00
14		EA	SHRINK WRAPPED PALLET	14	5.00 /EA	70.00
1		EA	FUEL SURCHARGE	1	50.41 /EA	50.41
				4,805.56		

*Stainbrook
30W-14*

AMOUNT CHARGED TO STORE ACCOUNT # 4,805.56
TAXABLE 4412.91
NON-TAXABLE 0.00
SUBTOTAL 4412.91

RECEIVED BY _____

TAX AMOUNT 392.75
TOTAL AMOUNT 4805.66

4805.66

9-04-2000 0:56AM FROM MOSSMAN LUMBER 9138375871