



CONSOLIDATED
Oil Well Services, LLC

264817

TICKET NUMBER 44923

LOCATION Ottawa, KS

FOREMAN Casey Kennedy

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

**FIELD TICKET & TREATMENT REPORT
CEMENT**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
12/17/13	4015	Chase # P-8	NW 33	17	21	FR
CUSTOMER			TRUCK# DRIVER TRUCK# DRIVER			
STC Oil Inc.			729 Cas Ken ✓ Safety Meeting			
MAILING ADDRESS			57 Gar Moo ✓			
35688 Plum Creek			548 Mik Aga ✓			
CITY	STATE	ZIP CODE	675 Kei Det ✓			
Osawatimie	KS	66064				
JOB TYPE <u>logstring</u>	HOLE SIZE <u>6 3/4"</u>	HOLE DEPTH <u>800'</u>	CASING SIZE & WEIGHT <u>4 1/2"</u>			
CASING DEPTH <u>785'</u>	DRILL PIPE	TUBING	OTHER			
SLURRY WEIGHT	SLURRY VOL	WATER gal/sk	CEMENT LEFT in CASING			
DISPLACEMENT <u>12.52 bbls</u>	DISPLACEMENT PSI	MIX PSI	RATE <u>4 bpm</u>			

REMARKS: held safety meeting, established circulation, mixed & pumped 200 # Premium Gel, circulated out of pit to condition hole, mixed & pumped 7 bbls dye marker, mixed & pumped 84 sks OWC cement w/ 1/4 # Floseal per sk, dye marker to surface, flushed pump clean, pumped 4 1/2" rubber plug to casing ID w/ 12.52 bbls fresh water, pressured to 800 PSI, released pressure, washed up equipment.

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE		1085.00
5406	15 mi	MILEAGE		63.00
5402	785'	casing footage		
5407	1/2 minimum	tan mileage		184.00
5502C	1.5 hrs	SD Vac		135.00
1126	84 sks	OWC cement		1659.00
1118B	200 #	Premium Gel		44.00
1107	21 #	Floseal		51.87
4404	1	4 1/2" rubber plug		47.25
			7.65%	SALES TAX ESTIMATED TOTAL
				137.86
				3406.98

completed

Revin 3737

AUTHORIZATION [Signature] TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form