



CONSOLIDATED
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

268069

TICKET NUMBER 46860
LOCATION Oakley Ks
FOREMAN Jerry Y
Miles S

FIELD TICKET & TREATMENT REPORT
CEMENT

| DATE | CUSTOMER # | WELL NAME & NUMBER | SECTION | TOWNSHIP | RANGE | COUNTY |
|-----------------|------------|------------------------------|---|-----------|---------|---------|
| 5-9-14 | 7251 | Coakes/Collingwood Unit 1-22 | 22 | 20s | 38w | Wichita |
| CUSTOMER | | Red Oak Energy | Leoti W to 3,5 to 8B E 104, 1/2 S, E into | | | |
| MAILING ADDRESS | | | | | | |
| CITY | STATE | ZIP CODE | TRUCK # | DRIVER | TRUCK # | DRIVER |
| | | | 5287118 | Michael R | | |
| | | | 5290T127 | Steven O | | |
| | | | assist | Doc K | | |

JOB TYPE long string HOLE SIZE 7 7/8 HOLE DEPTH 5700' CASING SIZE & WEIGHT 5 1/2 15.5
CASING DEPTH 5085.58 DRILL PIPE _____ TUBING _____ OTHER PC 466 @ 23.28
SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 42.13'
DISPLACEMENT 120 bbl DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Sally meeting & rigup on Merita 22 run float Equipt centralizers on 1,3,5,7,9,15,17,65,67 baskets on 8 & 66 scratchers on 6x2, 7x3, 8x3, 9x2, circled for 20 min @ j 67, run casing to bottom pump doll then circulate this pump 5 bbl H₂O, 500 gal mud flush, 5 H₂O brine mix 180 sks OWC with 5# Kolseal prsk shut down release plug wash pump & lines and displace w/ 121 bbl H₂O plug landed @ 1500' & with 1000' lift psi released back at float held

Thank you Jerry & Crew

30 sks Rh 15 mh

Part Collar S.N. 1402389

| ACCOUNT CODE | QUANTITY or UNITS | DESCRIPTION of SERVICES or PRODUCT | UNIT PRICE | TOTAL |
|--------------|-------------------|------------------------------------|--------------------|--------------------|
| 5401P | 1 | PUMP CHARGE | 3400 ⁰⁰ | 3400 ⁰⁰ |
| 5406 | 60 | MILEAGE | 525 | 31500 |
| 5407a | 10.6 | ton mileage delivery | 175 | 11300 |
| 1126 | 225 SKS | OWC | 23.70 | 5332.50 |
| 1110 A | 1125 # | Kolseal | 56 | 63000 |
| 4314 | 10 | reciprocating scratchers | 82 ⁰⁰ | 820 ⁰⁰ |
| 1144g | 500 gal | WFR mud flush | 1 ⁰⁰ | 500 ⁰⁰ |
| 4159 | 1 | 5 1/2 AFM float shoe (W) | 433.75 | 433.75 |
| 4454 | 1 | 5 1/2 latchman assy (W) | 567 ⁰⁰ | 567 ⁰⁰ |
| 4130 | 9 | 5 1/2 centralizers (W) | 61 ⁰⁰ | 549 ⁰⁰ |
| 4104 | 2 | 5 1/2 baskets (W) | 290 ⁰⁰ | 580 ⁰⁰ |
| 4285 | 1 | 5 1/2 part collar (I) | 2178 ⁰⁰ | 2178 ⁰⁰ |
| | | Subtotal | | 16,418.25 |
| | | 5% disc | | 1,641.83 |
| | | Subtotal | | 14,776.42 |
| | | SALES TAX | | 850.15 |
| | | ESTIMATED TOTAL | | 15,626.57 |

Revin 3737

AUTHORIZATION [Signature]

TITLE Agent

DATE _____

complete

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



268043

TICKET NUMBER 46854
 LOCATION Oakley Ks
 FOREMAN Jerry Y Wall

PO Box 884, Chanute, KS 66720
 620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
 CEMENT

| DATE | CUSTOMER # | WELL NAME & NUMBER | SECTION | TOWNSHIP | RANGE | COUNTY |
|----------------------------|------------|-------------------------------|--|----------|---------|---------|
| 5-3-14 | 7251 | Coakes / Collingwood Unit #22 | 22 | 205 | 38W | Wichita |
| CUSTOMER Red Oak Energy | | | Leoti West to 3 South to 8B East to 4 1/2 S E into | | | |
| MAILING ADDRESS | | | TRUCK # | DRIVER | TRUCK # | DRIVER |
| CITY | | | 399 | Jeremy R | | |
| STATE | | | 397 | Cody R | | |
| ZIP CODE | | | | | | |

JOB TYPE Surface HOLE SIZE 12 1/4 HOLE DEPTH 351 CASING SIZE & WEIGHT 8 5/8 24
 CASING DEPTH 351.55 DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT 14.8 SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 42.24
 DISPLACEMENT 19.70 DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety meeting swing up on Martin 22 baffle plate top shoe jt run casing to bottom break circulation w/ light hook up to truck mix 270 sks com class A cement with 3% calcium chloride 22% gel release plug wash up & displace with 19.7 bbl H₂O & shut in. plug loaded @ 400 psi circulated approx 8 bbl to pit

*Cement
did circulate*

*Thank you
Jerry Y Wall*

| ACCOUNT CODE | QUANTITY or UNITS | DESCRIPTION of SERVICES or PRODUCT | UNIT PRICE | TOTAL |
|--------------|-------------------|------------------------------------|--------------------|-----------------------|
| 54015 | 1 | PUMP CHARGE | 1150 ⁰⁰ | 1150 ⁰⁰ ✓ |
| 5406 | 60 | MILEAGE | 52 ² | 3150 ⁰⁰ ✓ |
| 5407A | 12.7 | ton mileage delivery | 17 ² | 1333 ⁹⁸ ✓ |
| 11045 | 270 sks | com class A cement | 18 ⁵⁵ | 5,008 ⁵⁰ ✓ |
| 1102 | 761 # | calcium chloride | 97 | 738 ¹⁷ ✓ |
| 1118b | 507 # | gel | 21 | 136 ⁸⁷ ✓ |
| 4244 | 1 | 8 5/8 baffle plate | 82 ⁷⁵ | 82 ⁷⁵ ✓ |
| 4132 | 1 | 8 5/8 centralizer | 86 ⁰⁰ | 86 ⁰⁰ ✓ |
| | | | Subtotal | 8851.11 ✓ |
| | | | less 10% disc | 8851.11 ✓ |
| | | | Subtotal | 7966.00 ✓ |
| | | | SALES TAX | 443.93 ✓ |
| | | | ESTIMATED TOTAL | 8409.93 ✓ |

[Signature]

completed

Ravin 3737

AUTHORIZATION _____

TITLE _____

DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.