



CONSOLIDATED
Oil Well Services, LLC

268544

TICKET NUMBER 47208

LOCATION Ottawa, KS

FOREMAN Cassey Kennedy

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
5/28/14	7069	McCannell # 33	NE18	16	21	FR
CUSTOMER <u>Rensch Oil Well</u>						
MAILING ADDRESS <u>PO Box 520</u>						
CITY <u>Ottawa</u>		STATE <u>KS</u>	ZIP CODE <u>66067</u>			

TRUCK #	DRIVER	TRUCK #	DRIVER
729	Casken	✓ Safety	Medina
666	Garner	✓	
548	Matloc	✓	
370	Jas Ric	✓	

JOB TYPE longstring HOLE SIZE 5 7/8" HOLE DEPTH 730' CASING SIZE & WEIGHT 2 7/8" EUE
 CASING DEPTH 725' DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
 DISPLACEMENT 4.20 bbls DISPLACEMENT PSI _____ MIX PSI _____ RATE 5 bpm

REMARKS: held safety, waiting, established circulation, mixed & pumped 200 # Premium Gel followed by 10 bbls fresh water, mixed & pumped 108 sks 5450 Pozmix cement w/ 2% gal per sk, cement to surface, flushed pump clean, pumped 2 1/2" rubber plug to casing TD w/ 4.20 bbls fresh water, pressured to 800 PSI, released pressure, shut in casing.

Handwritten signature/initials

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE		1685.00 ✓
5406	15 mi.	MILEAGE		63.00 ✓
5402	725'	Casing footage		368.00 ✓
5407	minimum	van mileage		200.00 ✓
5502C	2 hrs	80 Vac		
1124	108 sks	5450 Pozmix cement	1242.00 ✓	
118B	381 #	Premium Gel	83.82 ✓	
		materials	1325.82	
		-30%	397.75 ✓	
		subtotal		928.07
4402	1	2 1/2" rubber plug		29.50 ✓
			3175.00	
		7.65%	SALES TAX	73.25 ✓
			ESTIMATED TOTAL	2746.82 ✓

Ravin 3737

AUTHORIZATION

Handwritten signature: Bob Rensch

TITLE

Handwritten signature: PR ES.

DATE

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.