



BASICSM
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

10244 NE Hwy. 61
P.O. Box 8613
Pratt, Kansas 67124
Phone 620-672-1201

FIELD SERVICE TICKET

1718 06562 A

DATE _____ TICKET NO. _____

DATE OF JOB 8-28-12	DISTRICT Kansas	NEW WELL <input checked="" type="checkbox"/>	OLD WELL <input type="checkbox"/>	PROD <input type="checkbox"/>	INJ <input type="checkbox"/>	WDW <input type="checkbox"/>	CUSTOMER ORDER NO.:		
CUSTOMER F.G. Hall Co. LLC	LEASE Demol Unit # 1-36		WELL NO.						
ADDRESS	COUNTY Barton 36-20-16	STATE Ks							
CITY	STATE	SERVICE CREW Allen, Eric, Tessie							
AUTHORIZED BY	JOB TYPE: 5 1/2" 1.5								
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	AM	TIME
28443 Pu	3						8-28-12	PM	900
33708-20920	3					ARRIVED AT JOB	8-28-12	PM	1200
19831-19862	3					START OPERATION	8-28-12	AM	230
						FINISH OPERATION	8-28-12	PM	530
						RELEASED	8-28-12	AM	630
						MILES FROM STATION TO WELL 65 miles			

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: [Signature]
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CP105	AA2 cement	SK	125		
CP103	60/40 Poz	SK	75		
CC102	Cell FLAKE	lb	32		
CC105	C-41P Defoamer	lb	30		
CC111	salt	lb	522		
CC115	C-44	lb	118		
CC129	FIA-322	lb	118		
CC201	Gilsonite	lb	1625		
CF607	Latch Down Plug & Baffle 5 1/2" Blue	EA	1		
CF1251	Auto Fill Float Shoe 5 1/2" Blue	EA	1		
CF1651	Turbolizer	EA	8		
CF1901	5 1/2" Bucket Blue	EA	1		
CF2402	Cement Scratchers Rotating Type	EA	40		
CC154	Super flush	gal	500		

CHEMICAL / ACID DATA:			

SUB TOTAL	
SERVICE & EQUIPMENT	%TAX ON \$
MATERIALS	%TAX ON \$
TOTAL	

SERVICE REPRESENTATIVE [Signature] THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: [Signature]
(WELL OWNER OPERATOR CONTRACTOR OR AGENT)

FIELD SERVICE ORDER NO.

Customer F.G. Holl Co. LLC	Lease No.	Date 8-28-12
Lease Demol Unit	Well # 1-36	
Field Order # #06562A	Station Pratt	Casing 5 1/2"
Type Job 5 1/2" L.S.	Formation C.N.W.	Depth 3940'
		County Barton
		State KS
		Legal Description 36-20-16

PIPE DATA		PERFORATING DATA		FLUID USED		TREATMENT RESUME		
Casing Size 5 1/2"	Tubing Size	Shots/Ft		Acid 12 BBI super flush	RATE	PRESS	ISIP	
Depth 3940'	Depth	From	To	Pre Pad 25 SKS 60/40 Duz	Max Scavenger @ 14#		5 Min.	
Volume 96 1/2	Volume	From	To	Pad 125 SKS AA2 @ 15#	Min #		10 Min.	
Max Press 1500#	Max Press	From	To	Frac 30 SKS 60/40	Avg #		15 Min.	
Well Connection PC	Annulus Vol.	From	To	Flush 20 SKS 60/40	HHP Used		Annulus Pressure	
Plug Depth 3927'	Packer Depth	From	To	Flush Disp H2O	Gas Volume		Total Load	

Customer Representative Rub Long "Adam"	Station Manager scotty	Treater Allen
--	---------------------------	------------------

Service Units	28443	33708	20920	19831	19862				
Driver Names	Allen	Eric	Wright	Jessie	Pierce				

Time	Casing Pressure	Tubing Pressure	Bbbs. Pumped	Rate	Service Log
1200	2m				onloc. Discuss Safety, Setup, Plan Job
					Laying down Kelly - Rig up To
					Run 5 1/2" casing 14# /ft
1254					Start casing, shoe joint + 13.62
					w/ float shoe & latch down Baffle
					in collar cen 7-8, Basket #5
245					TAG Bottom @ 3951 CIR @ 3940
					+ Rotate pipe.
445			5	5	Pump 5 BBI H2O spacer
			12	5	Pump 12 BBI super flush
			5	5	Pump 5 BBL H2O spacer
			5	5	mix + pump 25 SKS 60/40 scavenger @ 14#
					mix + pump 125 SKS AA2 @ 15#
			32		Finish mix cnt wash out Pump Line
500				16	Drop Latch Down Plug, Start Disp
	500#			5 1/2	caught lift PSI @ 68 BBI out
520	1500#		9 1/2	4	Plug down
	0#				Release PSI To TRUCK 0#
			7		Plug R.H. w/ 30 SKS 60/40
			5		Plug M.H. w/ 20 SKS 60/40
					washup + Rackup
630					Job complete. Thank you Allen, Eric, Jessie