



269748

TICKET NUMBER 47420
 LOCATION Ottawa, KS
 FOREMAN Casper Kennedy

PO Box 884, Chanute, KS 66720
 620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
 CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
7/18/14	10370	Sewer # 10-I	SW29	14	22	JO

CUSTOMER
Petroleum Technologies Inc.
 MAILING ADDRESS
801 W. 47th St
 CITY
Kansas City STATE MO ZIP CODE 64112

TRUCK #	DRIVER	TRUCK #	DRIVER
729	Casper	✓	Safety Meeting
1000	Keiler	✓	
510	DusWeb	✓	
370	Mittler	✓	

JOB TYPE Logging HOLE SIZE 5 5/8" HOLE DEPTH 887' CASING SIZE & WEIGHT 2 7/8" EUE
 CASING DEPTH 867' DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT In CASING _____
 DISPLACEMENT 5.02 bbls DISPLACEMENT PSI _____ MIX PSI _____ RATE 5 bpm

REMARKS: held safety meeting, established circulation mixed + pumped 200# Premium Gel followed by 10 bbls fresh water, mixed + pumped 122 sks 5/8" Pozmix cement w/ 2 1/2 gal + 1/4# Floccal per sk, cement to surface, flushed pump down, pumped 2 1/2" rubber plug to casing TD w/ 5.02 bbls fresh water, pressured to 800 PSI, well held pressure for 30 min MIT, released pressure, shut in casing.

[Handwritten signature]

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE		1085.00 ✓
5406	30 mi	MILEAGE		126.00 ✓
5402	867'	casing footage		— ✓
5407	minimum	tax mileage		368.00 ✓
5502C	2 hrs	80 Vac		200.00 ✓
1124	122 sks	5/8" Pozmix cement	1403.00	✓
1118B	405 #	Premium Gel	89.10	✓
1107	31 #	Floccal	76.57	✓
		materials	1568.67	✓
		-30%	470.60	✓
		subtotal		1098.07
4402	1	2 1/2" rubber plug		29.50 ✓
			3495.04	
		7.375	SALES TAX	83.16 ✓
			ESTIMATED TOTAL	2989.73 ✓

AUTHORIZATION No Company Rep TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form