



BASICSM
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

10244 NE Hwy. 61
P.O. Box 8613
Pratt, Kansas 67124
Phone 620-672-1201

146520-6
FIELD SERVICE TICKET

1718 06597 A

DATE _____ TICKET NO. _____

DATE OF JOB: 10-22-12		DISTRICT: Kansas		NEW WELL <input checked="" type="checkbox"/>		OLD WELL <input type="checkbox"/>		PROD <input type="checkbox"/>		INJ <input type="checkbox"/>		WDW <input type="checkbox"/>		CUSTOMER ORDER NO.:	
CUSTOMER: F.G. Holl Coi LLC				LEASE: Mauney # 1-6				WELL NO.:							
ADDRESS:				COUNTY: Pawnee 6-21-15				STATE: KS							
CITY:				STATE:				SERVICE CREW: Allen Joe & Tossie							
AUTHORIZED BY:				JOB TYPE: 5 1/2" L.I.S.				C.N.W.							
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	AM	PM	TIME					
28443	3 1/2						10-21-12			730					
33768-20920	3 1/2						10-21-12			610					
19831-19262	3 1/2						10-21-12			900					
							10-22-12			1230					
							10-22-12			100					
						MILES FROM STATION TO WELL: 6.5 miles									

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: *[Signature]*
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CP105	AA 2 cement	SK	125		
CP103	60/40 P02	SK	75		
CC102	cell FLAK	lb	32		
CC105	C-41P Deformer	lb	30		
CC111	SAH	lb	562		
CC115	C-44	lb	118		
CC129	FIA-322	lb	118		
CC201	Gilsonite	lb	1623		
CF1007	5 1/2" Latch down Plus Assy.	EA	1		
CF1201	Auto Fill Float 5/8"	EA	1		
CF1651	Turbolizer 5 1/2" Blue	EA	8		
CF1901	5 1/2" Basket Blue	EA	1		
CF2002	Cement Scratchers Rotating Type	EA	40		
C154	Super flush	gal	300		

SUB TOTAL *KG*

CHEMICAL / ACID DATA:			

SERVICE & EQUIPMENT	%TAX ON \$		
MATERIALS	%TAX ON \$		
TOTAL			

SERVICE REPRESENTATIVE: *[Signature]* THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: *[Signature]*

(WELL OWNER OPERATOR CONTRACTOR OR AGENT)

FIELD SERVICE ORDER NO.



BASICSM
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

10244 NE Hwy. 61
P.O. Box 8613
Pratt, Kansas 67124
Phone 620-672-1201

FIELD SERVICE TICKET

1718 ~~06598~~ A

Continuation of

DATE TICKET NO. 106597A

DATE OF JOB <u>10-22-12</u> DISTRICT <u>KANSAS</u>				NEW WELL <input checked="" type="checkbox"/> OLD WELL <input type="checkbox"/> PROD <input type="checkbox"/> INJ <input type="checkbox"/> WDW <input type="checkbox"/> CUSTOMER ORDER NO.:						
CUSTOMER <u>FGHOLL CO LLC</u>				LEASE <u>MAUNEY #1-6</u> WELL NO.:						
ADDRESS				COUNTY <u>PAWNEE</u> STATE <u>6-21-15</u>						
CITY STATE				SERVICE CREW <u>Allen, Tom, Jesse</u>						
AUTHORIZED BY				JOB TYPE: <u>5 1/2" L.S.</u> <u>CNW</u>						
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	AM	PM	TIME
<u>428443</u>							<u>10-21-12</u>			<u>730</u>
<u>33708-20920</u>							<u>10-21-12</u>			<u>610</u>
<u>19831-19862</u>							<u>10-21-12</u>			<u>900</u>
							<u>10-22-12</u>			<u>1230</u>
							<u>10-22-12</u>			<u>100</u>
						MILES FROM STATION TO WELL	<u>mile 65</u>			

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: [Signature]
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
E100	unit mileage chg. P.U.	mi	65		
E101	Hourly Equip Mileage	mi	130		
E113	Bulk Del. Chg	Tm	595		
CE204	Depth Chg 2001-4000	4hr	1		
CE240	Blending & Mixing Service chg.	SK	200		
CE301	Casing Service Rental	EA	1		
CE304	Plus Container Utilization chg.	Job	1		
5003	Sedvice Super Sealant 8lbs	EA	1		

SUB TOTAL

CHEMICAL / ACID DATA:			

SERVICE & EQUIPMENT	%TAX ON \$	
MATERIALS	%TAX ON \$	
TOTAL		

SERVICE REPRESENTATIVE <u>[Signature]</u>	THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: <u>[Signature]</u>
FIELD SERVICE ORDER NO.	(WELL OWNER OPERATOR CONTRACTOR OR AGENT)

BASIC

energy services, L.P.

TREATMENT REPORT

Customer EG Holl Co LLC	Lease No.	Date 10-22-12
Lease MAUNES	Well # #1-6	
Field Order # #06597A	Station Pratt KS	Casing 5/2"
Type Job 5/2" Long String	Formation Cmw	Depth 3947
		County Lawnee
		State KS
		Legal Description 6-21-15

PIPE DATA		PERFORATING DATA		FLUID USED		TREATMENT RESUME		
Casing Size 5/2"	Tubing Size	Shots/Ft		Acid 25 SKS 60/40	Rate A02 scavenge @ 14 #/gal	PRESS	ISIP 14 #/gal	
Depth 3947'	Depth	From	To	Pre Pad 125 SKS AA2 @ 15 #/gal	Max		5 Min.	
Volume 76 BBL	Volume	From	To	Pad	Min		10 Min.	
Max Press # 1500	Max Press	From	To	Frac 12-BBL super	Avg	Push ahead of cent	15 Min.	
Well Connection PC	Annulus Vol.	From	To		HHP Used		Annulus Pressure	
Plug Depth 3926'	Packer Depth	From	To	Flush Disp. w/ H ₂ O	Gas Volume		Total Load	

Customer Representative Rob Long - ADAM	Station Manager Scotty	Treater Allen
Service Units 28443 33708 20920 19831 19862		
Driver Names Allen Joe Melson Jessie Pierce		

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
6:10 pm					on loc. Discuss Safety Setup Plan Job
					Rig laying down collars
					out of hole Lay down Kelly mousehole
					Ricup to Run 5/2" csg 19'
7:40					start 5/2" csg shoe JF. 20.73
					Auto Fill Float shoe + L.O. insert
					in collar cent - 1-Thru 8
					Basket on #5
9:15					Tag Bottom Pickup to 3947' cir w/ Rig
					+ Rotate Pipe
	200		5	5	Pump 5-BBL H ₂ O space
			12	5	Pump 12-BBL super flush
			5	5	Pump 5-BBL H ₂ O space
			6	5	Mix + Pump 25 SKS 60/40 scavenge 14'
			32	5	Mix + Pump 125 SKS AA2 @ 15 #
					wash out pump + line, Drop L.P. Plug
11:40	200 #			6	start Disp. + Rotate
	600 #			5	caught L. + PSI 72-BBLs
12:00	1500 #	10-22-12			Plug Down
12:15			7		Release PSI - 0" Plug R.H 30 SKS
12:20			5		Plug MH w/ 20 SKS
100					wash up + RHC KUP. Job complete