



BASICSM
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

10244 NE Hwy. 61
P.O. Box 8613
Pratt, Kansas 67124
Phone 620-672-1201

FIELD SERVICE TICKET
1718 06607 A

DATE _____ TICKET NO. _____

DATE OF JOB <u>9-28-12</u> DISTRICT <u>Pratt</u>		NEW WELL <input checked="" type="checkbox"/> OLD WELL <input type="checkbox"/> PROD <input type="checkbox"/> INJ <input type="checkbox"/> WDW <input type="checkbox"/> CUSTOMER ORDER NO.:								
CUSTOMER <u>FG HOLL</u>		LEASE <u>Lang/BaHR Unit</u>		126 WELL NO.						
ADDRESS		COUNTY <u>Barton</u>		STATE <u>KS</u>						
CITY		STATE		SERVICE CREW <u>Matt & L REED MELSON</u>						
AUTHORIZED BY		JOB TYPE: <u>CWU 898 Surface</u>								
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	AM	PM	TIME
<u>19959-19905</u>	<u>1</u>						<u>9:27</u>	<input checked="" type="radio"/>	<input type="radio"/>	<u>4:45</u>
<u>70959-8918</u>	<u>1</u>					ARRIVED AT JOB	<u>9:27</u>	<input checked="" type="radio"/>	<input type="radio"/>	<u>7:00</u>
<u>37900</u>						START OPERATION	<u>9:27</u>	<input checked="" type="radio"/>	<input type="radio"/>	<u>11:15</u>
						FINISH OPERATION	<u>9:28</u>	<input checked="" type="radio"/>	<input type="radio"/>	<u>12:15</u>
						RELEASED	<u>9:28</u>	<input checked="" type="radio"/>	<input type="radio"/>	<u>1:15</u>
						MILES FROM STATION TO WELL				<u>75</u>

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: _____
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CP 101	A-con Blend	SK	200		
CP 100C	Common Cement	SK	200		
CC 102	Celloflake	lb	100		
CC 109	Calcium Chloride	lb	940		
CF 105	TOP Rubber Plug	eq	1		
CF 1753	Centralizer	eq	3		
E 100	Rekup mileage	Mi	75		
E 101	Heavy mileage	Mi	150		
E 113	Bulk Delivery	TM	1110		
CE 201	Depth Charge	Lbs	1		
CE 240	Mixing Charge	SK	400		
CE 304	Plug Container	JOB	1		
S 003	Supervisor	eq	1		

SUB TOTAL
DLS

CHEMICAL / ACID DATA:			

SERVICE & EQUIPMENT	%TAX ON \$		
MATERIALS	%TAX ON \$		
TOTAL			

SERVICE REPRESENTATIVE <u>Joe Melson</u>	THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: <u>Dwight G. ...</u>
FIELD SERVICE ORDER NO.	(WELL OWNER OPERATOR CONTRACTOR OR AGENT)

Customer FG HOLL	Lease No.	Date
Lease LQNG / BARR UNIT	Well # 1-26	
Field Order # 6607	Station PRATT	Casing 8 5/8
		Depth 1036
Type Job CNW 8 5/8 SF	Formation	County BARTON
		State ISS
		Legal Description 26-17-15

PIPE DATA		PERFORATING DATA		FLUID USED		TREATMENT RESUME		
Casing Size 8 5/8	Tubing Size	Shots/Ft		Acid		RATE	PRESS	ISIP
Depth 1036	Depth	From	To	Pre Pad	Max			5 Min.
Volume 65	Volume	From	To	Pad	Min			10 Min.
Max Press	Max Press	From	To	Frac	Avg			15 Min.
Well Connection	Annulus Vol.	From	To		HHP Used			Annulus Pressure
Plug Depth 1016	Packer Depth	From	To	Flush	Gas Volume			Total Load

Customer Representative SCOTT	Station Manager D. SCOTT	Treater JOE MELSON
--------------------------------------	---------------------------------	---------------------------

Service Units	19959	19905	70959	19918	37900			
Driver Names	MIKE	MANAL	BRETT REED		JOE MELSON			

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
7 PM					on LOC - Safety meeting
					Run 23 JTS casing 24 # casing
					centralizer on 1, 11, 23
10:45					Casing on Bottom
					Break Cir. with Rig
11:15	200		88	6.5	Mix 200stk A. con with 3% CC 1/4 # cell fluid
	200		43	6.5	Mix 200sc Common with 2% CC 1/4 # cell fluid
					SHUT DOWN
					Release Plug
11:45	200		8	5	START H2O Displacement
	200		20	5	Cement to surface
12:15	400		64	5	Plug Down
					Circulation thru JOB
					Circulated 44 BBL cement to surface
					JOB complete
					Thank you
					Joe