
McGOWN

DRILLING, INC.

Operator:
Grand Mesa Operating Co.
Wichita, KS

Vesecky #3-7

Douglas Co., KS
23-14S-20E
API: 045-22226

Spud Date:	8/18/2014	Surface Bit:	11.0"
Surface Casing:	7.0"	Drill Bit:	6.125"
Surface Length:	44.0'	Longstring:	755.0'
Surface Cement:	10 sx	Longstring Date:	8/20/2014
Longstring:			

Driller's Log

Top	Bottom	Formation	Comments
0	12	Soil & clay	
12	40	Sand & Gravel	
40	56	Shale	
56	82	Lime	
82	91	Bl. Shale	
91	98	Lime	
98	103	Shale	
103	141	Lime	
141	158	Shale	
158	179	Lime	
179	244	Shale	
244	248	Lime	
248	250	Shale	
250	264	Lime	
264	265	Coal	
265	268	Lime	
268	285	Shale	
285	294	Lime	
294	308	Sandy Shale	
308	326	Shale	
326	333	Lime	
333	337	Shale	
337	339	Lime	
339	346	Shale	

Vesecky #3-7

346	374	Lime	Douglas Co., KS
374	378	Bl. Shale	
378	404	Lime	
404	407	Bl. Shale	
407	412	Lime	
412	414	Shale	
414	421	Lime	
421	535	Shale	
535	537	Shale	Limey
537	558	Shale	
558	563	Red Bed	
563	571	Shale	
571	578	Lime	
578	582	Shale	
582	584	Lime	
584	591	Shale	
591	597	Lime	
597	601	Bl. Shale	
601	604	Lime	
604	613	Shale	
613	620	Lime	
620	634	Shale	
634	639	Bl. Shale	
639	641	Lime	
641	647	Shale	
647	657	Lime	
657	669	Shale	
669	671	Lime	
671	678	Bl. Shale	
678	680	Lime	
680	693	Shale	
693	699	Sand	Laminated with shale, light oil show
699	700	Sand	Good sand, good oil show, gassy
700	702	Sand	Laminated, lighter oil show than above
702	762	Shale	
762		TD	

	Coring	
Run	Footage	Rec.
1	685-705	20'