



**CONSOLIDATED**  
Oil Well Services, LLC

TICKET NUMBER 48049  
LOCATION Ottawa KS  
FOREMAN Fred Mader

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

**FIELD TICKET & TREATMENT REPORT**  
**CEMENT**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8-20-14	3372	Vesucky # 3-7	NE 23	14	20	DG
CUSTOMER Grand Mesa Operating			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS 1700 N Waterfront Pkwy			712	Fred Mader		
CITY STATE ZIP CODE Wichita KS 67206			495	Har Bee		
			505/1706	Mat Coc		
			510	Dave Web		

JOB TYPE Long string HOLE SIZE 5 7/8 HOLE DEPTH 763 CASING SIZE & WEIGHT 2 7/8 EUE  
CASING DEPTH 755 DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING 2 1/2" Plug  
DISPLACEMENT 4.39 DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE 5BPM

REMARKS: Hold crew safety meeting. Establish circulation. Mix Pump 100% Gel Flush. Mix Pump 5ks 50/50 Poz Mix Cement 2% Gel 5% Salt 5# Kal Seal/sk. Cement to Surface. Flush pumps & lines clean. Displace 2 1/2" Rubber plug to casing. Tm pressure to 800# PSI. Release pressure to set float valve. Shut in casing.

McGown Drilling

Fred Mader

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE	495	
5406	-	MILEAGE		
5402	755	Casing footage		
5407	131.26	Ton Miles	510	
5501C	1 1/2 hr	Transport	305/1706	
1124	113 SKS	50/50 Poz Mix Cement		
1118B	290 #	Premium Gel		
1111	242 #	Granulate d Salt		
1110A	565 #	Kal Seal		
		Material		
		Less 30%		
		Total		
4402	1	2 1/2" Rubber Plug		
			7.15%	
			SALES TAX	
			ESTIMATED	
			TOTAL	

Ravin 3737

OK'd J. Green

AUTHORIZATION Mo Co Rep on site TITLE \_\_\_\_\_ DATE \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.