

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **1641**
 Foreman Steve Mead
 Camp Eureka

API 15-015-24044

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
9-8-14	1027	Bussenitz #1	24	24	4E	Butler	KS
Customer			Unit #	Driver	Unit #	Driver	
Noble Petroleum Inc			104	Alan M			
Mailing Address			113	Johns. JOR			
8918 W. 21 ST No. Suite 200 [*] 304							
City	State	Zip Code					
Wichita	KS	67226					

Job Type Surface Hole Depth 239' Slurry Vol. _____ Tubing _____
 Casing Depth 225 GL. ^{235 KB} Hole Size 12 1/4" Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 8 5/8 23* Cement Left in Casing 15' Water Gal/SK _____ Other _____
 Displacement 14 bbls Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting: Rig up to 8 5/8 casing. Break circulation w/ fresh water. Mix 115 sks Class A cement w/ 3% Cadz, 2% gel + 1/4" Flo Seal per sk. Displace with 14 bbls fresh water. Shut well in. Good cement returns to surface 4 bbl top it. Job complete Rig down.

Thank you.



Code	Qty or Units	Description of Product or Services	Unit Price	Total
C101	1	Pump Charge	840.00	840.00
C107	15	Mileage	3.95	59.25
C200	115 sks	Class A Cement	15.00	1725.00
C203	325 #	Cadz 3%	.60	195.00
C206	215 #	Gel 2%	.20	43.00
C209	28 #	Flo-Seal 1/4" per sk	2.25	63.00
C108A	5.41 Ton	Ton Mileage Bulk Truck	m/c	345.00
			Sub Total	3270.25
			Sales Tax <u>6.40%</u>	129.66
Authorization _____ Title _____			Total	3399.91

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.