

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. 1655
 Foreman Rick Ledford
 Camp Eureka Ks

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
9-11-14	1027	Busenitz #1	24	24	4E	Butler	Ks
Customer	Mailing Address	City	State	Zip Code	Safety Meeting	Unit #	Driver
Noble Petroleum Inc.	8918 W. 21 st No. suite 200	Wichita	Ks	67226	QL Am JS A	104 112 144	Alan M. John S. Russ M.

Job Type L/S Hole Depth 2620' Slurry Vol. 41 Bbl Tubing _____
 Casing Depth 2619.4' Hole Size 7 7/8" Slurry Wt. 13.7" Drill Pipe _____
 Casing Size & Wt. 5 1/2" 14" Cement Left in Casing 12.10 SJ Water Gal/SK 9.0 Other _____
 Displacement 65 1/2 Bbls Displacement PSI 500 Bump Plug to 1000 BPM _____

Remarks: Safety meeting - Rig up to 5 1/2" casing. Break circulation w/ 10 Bbl fresh water. Pump 100" metasilicate pre-flush w/ 12 Bbls water. 10 Bbl water spacer. Mixed 125 sks thickset cement w/ 5" Hot-seal/sk @ 13.7"/gal. yield 1.85 washout pump & lines, release 5 1/2" latch down plus. Displace w/ 65 1/2 Bbls fresh water. Final pump pressure 500 PSI. Bump plug to 1000 PSI. release pressure, float & plug held. Good circulation @ all times while cementing. Job complete. Rig down.

cont on p# 1, 3, 5, 7, 9

"Thank You"

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C107	1	Pump Charge	1050.00	1050.00
C107	15	Mileage	3.95	59.25
C201	125 sks	thickset cement	19.50	2437.50
C207	625"	5" Hot-seal/sk	.45	281.25
C216	100"	metasilicate pre-flush	2.00	200.00
C108A	6.88	tan mileage bulk trix	m/c	345.00
C113	4 hrs	80 Bbl HAC. TRK	85.00	340.00
C224	3,000 gals	city water	10.00/1000	30.00
C421	1	5 1/2" latch down plus	230.00	230.00
C504	5	5 1/2" x 7 7/8" centralizers	48.00	240.00
C691	1	5 1/2" Guide shoe	1167.00	1167.00
C703	1	5 1/2" AFV flapper valve insert	145.00	145.00
			Subtotal	5525.00
			6.88% Sales Tax	238.77
Authorization <u>Doug Lead</u> Title <u>X</u>			Total	5763.77

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.