



CONSOLIDATED
Oil Well Services, LLC

INVOICE #80240

TICKET NUMBER 50685

LOCATION Ottawa KS.

FOREMAN Fred Mader

1077
104

884, Chanute, KS 66720
620-461-9210 or 800-467-8676

**FIELD TICKET & TREATMENT REPORT
CEMENT**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
11-18-14	4448	Cartwright # KRI. 13	NE 23	18	21	MI
CUSTOMER			TRUCK # DRIVER TRUCK # DRIVER			
Kansas Resources Expl & Dev.			712	Fred Mader		
MAILING ADDRESS			495	Gar Moo		
9393 W 110 th St			370	Mik Fox		
CITY		STATE	ZIP CODE	548	Dan Wha	
Overland Park		KS	66210			

JOB TYPE long string HOLE SIZE 5 7/8 HOLE DEPTH 562 CASING SIZE & WEIGHT 2 7/8 EUE
 CASING DEPTH 568.70 DRILL PIPE Baffle in TUBING @ 53 P. 70 OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 30' x Plug
 DISPLACEMENT 3.133 BL DISPLACEMENT PSI _____ MIX PSI _____ RATE 43 P/M

REMARKS: Hold Safety meeting. Establish circulation. Mix + Pump 100' Gel Flush.
Mix + Pump 86 sks 50/50 Poz Mix Cement 2 7/8 Gel 1/2" Pheno Seal/SK.
Cement to surface. Flush pump + lines clean. Displace 2 1/2"
Rubber plug to baffle in casing. Pressure to 700' PSI. Release
pressure to set float valve. Shut in casing.

Mc Gowan Drilling

Fred Mader

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE	495	1085.00
5400		MILEAGE		N/C
5402	568.70	Casing footage		N/C
5407	1/2 minimum	Ton Miles	545	184.00
5502C	1 1/2 hr	80 BBL Vac Truck	370	150.00
1124	86 SKS	50/50 Poz Mix Cement	989.00	
1115B	245#	Premium Gel	53.20	
1107A	43#	Pheno Seal	58.05	
		Material	1100.95	
		Less 30%	-330.29	
		Total		770.66
4402	1	2 1/2" Rubber Plug		29.50
				21635.93
			7.65%	161.22
			SALES TAX ESTIMATED	
			TOTAL	2280.38

1639

completed

Rev'n 3737

OK'd J Green

AUTHORIZATION No Co Rep on Site TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.