



CONSOLIDATED
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

Invoice #802117

TICKET NUMBER 50684

LOCATION Ottawa KS

FOREMAN Fred Mader

1074
104

**FIELD TICKET & TREATMENT REPORT
CEMENT**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
11.18.14	4448	Cartwright #KRI-17	NE 23	18	21	MI
CUSTOMER Kansas Resources Expl & Dev			TRUCK # DRIVER TRUCK # DRIVER			
MAILING ADDRESS 9393 W 110th St			712 Fred Mader			
CITY STATE ZIP CODE Overland Park KS 66210			495 Garmon			
			370 Mike Fox			
			548 Dan Wha			

JOB TYPE Longstring HOLE SIZE 5 7/8 HOLE DEPTH 582 CASING SIZE & WEIGHT 2 7/8 EVE
 CASING DEPTH 562.50 DRILL PIPE Baffle in TUBING @ 533.10 OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 29.41 Plug
 DISPLACEMENT 3.10BL DISPLACEMENT PSI _____ MIX PSI _____ RATE 4BPM

REMARKS: Hold safety meeting. Thaw Pumps. Establish circulation. Mix & Pump 100# Gel Flush. Mix & Pump 86 sks 50/50 Poz Mix Cement 2 7/8 Gel 1/2" Pheno Seal/sk. Cement to surface. Flush pump & lines clean. Displace 2 1/2" Rubber Plug to baffle in casing. Pressure to 700 PSI. Release pressure to set float valve. Shut in casing

McGown Drilling.

Fred Mader

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE	495	1085.00
5406	25 mi	MILEAGE	495	105.00
5402	562.50	Casing footage		N/C
5407	1/2 Minimum	Ton Miles	548	164.00
5502C	1 1/2 hr	80 BBL Vac Truck	370	150.00
1124	86 sks	50/50 Poz Mix Cement	989.00	
1118B	245#	Premium Gel	53.90	
1107A	43#	Pheno Seal	5805	
		Material	1185.95	
		Less 30%	-330.00	
		Total		829.62
4402	1	2 1/2" Rubber Plug		29.00
				2740.93
			7.65%	208.77
			SALES TAX	
			ESTIMATED TOTAL	2385.38

completed

Revin 3737

ok'd J Green

AUTHORIZATION No Co Rep on Site

TITLE _____

DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.