

QUALITY OILWELL CEMENTING, INC.

Federal Tax I.D.# 20-2886107

Phone 785-483-2025

Home Office P.O. Box 32 Russell, KS 67665

No. 6488

Cell 785-324-1041

Date	Sec.	Twp.	Range	County	State	On Location	Finish
3-20-13	27	11	17	ELIOT	KANSAS		1:45 pm

Location: CONELL-10 1/2 N 1 W / INFO

Lease BAUMER	Well No. # 600	Owner CITATION OIL
Contractor DUKE # 2		To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.
Type Job PROD. STRING		
Hole Size 7 1/8	T.D. 3,645'	Charge To CITATION OIL
Csg. 5 1/2" 15LB-NEW	Depth 3,638'	Street 14011 CITATION
Tbg. Size	Depth	City HOUSTON State TX
Tool	Depth	The above was done to satisfaction and supervision of owner agent or contractor.
Cement Left in Csg.	Shoe Joint 84'	Cement Amount Ordered 235 CLASS A 10 SALT - 20 GAL KUBER
Meas Line	Displace 86 3/4 BBL'S	

EQUIPMENT

	No.	Common	
Pumptrk # 15	No. Cementer Helper NICK W.	Poz. Mix	
Bulktrk # 14	No. Driver DRIVER LONNIE M	Gel.	
Bulktrk # 14	No. Driver DRIVER LONNIE M	Calcium	

JOB SERVICES & REMARKS

Remarks:	
Rat Hole 30 SKS	Flowseal
Mouse Hole 15 SKS	Kol-Seal
Centralizers	Mud CLR 48 500 GALLONS
Baskets	CFL-117 or CD110 CAF 38
D/V or Port Collar	Sand
DROPPED BALL - BROKE CIRCULATION	Handling
CIRCULATED 1/2 HR ON BOTTOM - PUMPED	Mileage
500 GAL MUD FLUSH - PLUGGED PATH HOLE -	FLOAT EQUIPMENT
30 SKS - PLUGGED MOUSE HOLE 15 SKS - MIXED	Guide Shoe
& PUMPED 205 SKS DOWN 5 1/2" - DROPPED -	Centralizer 14-5 1/2" TURBOS
PLUG WASHED PUMP - DISPLACED PLUG	Baskets 2-5 1/2"
PLUG LANNED & HELD!	AFU Inserts
	Float Shoe 1-5 1/2" W/BALL
LIFT PRESSURE @ 1000 LBS	Latch Down 1-5 1/2" W/DWG
PLUG LANNED @ 8 1/2 BBL'S @ 1,500 LBS	

	Pumptrk Charge	
	Mileage	
	Tax	
	Discount	
	Total Charge	

THANK YOU!
Signature [Signature]