



**BASIC**<sup>SM</sup>  
ENERGY SERVICES  
PRESSURE PUMPING & WIRELINE

1700 S. Country Estates Rd.  
P.O. Box 129  
Liberal, Kansas 67905  
Phone 620-624-2277

FIELD SERVICE TICKET  
1717 03341 A

DATE \_\_\_\_\_ TICKET NO. \_\_\_\_\_

DATE OF JOB 12-6-12	DISTRICT 1717	NEW WELL <input checked="" type="checkbox"/>	OLD WELL <input type="checkbox"/>	PROD <input type="checkbox"/>	INJ <input type="checkbox"/>	WDW <input type="checkbox"/>	CUSTOMER ORDER NO.:	
CUSTOMER Oxy USA	LEASE Hylbom A#2	WELL NO.						
ADDRESS	COUNTY Finney	STATE KS						
CITY	STATE	SERVICE CREW J. Grifflida, E. Amaran, H. Rutledge						
AUTHORIZED BY J. Bennett	JRB	JOB TYPE: 242-85' Surface						
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE 12-6-12	TIME 2:00 PM
19902	8					ARRIVED AT JOB		9:00 AM
27462	8					START OPERATION		9:00 AM
30464	4					FINISH OPERATION		5:00 PM
37724	4					RELEASED		6:00 AM
19827	4					MILES FROM STATION TO WELL	85	mi
19566	4							

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: \_\_\_\_\_  
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CL101	A-Con	sk	350	13 02	4557 00
CL110	Premium Plus	sk	245	11 41	2795 45
CC109	Calcium Chloride	lb	1449	74	1072 26
CC102	Gulflake	lb	149	2 59	385 91
CC130	G-51	lb	66	17 50	1155 00
CF253	85/8" Guide Shoe	ea	1		266 00
CF1453	Insert		1		196 00
CF4405	Centralizer		15	101 50	1522 50
CF4556	Basket		1		735 00
CF105	Rubber Plug		1		157 50
CF4109	Stop Cellard		1		70 00
E101	Heavy Equipment Mileage	mi	255	4 90	1249 50
CE240	Blending + Mixing Service	sk	595	98	583 10
E113	Proppant + Bulk Delivery	cu yd	2380	1 12	2665 60
CE202	Pump Depth: 1000-2000'	ea	1		1050 00
CE504	Plug Container	ea	1		175 00
E100	Unit Mileage	mi	85	2 98	253 30
S003	Service Supervisor	ea	1		122 50
SUB TOTAL					19,431 62

CHEMICAL / ACID DATA:			

**Libcap**

AP LOCATION/DEPT. \_\_\_\_\_ SERVICE & EQUIPMENT \_\_\_\_\_ %TAX ON \$ \_\_\_\_\_  
 LEASE/WELL/FAC. \_\_\_\_\_ MATERIALS Hylbom A2 %TAX ON \$ \_\_\_\_\_  
 MAXIMO / WSM # \_\_\_\_\_  
 TASK 0102 ELEMENT 3023  
 PROJECT # 1151901 CAPEX / OPEX - Circle one

SERVICE REPRESENTATIVE: Gene Bilby

FIELD SERVICE ORDER NO. \_\_\_\_\_

SIGNATURE: Gene Bilby (WELL OWNER OPERATOR CONTRACTOR OR AGENT)  
 I certify that these services/materials have been received



### Cement Report

Customer <b>Oxy USA</b>		Lease No.		Date <b>12-6-12</b>						
Lease <b>Hullbom A</b>		Well # <b>2</b>		Service Receipt <b>03341</b>						
Casing <b>8 5/8" 24#</b> Depth <b>1804'</b>		County <b>Finney</b>		State <b>KS</b>						
Job Type <b>242-8 5/8" surface</b>		Formation		Legal Description <b>30-23-34</b>						
Pipe Data			Perforating Data			Cement Data				
Casing size <b>8 5/8" 24#</b>		Tubing Size		Shots/Ft			Lead <b>350 sk</b>			
Depth <b>1800'</b>		Depth		From		To		A-Con		
Volume <b>Disp-</b>		Volume		From		To				
Max Press <b>1500#</b>		Max Press		From		To		Tail in <b>245 sk</b>		
Well Connection <b>ID-1800'</b>		Annulus Vol.		From		To		Class <b>C</b>		
Plug Depth <b>51-41'</b>		Packer Depth		From		To				
Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log					
8:30					on loc-site assesment					
8:40					spot trucks-rig up					
10:00					start csg + float equip					
1:00					csg on btm, break circ					
2:00					safety meeting /ISA					
2:20					pressure test 3000#					
2:25	100		150	6	mix + pump 350 sk A-Con w/3% calcium chloride, 1/4# polyflake, 2% WCA1 @12.4ppg - 2.40 ft <sup>3</sup> /sk - 14.00 gal/sk					
3:00	100		58	6	switch to 245 sk Premium Plus w/ 2% calcium chloride 1/4# polyflake @14.8ppg - 1.34 ft <sup>3</sup> /sk, 6.33 gal/sk					
3:45	0		0	5	drop plug, disp csg					
3:40	600		102	2	slow rate last 10 bbl off disp					
3:45	1100		112	0	land plug float held circ chnt' to surface					
3:50	1500				psi test csg 1500# for 30 min					
4:20					job complete					
Service Units		19902	27462	30464-37724	19877-19806					
Driver Names		A. Ovea	J. Grijalva	E. Amparan	H. Lutiaga					

J. Bennett

A. Ovea

Customer Representative

Station Manager

Cementer