

pre

Elite Cementing & Acid Service, LLC

810 E 7th, PO Box 92
Eureka, KS 67045



Date	Invoice #
6/25/2014	1422

Bill To	
Drake Exploration 6535 12th Rd Douglass, KS 67039	
Customer ID#	1012

Job Date	6/21/2014
Lease Information	
Snyder #4	
County	Cowley
Foreman	SM

Item	Description	Qty	Terms	Net 30
			Rate	Amount
C101	Cement Pump-Surface	1	840.00	840.00
C107	Pump Truck Mileage (one way)	80	3.95	316.00
C200	Class A Cement-94# sack	130	15.00	1,950.00T
C205	Calcium Chloride	360	0.60	216.00T
C206	Gel Bentonite	245	0.20	49.00T
C209	Flo-Seal	30	2.25	67.50T
C108B	Ton Mileage-per mile (one way)	397.15	1.35	536.15

Pd 4/20/23
7/7/14
3818

We appreciate your business!

Phone #	Fax #
620-583-5561	620-583-5524
E-mail	
rene@elitecementing.com	

Subtotal	\$3,974.65
Sales Tax (6.4%)	\$146.08
Total	\$4,120.73
Payments/Credits	\$0.00
Balance Due	\$4,120.73

PRE

Elite Cementing & Acid Service, LLC

810 E 7th, PO Box 92
Eureka, KS 67045



Date	Invoice #
7/23/2014	1459

Bill To	
Drake Exploration 6535 12th Rd Douglass, KS 67039	
Customer ID#	1012

Entered
7/27/2014

Job Date	7/21/2014
Lease Information	
Snyder #4	
County	Cowley
Foreman	SM

Item	Description	Qty	Terms	Net 30
			Rate	Amount
C104	Cement Pump-Top Outside	1	1,050.00	1,050.00
C107	Pump Truck Mileage (one way)	80	3.95	316.00
C203	Pozmix Cement 60/40	110	12.75	1,402.50T
C206	Gel Bentonite	375	0.20	75.00T
Cement Equipmen...	1" tubing rental		250.00	250.00T
C108B	Ton Mileage-per mile (one way)	378.4	1.35	510.84

Complete the surface (long string)

We appreciate your business!


Phone #	Fax #
620-583-5561	620-583-5524
E-mail	
rene@elitecementing.com	

Subtotal	\$3,604.34
Sales Tax (6.4%)	\$110.56
Total	\$3,714.90
Payments/Credits	\$0.00
Balance Due	\$3,714.90

10 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561

Elite

**Cementing & Acidizing
 of Kansas, LLC**



Cement or Acid Field Report
 Ticket No. **1459**
 Foreman Steve Moad
 Camp Eureka

APT 15-CRE-24558

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
2-21-14	1012	Snyder #4	20	335	8E	Cowley	Ks	
Customer <u>Drake Exploration LLC</u>			Safety Meeting		Unit #	Driver	Unit #	Driver
Mailing Address <u>6535 12th Rd.</u>					<u>102</u>	<u>CHRIS B</u>		
City <u>Douglas</u>					<u>110</u>	<u>ALLIE G.</u>		
State <u>Ks</u>		Zip Code <u>67039</u>						

Job Type Repair Hole Depth _____ Slurry Vol. _____ Tubing 1" 500'
 Casing Depth _____ Hole Size _____ Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. _____ Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting. H 1/2" 110skgs Run 500' 1" Tubing. Break Circulation w/ 2166lb Fresh water. Mix 110skgs 60/40 Pozmix Cement w/ 4 1/2 Gal 500' To Surface. Pull out 1" Tubing w/ 110skgs Fall Job complete Rig down

Thank you

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C104	1	Pump Charge		
C107	80	Mileage	1050.00	1050.00
			3.95	316.00
C203	110skgs	60/40 Pozmix Cement	12.75	1402.50
C206	375#	Gel 4 1/2	.70	262.50
C116	1	1" Tubing Rental Flat Rate - 500'	250.00	250.00
C108	4.37	Ten mileage Bulk Truck	1.35	510.84
			Subtotal	3604.34
			Sales Tax	110.56
			<u>6.40%</u>	<u>3714.90</u>

Authorization Called by Darron Brayles Title _____ Total _____

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.

POST

Elite Cementing & Acid Service, LLC

810 E 7th, PO Box 92

Eureka, KS 67045



Date	Invoice #
6/27/2014	1467

Eureka
7/27/2014

Bill To	
Drake Exploration 6535 12th Rd Douglass, KS 67039	
Customer ID#	1012

Job Date	6/27/2014
Lease Information	
Snyder #4	
County	Cowley
Foreman	KM

Item	Description	Qty	Terms	Net 30
			Rate	Amount
C102	Cement Pump-Longstring	1	1,050.00	1,050.00
C107	Pump Truck Mileage (one way)	80	3.95	316.00
C201	Thick Set Cement	150	19.50	2,925.00T
C207	KolSeal	750	0.45	337.50T
C216	Sodium Metasilicate	100	2.00	200.00T
C108B	Ton Mileage-per mile (one way)	660	1.35	891.00
C660	4 1/2" AFU Float Shoe	1	275.00	275.00T
C420	4 1/2" Latch Down Plug	1	200.00	200.00T
C503	4 1/2" Centralizer	9	44.00	396.00T
C791	4 1/2" Weld On Collar	1	70.00	70.00T

pd
3820
7/7/14
3820

We appreciate your business!

Phone #	Fax #
620-583-5561	620-583-5524
E-mail	
rene@elitecementing.com	


long string

Subtotal	\$6,660.50
Sales Tax (6.4%)	\$281.82
Total	\$6,942.32
Payments/Credits	\$0.00
Balance Due	\$6,942.32

40 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561

Elite

**Cementing & Acidizing
 of Kansas, LLC**



Cement or Acid Field Report

Ticket No. **1467**
 Foreman Kevin McCoy
 Camp EUREKA

API # 15-035-24588

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
6-27-14	1012	Snyder # 4	30	335	8E	Cowley	Ks
Customer	Mailing Address	City	State	Zip Code	Safety Meeting	Unit #	Driver
DRAKE EXPLORATION, LLC	6535 12 TH Rd	Douglas	Ks	67039	KM DG RM	102 110	DAVE G. RUDY M.

Job Type Longstring Hole Depth 2927' KB Slurry Vol. 50 Bbl Tubing _____
 Casing Depth 2918' G.L. Hole Size 7 7/8 Slurry Wt. 13.7" Drill Pipe _____
 Casing Size & Wt. 4 1/2 10.5" Cement Left in Casing 0' Water Gal/SK 9.0 Other _____
 Displacement 47.5 Bbl Displacement PSI 500 Bump Plug to 1000 PSI BPM _____

Remarks: Safety Meeting: Rig up to 4 1/2 casing. Break Circulation w/ 5 Bbl Fresh water. Pump 10 Bbl Metasilicate Pre Flush, 5 Bbl water spacer. Mixed 150 SKS THICK Set Cement w/ 5" Kol-Seal / SK @ 13.7" yield 1.85 = 50 BBL SLURRY. Wash out Pump & Lines. Shut down. Release Latch down Plug. Displace Plug to Seat w/ 47.5 Bbl Fresh water. Final Pumping Pressure 500 PSI. Bump Plug to 1000 PSI. Wait 2 mins. Release Pressure. Float & Plug. Job Complete. Rig down.

Note: Last Circulation Last 2 mins of Mixing Cement, & First 15 Bbl of Displacement. Then we had Good Circulation.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 102	1	Pump Charge	1050.00	1050.00
C 107	80	Mileage	3.95	316.00
C 201	150 SKS	THICK Set Cement	19.50	2925.00
C 207	750 #	KOL-SEAL 5 #/SK	.45 #	337.50
C 216	100 #	Metasilicate Pre Flush	2.00 #	200.00
C 108	8.25 TONS	Ton Mileage 80 miles	1.35	891.00
C 660	1	4 1/2 AFD Float shoe	275.00	275.00
C 420	1	4 1/2 Latch down Plug	200.00	200.00
C 503	9	4 1/2 x 7 7/8 Centralizers	44.00	396.00
C 791	1	4 1/2 Weld on Collar	70.00	70.00
THANK YOU			Sub Total	6660.50
			Sales Tax 6.4%	281.82
Authorization <u>Witnessed By Darren Boyles Title Owner</u>			Total	6942.32

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.

310 E 7TH
 PO Box 92
 REKA, KS 67045
 (620) 583-5561



**Cementing & Acidizing
 of Kansas, LLC**



Cement or Acid Field Report
Ticket No. 1422
Foreman <u>Steve Mead</u>
Camp <u>Eureka</u>

API 15-C35-24588

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
6-21-14	1012	Snyder #4	30	33S	8E	Cowley	Ks
Customer Drake Exploration LLC			Unit #	Driver	Unit #	Driver	
Mailing Address 6535 12 th RD			102	Dave G.			
City Douglass			111	Randy M			
State Ks		Zip Code 67039					

Job Type <u>Surface</u>	Hole Depth <u>235'</u>	Slurry Vol. _____	Tubing _____
Casing Depth <u>227'</u>	Hole Size <u>12 1/4</u>	Slurry Wt. _____	Drill Pipe _____
Casing Size & Wt. <u>5 5/8</u>	Cement Left in Casing <u>20'</u>	Water Gal/SK _____	Other _____
Displacement <u>13 3/4</u>	Displacement PSI _____	Bump Plug to _____	BPM _____

Remarks: Safety Meeting. Rig up to 5 5/8 casing. Break circulation w/ Fresh water. Mix 13 sacks Class Cement w/ 37 coils 2% Gel. 1.7 Flt. Calc. displ. Displace w/ 13 3/4 H2O Fresh water. Shut casing. Feed cement returns to surface. 9601 70 ft. Job complete. Rig down.

Thank you

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C101	1	Pump Charge		
C107		Mileage	840.00	840.00
			3.95	316.00
C200	130 Sks	Class Cement	15.00	1950.00
C205	360 #	Coil 3%	.60	216.00
C206	245 #	Gel 2%	.20	49.00
C209	30 "	Flt Calc 4" 2.15%	2.25	67.50
C108B	6.11	Tenmileage Bulk Truck	1.35	536.15
			Subtotal	3974.65
			Sales Tax 6.40%	146.08
Authorization <u>Dudley Mead</u> Title _____			Total	4120.73

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.