



PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

### FIELD TICKET & TREATMENT REPORT CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
3/8/13	7806	P. Winfrey #5-T	SW 27	20	20	AN
CUSTOMER <u>Tailwater Inc</u>			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS <u>6421 Avondale Dr., Suite 212</u>			<u>481</u>	<u>Cr Ken</u>	<u>✓</u>	<u>Safety Meeting</u>
CITY <u>Oklahoma City</u>			<u>503</u>	<u>Kei Car</u>	<u>✓</u>	
STATE <u>OK</u>			<u>675</u>	<u>Kei Det</u>	<u>✓</u>	
ZIP CODE <u>73116</u>						

JOB TYPE long string HOLE SIZE 5 5/8" HOLE DEPTH 854' CASING SIZE & WEIGHT 2 7/8" EUE  
 CASING DEPTH 844' DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
 SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING \_\_\_\_\_  
 DISPLACEMENT 4.89 bbls DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE 4.5 bpm

REMARKS: held safety meeting, established circulation, mixed + pumped 100 # Premium Gel followed by 10 bbls fresh water, mixed + pumped 113 sks 50/50 Pozmix cement w/ 2% gel per sk, cement to surface, flushed pump clean, pumped 2 1/2" rubber plug to casing TD w/ 4.89 bbls fresh water, pressured to 800 PSI, released pressure, shut in casing.

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE		1030.00
5406	25 mi	MILEAGE		100.00
5402	844'	casing footage		
5407	minimum	tan mileage		350.00
5502c	2 hrs	80 Vac		180.00
1124	113 sks	50/50 Pozmix cement		1237.35
1118B	290 #	Premium Gel		60.90
4402	1	2 1/2" rubber plug		28.00
			7.8%	SALES TAX
				ESTIMATED TOTAL
				103.44
				3089.69

Ravin 3737

AUTHORIZATION [Signature] TITLE \_\_\_\_\_ DATE \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.