

SPUD DATE: 10 March 2015  
 FINISH DATE: 12 March 2015  
 LEASE: Roberson  
 LEASE OPERATOR: Denny Gillette  
 WELL: 1-2  
 API: 15-059-26939  
 SEC: TWP: RNG:  
 COUNTY: Franklin  
 DRILLERS NAME: Ronnie Howard  
 RIG #: 1



2394 UTAH ROAD  
 RANTOUL, KS 66079

SURFACE: SIZE BIT 97/8 LENGTH 20'6" SIZE 7" CEMENT 5 Bags  
 DRILL BIT SIZE 57/8 LENGTH 673.80 SIZE 27/8 BAFFLE NA  
 TD 682 CORED NA

FORMATIONS	THICKNESS	FROM	TO	FORMATION	THICKNESS	FROM	TO
Soil	3	0	3	Lime	6	456	462
Lime	14	3	17	Shale	24	462	486
Shale	27	17	44	Lime	4	486	490
Lime	18	44	62	Shale	12	490	502
Shale	12	62	74	Lime	6	502	508
Lime	1	74	75	Shale	48	508	556
Shale	2	75	77	Coal	4	556	560
Lime	1	77	78	Lime	5	560	565
Shale	76	78	154	Shale	3	565	568
Lime	18	154	172	Lime	2	568	570
Shale	18	172	190	Shale	11	570	581
Lime	2	190	192	Lime	3	581	584
Shale	2	192	194	Shale/Coal	10	584	594
Lime	3	194	197	Lime	4	594	598
Shale	36	197	233	Shale	13	598	611
Lime	7	233	240	Lime/coal Smelly	3	611	614
Shale	1	240	241	Limey Sand (80% Bleed)	3	614	617
Lime	9	241	250	Lime	1	617	618
Shale	2	250	252	Shale	4	618	622
Lime	4	252	256	Broken (10% great Bleed)	4	622	626
Shale	10	256	266	oil Sand great Bleed	4	626	630
Lime	18	266	284	oil Sand great Bleed	4	630	634
Shale	2	282	284	Broken (10% 80% Bleed)	4	634	638
Lime	10	284	294	Shale TD	44	638	682
Shale	8	294	302				
Lime	23	302	325				
Coal	3	325	328				
Lime	4	328	332				
Shale	2	332	334				
Lime	7	334	341				
Shale	115	341	456				



250 N. Water, Ste 200 - Wichita, Ks 67202

**HURRICANE SERVICES INC**

104 Prairie Plaza Parkway - Garnett, Ks 66032

Customer: <b>Denny Gillete</b>		Customer Name:		Ticket No.: <b>50017</b>				
Address:		APE No.:		Date: <b>3/12/2015</b>				
City, State, Zip:		Job type: <b>LONGSTRING</b>		<b>(NEW WELL)</b>				
Service District:		Well Details: <b>TD 682 5 7/8' HOLE 2 7/8' CASING TO 673.80'</b>						
Well name & No.: <b>Robertson I-2</b>		Well Location: <b>sec 8 / 18 / 21</b>		County: <b>Franklin</b>	State: <b>Kansas</b>			
Equipment #	Driver	Equipment #	Driver	Equipment #	Hours	AM	PM	TIME
<b>230</b>	<b>ALEX</b>				<b>TRUCK CALLED</b>			
<b>extra</b>	<b>JESSIE</b>				<b>ARRIVED AT JOB</b>			<b>1:30PM</b>
<b>110</b>	<b>JUNIOR</b>				<b>START OPERATION</b>			
<b>109</b>	<b>Rick</b>				<b>FINISH OPERATION</b>			<b>3pm</b>
<b>25</b>	<b>Dwayne</b>				<b>RELEASED</b>			
<b>MILES FROM STATION TO WELL.</b>								<b>20</b>

**Treatment Summary**

Hook onto well and establish circulation then pump 10 Bbrl gel flush followed by a 15 Bbrl pad and start cement pump 104 sacks of cement then stop and flush pump then pump wiper plug to bottom and shut in.

Product/Service Code	Description	Unit of Measure	Quantity	List Price/Unit	Gross Amount	Item Discount	Net Amount
p01603	60/40 Pozmix Cement	sack	104.00	\$12.00	\$1,248.00	10.00%	\$1,123.20
p01607	Bentonite Gel	lb	200.00	\$0.30	\$60.00	10.00%	\$54.00
p02000	H2O	gal	4,000.00	\$0.01	\$52.00	10.00%	\$46.80
p01607	Bentonite Gel 2%	lb	179.00	\$0.30	\$53.70	10.00%	\$48.33
c00101	Heavy Equip. One Way	mi	20.00	\$3.25	\$65.00	10.00%	\$58.50
c00102	Light Equip. One Way	mi	20.00	\$1.50	\$30.00	10.00%	\$27.00
p01631	Rubber 2 7/8	ea	1.00	\$25.00	\$25.00		\$25.00
c23003	Cement Pump (Multiple wells)	ea	1.00	\$675.00	\$675.00	10.00%	\$607.50
c24201	Cement Bulk Truck - Minimum	ea	1.00	\$300.00	\$300.00	10.00%	\$270.00
c11000	Vacuum Truck 80 bbl	ea	2.00	\$84.00	\$168.00	10.00%	\$151.20
c10900	Vacuum Truck 80 bbl	ea	2.00	\$84.00	\$168.00	10.00%	\$151.20

TERMS: Cash in advance unless Hurricane Services Inc has approved credit prior to sale. Credit terms of sale for approved accounts are total invoice due on or before the 30th day from the date of invoice. Past due accounts may pay interest on the balance past due at the rate of 1 1/4% per month or the maximum allowable by applicable state or federal laws if such laws limit interest to a lesser amount. In the event it is necessary to employ an agency and/or attorney to affect the collection of said account, Customer hereby agrees to pay all fees directly or indirectly incurred for such collection. In the event that Customer's account with HSI becomes delinquent, HSI has the right to revoke any and all discounts previously applied in arriving at net invoice price. Upon revocation, the full invoice price without discount will become immediately due and owing and subject to collection.

<b>Gross: \$ 2,844.70</b>		<b>Net: \$ 2,562.73</b>	
<b>Total Taxable</b>	<b>\$1,297.33</b>	<b>Tax Rate:</b>	
Frac and Acid service treatments designed with intent to increase production on newly drilled or existing wells are not taxable.		<b>Sale Tax:</b>	<b>\$ -</b>
		<b>Total:</b>	<b>\$ 2,562.73</b>

X \_\_\_\_\_  
CUSTOMER AUTHORIZED AGENT

Date of Service: **3/12/2015**  
 HSI Representative: **Dwayne**  
 Customer Representative: **Denny**

**Customer Comments or Concerns:**

Hurricane Services appreciates any Comments, Concerns or Criticism's from our valuable customers as Safety and Customer Satisfaction are our Number 1 goal. All Comments are confidential and will be used in a constructive manner to improve our Safety and Job Performance.