

# Sun Drilling Co., Inc.

P.O. Box 54  
 Ploua, Kansas 66761  
 Office: (316) 468-2510

Well No. #18	Farm Pancana	Gordon	Producer	Kanalta Resources Ltd.		
Location	SE ¼ 1280 FSL	2475 FEL	Sec.	13	Twp.	24 Rg 15 E
Elevation			State	Kansas	County	Woodson
Kind (Oil, Gas, Water, Dry Hole)	Oil		Contractor	Sun Drilling Co., Inc.		
Producing Formation	Top	Bottom				

Producing Formation	Top	Bottom
0-1	Soil	
1-22	Clay	
22-27	Clay & Sandstone	
27-83	Shale	
83-86	Lime	
86-272	Shale	
272-292	Lime w/ Shale St.	
292-314	Shale	
314-328	Lime w/ Shale St.	
328-471	Lime	
471-492	Lime w/ Shale St.	
492-549	White Sandy Lime	
549-554	Black Shale	
554-605	Shale	
605-615	Lime w/ Shale St.	
615-661	Lime Sandy	
661-682	Lime	
682-689	Black Shale	
689-742	Lime	
742-894	Big Shale	
894-930	Lime w/ Shale St.	
930-988	Sandy Shale	
988-1026	Lime w/ Shale St.	
1026-1029	Black Shale	
1029-1044	Shale	
1044-1065	Lime 20 Ft.	
1065-1069	Black Shale	
1069-1074	Lime 5 Ft.	
1074-1078	Shale	
1078-1091	Sand Show of Oil	
1091-1118	Shale	
1118-1119	Cap Rock	
1119-1121	Shale	
1121-1122	Cap Rock	
1122-1129½	Sand Good Show of Oil	
1129½-1185	Shale	
T.D.-1185		

Set 83 ft. of surface pipe 6 5/8  
 On 5-13-83  
Cement with 20 sacks of portland  
 Under Surface pipe on 5-16-83  
 Core #1 From Top 1118 to Top 1135  
 Ran 1177.45 of 2 7/8 pipe  
 Seating Niple @ 1119 ft.