

Bar Drilling, LLC

INVOICE

1317 105th Rd
Yates Center, KS 66783
(719) 210-8806, (620) 625-3679

DATE: June 30, 2015
INVOICE #

BILL TO:
Colt Energy Inc.
P.O. Box 388
Iola, KS 66749

FOR: Allen 11-I
API# 15-207-29223

15-207-29223

DESCRIPTION	Quantity	RATE	AMOUNT
set 42.5' of 8 5/8" surface casing with 14 sacks of cement		included	
drilled 1382', (6 3/4" hole)	1.00	10125.00	10,125.00
core: 1	1.00	included	
APPROVED JA 7/6/2015			
SUBTOTAL			\$ 10,125.00
TAX RATE			
SALES TAX			-
OTHER			
TOTAL			\$ 10,125.00

THANK YOU FOR YOUR BUSINESS!

Mud Rotary Drilling
 Andrew King - Manager/Driller

Bar Drilling, LLC
 Phone: (719) 210-8806

1317 105th Rd.
 Yates Center, KS 66783

Company/Operator Colt Energy Inc. P O Box 388 Iola, KS 66749		Well No. 11-1	Lease Name Allen	Well Location 360'±sl, 2150'±el	1/4 NW	1/4 SW	1/4 SW	Sec. 14	Twp. 26s	Rge. 14e	
Job/Project Name/No.		Well API # 15-207-29223	Type/Well Oil	County Woodson	State KS	Total Depth 1382'	Date Started 5/27/2015	Date Completed 6/2/2015			
Surface Record											
Driller/Crew Andy King Charles King	Bit Size: Casing Size: Casing Length: Cement Used: Cement Type:	11 1/4 8 5/8 42.5 14sx Portland	Type PDC PDC	Size 11 1/4 6 3/4	From 0' 42.5'	To 42.5' 1382'	Core # 1	Size 3"	From 1261	To 1283	% Rec. 35

Formation Record			Formation Record			Coring Record		
From	To	Formation	From	To	Formation	From	To	Formation
0	18	overburden	1065	1112	sandy shale			
18	184	shale	1112	1113	lime			
184	445	lime	1113	1189	shale			
445	525	shale	1189	1190	lime			
525	662	lime	1190	1258	shale			
662	665	shale	1258	1261	oil sand			
665	681	lime	1261	1283	Core #1			
681	684	shale	1283	1348	sandy shale			
684	694	lime	1348	1370	shale			
694	812	shale	1370	1379	soft shale			
812	817	lime	1379	1382	miss lime			
817	844	sandy shale						
844	944	lime						
944	950	sandy shale						
950	974	shale						
974	979	lime						
979	1001	shale						
1001	1019	sandy shale						
1019	1025	Ft Scott Lime						
1025	1031	shale						
1031	1044	lime						
1044	1045	shale						
1045	1059	lime						
1059	1065	sandy shale						

Well Notes:
 ran 1348' +/- of 4 1/2" casing.

11M
06-01-64S

235'

270'

371'

675' end of strip

699' end of KC
704'

755'

807'

800'

804'

800'

711'

710'

674'

605'

582'

516' end of Pt