





**CONSOLIDATED**  
Oil Well Services, LLC

**ENTERED**

TICKET NUMBER 43351

LOCATION Eureka

FOREMAN Kevin McCoy

Shannon Feck

**FIELD TICKET & TREATMENT REPORT**

CEMENT API # 15-197-20299

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
7-30-13	4027	WAUGH B #3	18	155	12E	WHAUNSEE
CUSTOMER			TRUCK #		DRIVER	
John O. Farmer			515		Merle R.	
MAILING ADDRESS			445		Dave G.	
P.O. Box 352						
CITY	STATE	ZIP CODE				
Russell	Ks	67665				

JOB TYPE Longstring 0 HOLE SIZE 7 7/8 HOLE DEPTH 3110' K.B. CASING SIZE & WEIGHT 5 1/2 15.50 new  
 CASING DEPTH 3103 K.B. DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
 SLURRY WEIGHT 13.6 SLURRY VOL 40 BBL WATER gal/sk 9.0 CEMENT LEFT in CASING 14'  
 DISPLACEMENT 75.8 BBL DISPLACEMENT PSI 700 PSI 1100 Bump Plug RATE 5 BPM

REMARKS: Safety Meeting: Rig up to 5 1/2 casing w/ Rotating Swivel & Cement Head. BREAK  
Circulation w/ 5 BBL fresh water. Pump 12 BBL (500 gals) Silt Suspender Pre-Flush, 10 BBL KCL  
water spacer, 5 BBL fresh water. MIXED 120 SKS THICK SET Cement w/ 5\* KOL-SEAL /SK @ 13.6  
9AL, yield 1.85, wash out Pump & Lines. Shut down. Release Latch down Plug. Displace Plug to  
SEAT w/ 75.8 BBL fresh water. FINAL Pumping Pressure 700 PSI. Bump Plug to 1100 PSI, wait 2  
Mins. Release Pressure. Float & Plug Held. Good Circulation @ ALL times while Cementing. Rotated  
Casing. Plug RAT Hole w/ 30 SKS. Job Complete. Rig down.

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE	1085.00	1085.00
5406	70	MILEAGE	4.20	294.00
1126 A	150 SKS	THICK SET Cement	20.16	3024.00
1110 A	750 *	KOL-SEAL 5*/SK	.46	345.00
5407 A	8.25 TONS	70 miles Bulk Delv.	1.41	814.27
1143	2 946	Silt Suspender Pre-Flush	42.42	84.84
1142	2 946	KCL	35.18	70.36
4203	1	5 1/2 Guide Shoe	168.00	168.00
4228 B	1	5 1/2 AFU INSERT FV	180.75	180.75
4104	1	5 1/2 Cement Basket	240.00	240.00
4130	6	5 1/2 Centralizers	50.50	303.00
4454	1	5 1/2 Latch down Plug	266.75	266.75
5611	1	Rental on 5 1/2 Rotating Swivel	100.00	100.00
Sub Total				6975.98
SALES TAX 7.65%				358.23
ESTIMATED TOTAL				7334.21

THANK YOU 061054

Revin 3737

AUTHORIZATION Ann Weasley TITLE \_\_\_\_\_ DATE \_\_\_\_\_  
 I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.