



Cement Report

Customer <i>Merit Energy</i>	Lease No.	Date <i>7-28-15</i>
Lease <i>Andrews</i>	Well # <i>17.2</i>	Service Receipt <i>1717 05462A</i>
Casing <i>5 1/2" 17#</i>	Depth <i>5655.46 ft</i>	County <i>Haskell</i>
Job Type <i>242 Production</i>	Formation	State <i>Ks.</i>
Legal Description <i>17 30 32</i>		

Pipe Data		Perforating Data		Cement Data
Casing size <i>5 1/2" 17#</i>	Tubing Size	Shots/Ft		Lead
Depth <i>5655.46ft</i>	Depth	From	To	
Volume <i>130.1</i>	Volume	From	To	
Max Press <i>2800</i>	Max Press	From	To	Tail in 50/50 Poz <i>277sk</i>
Well Connection <i>P.C.</i>	Annulus Vol.	From	To	
Plug Depth <i>5610.86ft.</i>	Packer Depth	From	To	<i>1.58⁵⁰/_{sk} 7.36⁵⁰/_{sk}</i>

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
<i>11:15</i>					<i>Call Out</i>
<i>14:15</i>					<i>On Location</i>
<i>14:30</i>					<i>Safety Meeting w/ BES personnel</i>
<i>14:45</i>					<i>Wait on Rig</i>
<i>15:30</i>					<i>Rig Up</i>
<i>15:45</i>					<i>Rig Up Head</i>
<i>16:05</i>					<i>Safety Meeting w/ Rig Crew</i>
<i>16:10</i>					<i>Pressure Test to 2800</i>
<i>16:15</i>	<i>50</i>		<i>77.94bbl</i>	<i>5.0</i>	<i>Pump Tail</i>
<i>16:35</i>					<i>Shutdown wash pump</i>
<i>16:40</i>	<i>50</i>		<i>10</i>	<i>6.0</i>	<i>Drop Plug, Displace</i>
	<i>50</i>		<i>20</i>	<i>6.0</i>	
	<i>50</i>		<i>30</i>	<i>6.0</i>	
	<i>50</i>		<i>40</i>	<i>6.0</i>	
	<i>50</i>		<i>50</i>	<i>6.0</i>	
	<i>100</i>		<i>60</i>	<i>5.0</i>	<i>Slow rate</i>
	<i>280</i>		<i>70</i>	<i>5.0</i>	
	<i>500</i>		<i>80</i>	<i>4.9</i>	
	<i>680</i>		<i>90</i>	<i>4.6</i>	
	<i>900</i>		<i>100</i>	<i>4.5</i>	
	<i>1100</i>		<i>110</i>	<i>4.0</i>	
	<i>1180</i>		<i>120</i>	<i>2.0</i>	
<i>17:15</i>	<i>1550</i>		<i>130.1</i>	<i>0</i>	<i>Land Plug wait 5min. Release Back Float Held</i>

Service Units	<i>78938</i>	<i>38117/15919</i>	<i>38111/37724</i>	Job Complete
Driver Names	<i>Daniel</i>	<i>Carlos</i>	<i>Santiago</i>	

Early Zion
Customer Representative

Tyce Davis
Station Manager

Daniel Beck
Cementer