



BASICSM
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

10244 NE Hwy. 61
P.O. Box 8613
Pratt, Kansas 67124
Phone 620-672-1201

FIELD SERVICE TICKET
1718 09140 A

10-225-14W

DATE _____ TICKET NO. _____

DATE OF JOB: 10-4-13	DISTRICT: Pratt, Kansas	NEW WELL <input type="checkbox"/>	OLD WELL <input type="checkbox"/>	PROD <input type="checkbox"/>	INJ <input type="checkbox"/>	WDW <input type="checkbox"/>	CUSTOMER ORDER NO.:		
CUSTOMER: F.G. Hill Company, LLC	LEASE: Krupp	WELL NO. 3-10							
ADDRESS:	COUNTY: Stafford	STATE: Kansas							
CITY:	STATE:	SERVICE CREW: C. M. Smith, M. McGraw, H. Boller							
AUTHORIZED BY:	JOB TYPE: NW - Surface								
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	AM/PM	TIME
38210	1.25						10-4-13	AM	7:30
						ARRIVED AT JOB		AM	10:45
						START OPERATION		AM	12:00
77696-19905	1.25					FINISH OPERATION		AM	1:15
						RELEASED	10-4-13	AM	1:30
78918-19362	1.25					MILES FROM STATION TO WELL			50

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: [Signature]
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CP101	A cov Blend Cement	sh	190	\$	
CP100C	Common Cement	sh	190	\$	
CC102	Cellflake	Lb	95	\$	
CC104	Calcium Chloride	Lb	895	\$	
CF105	Top Rubber Plug, 8 9/8"	ea	1	\$	
CF1753	Centralizer, 8 9/8"	ea	3	\$	
ET100	Pickup Mileage	mi	50	\$	
E101	Heavy Equipment Mileage	mi	100	\$	
E113	Bulk Delivery	tm	895	\$	
CE201	Cement Pump, 500 Feet To 1000 Feet	hrs	4	\$	
CE240	Blending and Mixing Service	sh	330	\$	
CE504	Plug Container	Job	1	\$	
S003	Service Supervisor	hrs	8	\$	

SUB TOTAL

16.97

CHEMICAL / ACID DATA:			

SERVICE & EQUIPMENT	%TAX ON \$
MATERIALS	%TAX ON \$

TOTAL

SERVICE REPRESENTATIVE: R. M. Smith

THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: [Signature]

(WELL OWNER OPERATOR CONTRACTOR OR AGENT)

FIELD SERVICE ORDER NO.

Customer F.G. Holt Company, LLC	Lease No.	Date 10-4-13
Lease Krupp	Well # 3-10	
Field Order # 9140	Station Pratt, Kansas	Casing 23lb
Type Job C.N.W. - Surface	Depth 842 Ft.	County Stafford
	Formation	State Kansas
		Legal Description 10-225-14W

PIPE DATA		PERFORATING DATA		CEMENT USED	TREATMENT RESUME		
Casing Size 23lb	Tubing Size 23lb	Shots/Ft 190sacks	From	To	RATE	PRESS	ISIP
Depth 842 Feet	Depth 842 Feet	From	From	To	Max 2.47 CU. Gall/1st.	2.25	15.7 st cell plate
Volume 54 Bbl.	Volume	From	From	To	Min 1.20 CU. Gall/1st.		10 Min. cell plate
Max Press 350 PSI	Max Press	From	From	To	Avg 2.23 Gall/1st.	1.20 CU. FT/1st.	15 Min.
Well Connection Plug Control	Annulus Vol.	From	From	To	HHP Used		Annulus Pressure
Plug Depth 842 Feet	Packer Depth	From	From	To	Flush 53 Bbl. Fresh Water	Gas Volume	Total Load

Customer Representative Steve Stephens	Station Manager Kevin Gordley	Treater Clarence R. Messich
---	----------------------------------	--------------------------------

Service Units	37216	77686	19905	78918	19862				
Driver Names	Messich	McGraw	Boyer						

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
10:15					Trucks on location and hold safety meeting.
11:00					Drill start to run 8 joints new 23lb/ft 8 5/8" casing.
11:55					Casing in well. Circulate for 5 minutes.
12:05	300			5	Start Fresh water Pre-Flush.
	300		10	6	Start mixing 190sacks A-con cement.
	250		93	5	Start mixing 190sacks common cement.
	-0-		133		Stop pumping. Shut in well. Release Top Rubber Plug. Open Well.
12:27	150			5	Start Fresh water Displacement.
12:40	350		53		Plug down Shut in well.
					circulated 15 Bbl cement to pit
					Wash up pump truck.
1:15					Job Complete.
					Thank You.
					Clarence, Mike, Huchelberry