



BASICSM
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

10244 NE Hwy. 61
P.O. Box 8613
Pratt, Kansas 67124
Phone 620-672-1201

FIELD SERVICE TICKET

1718 08722 A

10-215-14W

DATE _____ TICKET NO. _____

DATE OF JOB	9-14-13	DISTRICT	Pratt, Kansas	NEW WELL <input type="checkbox"/>	OLD WELL <input type="checkbox"/>	PROD <input type="checkbox"/>	INJ <input type="checkbox"/>	WDW <input type="checkbox"/>	CUSTOMER ORDER NO.:	
CUSTOMER	F G Hall Company LLC			LEASE	Anshutz B				WELL NO.	10
ADDRESS				COUNTY	Stafford		STATE	Kansas		
CITY				STATE						
AUTHORIZED BY				SERVICE CREW	C Messick M McGraw D Hye					
				JOB TYPE:	C.U.W. Surface					
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	AM	PM	TIME
37216							9-13-13			5:30
						ARRIVED AT JOB	9-14-13			
						START OPERATION				11
						FINISH OPERATION				2:00
						RELEASED				3:45
						MILES FROM STATION TO WELL				50

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: Don Vazquez
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CF 101	Acad Blend Cement	sh	190		
CF 100	Common Cement	sh	190		
CF 102	Cellulose	Lb	95		
CF 103	Calcium Chloride	Lb	895		
CF 105	Top Rubber Plug, 8 7/8"	ea	1		
CF 1753	Centralizer, 3 7/8"	ea	3		
E 100	Packing Mixture	ml	150		
E 101	Heavy Equipment Mixture	ml	100		
E 113	Bulk Delivery	hr	895		
CE 201	Cement Pump: 500 Feet To 1000 Feet	hrs	4		
CE 240	Blending and Mixing Service	sh	330		
CE 504	Plug Container	tbl	1		
S 003	Service Supervisor	hrs	8		

SUB-TOTAL

CHEMICAL / ACID DATA:			

SERVICE & EQUIPMENT	% TAX ON \$	
MATERIALS	% TAX ON \$	
		TOTAL

SERVICE REPRESENTATIVE R. Messick

THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: Don Vazquez

(WELL OWNER OPERATOR CONTRACTOR OR AGENT)

FIELD SERVICE ORDER NO.



ASIC Energy Services, L.P.

TREATMENT REPORT

Customer	G. Hall Company, LLC	Lease No.		Date	9-14-13
Lease	Anschutz "B"	Well #	1-10		
Field Order #	8722	Station	Pratt, Kansas	Casing	8 7/8 24" Depth 851 Feet
Type Job	C.N.W. - Surface	Formation		County	Stafford
				State	Kansas
				Legal Description	10-215-14W

PIPE DATA		PERFORATING DATA		CEMENT USED		TREATMENT RESUME		
Casing Size	8 7/8 24" Lb. Ft.	Shots/Ft	190 sacks	CEMENT	5 A-con with 38	RATE	PRESS	ISIP
Depth	851 Feet	From	To		12 Lb./Gal.	Max	14.49 Gal./Stk.	5 Min.
Volume	54 Bbl.	From	To		90 sacks common cement with 28	Min	10 Min.	10 Min.
Max Press		From	To		15.6 Lb./Gal.	Avg	3.23 Gal./Stk.	15 Min.
Well Connection	Annulus Vol.	From	To			HHP Used		Annulus Pressure
Plug Depth	Packer Depth	From	To	Flush	53 Bbl. Fresh Water	Gas Volume		Total Load

Customer Representative	Dean	Station Manager	Kevin Gordley	Treater	Clarence R. Messick	
Service Units	37216	19959	19905	70959	19918	2790
Driver Names	Messick	Mc Graw	Phye	Gulhaad		

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
10:00					Truckson location and hold safety meeting.
					Drilling start for run 20 To ints new 24 Lb./Ft 8 7/8 casing.
					A centralizer was installed on collars # 1, 10, 19.
12:55					Casing in well. Circulate for 5 minutes.
1:19	200			5	Start Fresh water pre-flush.
			10	6	Start mixing 190sacks A-con Blend cement.
			93	5	Start mixing 190sacks common cement.
	-0-		136		Stop pumping. Shut in well. Release Top Rubber Plug. Open well.
	150			5	Start Fresh water Displacement.
2:00			53		Plug down. Shut in well.
					circulated 20 Bbl. and Pit
					JOB complete

Thank you